

Deliverable 1.2

PORTFOLIOS



Project details			
Project acronym	NICE	Start / Duration	01/06/2021 48 months
Topic	SC5-27-2020	Call identifier	H2020-SC5-2020-2
Type of Action	RIA	Coordinator	CETIM
Contact persons	Daiane Trevisan– dtrevisan@cetim.es		
Website	www.nice-nbs.eu		

Deliverable details			
Number	D.1.2		
Title	Comprehensive portfolio of innovative NBS 1		
Work Package	WP1		
Dissemination level	CO	Nature	Report
Due date (M)	M35	Submission date (M)	M35
Deliverable responsible	GUT	Contact persons	Katarzyna Kolečka

Deliverable Contributors				
	Name	Organisation	Role / Title	E-mail
Deliverable leader	Magdalena Gajewska	GUT	Leader/Professor	mgaj@pg.edu.pl
Authors	Magdalena Gajewska	GUT	Leader/Professor	mgaj@pg.edu.pl
	Katarzyna Kolečka		Assistant/Professor	katkolec@pg.edu.pl
	Karolina Fitobór		Assistant/Assoc Prof.	karfitob@pg.edu.pl
	Magda Kasprzyk		Assistant/Assoc Prof.	magkaspr@pg.edu.pl
Final review and quality approval				

Document History			
Date	Version	Name	Changes
19.04.2024	0.1	D.1.2. Portfolio	Uploaded
05.05.2024	0.2	Comments to D1.2.	Uploaded
15.07.2024	0.3	Corrected -D.1.2 v 3	Uploaded

Abbreviations

DAFAST	Dissolved Air Flotation Unit
FRB	French Reed Bed
FWS-TW	Free Water System Treatment Wetland
HDPE	High-density polyethylene
HFTW	Horizontal Flow Treatment Wetland
HRAP	High Rate Algae Pond
HRT	Hydraulic Residence Time
HSSF	Horizontal Subsurface Flow Treatment Wetland
NBS	Nature Based Solution
NH₄-N	Ammonium Nitrogen
PE	Personal Equivalent
PO₄-P	Orthophosphate
PVC	Polyvinyl Chloride
RBF	Reed Bed Filters
TKN	Total Kjeldahl Nitrogen
TN	Total Nitrogen
TP	Total Phosphorus
TSS	Total Suspended Solids
TW	Treatment Wetland
VF	Vertical Flow
VFRB	Vertical French Reed Bed
VFTW	Vertical Flow Treatment Wetland
VRBF	Vertical Reed Bed Filters
VSSF	Vertical Subsurface Flow Treatment Wetland
WWTP	Wastewater Treatment Plant
STRB	Sludge Treatment Reed Beds



www.nice-nbs.eu

PORTFOLIO PREFACE



This project has received funding from the European Union's Horizon 2020 research and innovation programme under grant agreement No 101003765.

WHY WE ELABORATE PORTFOLIO:

Extensive research carried out over the recent decades indicates that the globe's freshwater resources are limited, and human activity contributes to their further degradation and impoverishment.

Additionally, rapid climate change caused by human activity results in unexpected events such as uneven distribution of precipitation causing torrential rains and their consequences, i.e. flash floods or long periods of no rainfall causing droughts.

The consequences of these changes are becoming more and more felt, both in urban and rural areas. Thus saving water and treatment of various types of wastewater to recycle its use or retention, becomes a top priority of water and wastewater management. Currently available technologies of purification, allow to remove variety, almost all, of contaminants from wastewater. However, the basic limitation is the necessary energy input and connected carbon and water footprint and thus associated treatment costs.

Due to rising energy prices, especially in the last two decades, low-energy technologies are gaining popularity and importance. In addition, the adoption by the EU of the circular economy rewards technologies such as nature-based solutions (NBS) in water protection and recovery. The European Commission describes them as "Nature-inspired and nature-supported solutions that are economical, offer environmental, social, and economic advantages, and contribute to resilience. These solutions introduce a greater variety of natural elements and processes into urban areas, landscapes, and marine environments through interventions that are locally tailored, resource-efficient, and systemic. Therefore, nature-based solutions must enhance biodiversity and support the provision of various ecosystem services. The advantage of NBS, apart from the low energy consumption is their low emissivity. Characteristic is no secondary sludge production during treatment wastewater, and it is possible to design systems with "0-emission" or even with additional production, e.g. biomass (for energy purposes) or water production for different urban purposes.

It should be underlined that NBS also perfectly fulfills four functions of ecosystems: supply (clean water and biomass), supporting (biodiversity, habitat creation, support for water circulation and matter and others), regulatory (regulation of flooding, temperature, water production) and cultural (recreation, education, aesthetics).

Therefore, NBSs are not only an alternative to conventional ones such as e.g. the activated sludge method but a solution providing undeniable benefits.

So far, the primary argument against the widespread use of the NBSs was their high-level space requirements, in comparison with conventional systems. In many cases, this is not a real limitation, all the more so because it can use different combinations of NBSs, which are characterized by lower demand for space. At the same time, the space dedicated to NBS should be treated as a type of compensation for a degraded environment providing ecosystem service.

Now is the time to provide you with the definition. One of them given by EC is "Solutions that are inspired and supported by nature, which are cost-effective, simultaneously provide environmental, social and economic benefits and help build resilience. Such solutions bring more, and more diverse, nature and natural

features and processes into cities, landscapes, and seascapes, through locally adapted, resource-efficient and systemic interventions.”¹

In the NICE portfolio, You will be provided with such information as main dedication, some technical data about construction and operation, the location of the facility, or its ecological potential.

On the next few pages, instructions about graphics dedicated to different types of treated mediums, as well as ecosystem service and urban circularity challenges will be provided.

¹ https://research-and-innovation.ec.europa.eu/research-area/environment/nature-based-solutions_pl

GRAPHICAL GUIDE OF PORTFOLIO:

The font and color used in the portfolio are as suggested in the NICE Style guide. The first step of creating the portfolio was choosing background colors for the different types of treated media. The backgrounds are derivatives of the original color scheme depending of the media colour. Next step consisted of choosing the correct icons from the Flowchart. The icons are placed on the front page of the portfolio for easy recognition of the type of NBS. There are 8 categories and they present in Table 1.







Icons are also placed on the top part of the portfolio for facilities such as rain gardens, green roofs, and vegetated walls (Table 2).

Table 1. Type of medium with corresponding portfolio colour

Type	Colour
NBS for greywater	
NBS for industrial wastewater	
NBS for domestic wastewater	
NBS for surface water	
NBS for stormwater (surface)	
NBS for stormwater (rainfall)	
NBS for landfill leachate	
NBS for sewage sludge	

Table 2. Different types of NBS with corresponding portfolio icons

Type of NBS	Icon
Horizontal Subsurface Flow Treatment Wetland (HSSF), Vertical Subsurface Flow Treatment Wetland (VSSF), Free Water Surface Treatment Wetland (FWS-TW), Hybrid Treatment Wetland (HTW),	

<p>French Reed Bed (FRB), Aerated Treatment Wetland, High Rate Algal Pond (HRAP), One-stage Treatment Wetland, Treatment Wetland (TW), Floating Treatment Wetland (FTW), Floating Wetland Island (FWI), Sewage Sludge Treatment Reed Bed (STRB), Bioremediation Cells</p>	
<p>Green Roofs (GR)</p>	
<p>Living walls/green walls (LW/GW)</p>	
<p>Rain garden (RG)</p>	
<p>In-stream restoration (buffer zones), Water storage systems (reservoir)</p>	
<p>NBS with ensure reuse of treated medium</p>	

The first page consists of basics including a short description and information such as construction year, costs, and operators as well as a table with ecosystem service provided by the NBS. Moreover, location and climate information can be found there, according to World Map Koppen-Geiger Climate Classification (Figure 1). A few pictures of the facility are placed on the front page.




Figure 1. World Map of Köppen-Geiger climate classification².

The back page of the portfolio consists of more technical data. The disadvantages and advantages of the particular object can be found there. A section was also devoted to ecological potential - how the facility helps improve the ecological situation of the area. The back page has a designated spot for technical drawings. If none are available, more pictures are placed there. Information about the European framework and author is placed on the back page of the portfolio.

² Kottek, M., Grieser, J., Beck, C., Rudolf, B., & Rubel, F. (2006). World Map of the Köppen-Geiger climate classification updated. *Meteorologische Zeitschrift*, 15(3), 259–263. DOI: 10.1127/0941-2948/2006/0130

ECOSYSTEM SERVICES:

Ecosystem services are the benefits people obtain from ecosystems. These include provisioning services such as food and water; regulating services such as flood and disease control; cultural services such as spiritual, recreational, and cultural benefits; and supporting services, such as nutrient cycling, that maintain the conditions for life on Earth³.

With the publication of the Millennium Ecosystem Assessment (2005) came an alternative categorization for ecosystem services, whereby the services are described as being provisioning, regulating, cultural, and supporting (Table 3). Thus according to the definition given by EC cited on the first page: "Nature-based solutions must therefore benefit biodiversity and support the delivery of a range of ecosystem services".

Table 3. Categories and examples of ecosystem services^{4 5 6}

Ecosystem service	Provisioning	Regulating	Cultural	Supporting
item	☆ food	☆ climate	☆ educational	☆ nutrient cycling
	☆ raw materials	☆ air quality	☆ spiritual	☆ soil formation
	☆ fresh water	☆ water runoff	☆ aesthetic	☆ habitat provision
	☆ fuel	☆ treatment and processing	☆ recreational	☆ water cycling
	☆ medicine	☆ pollination	☆ health	☆ primary production
summary value	☆☆☆☆☆	☆☆☆☆☆	☆☆☆☆☆	☆☆☆☆☆

For each object presented in portfolio an individual assessment of ecosystem services was elaborate (Table 4).

Table 4. Example ecosystem services assessment for constructed wetland for domestic wastewater in Lesvos (HYDROUSA project)

Ecosystem services			
Provisioning	Regulating	Cultural	Supporting
☆☆	☆☆☆☆	☆☆☆	☆☆☆☆☆

If the ecosystem services for particular wetland does not occur, the "-" sign is used.

³ <https://www.millenniumassessment.org/documents/document.300.aspx.pdf>

⁴ <https://www.greenelement.co.uk/blog/ecosystem-services-the-fundamentals-part-i/>

⁵ <https://www.earthwiseaware.org/what-are-ecosystem-services/>

⁶ <https://www.integrallc.com/recent-developments-ecosystem-services/>

NBS IN CIRCULARITY:

In the contrast to linear management of resources (water, food, materials, energy) the circular economy (CE) model is proposed in 2015 by EU, provides economic growth without increasing the consumption of new resources and reducing the impact on the environment⁷.

Multifunctionality makes NBS an important concept for cities to achieve resource management according to the CE principles.

The concept, relating urban challenges with NBS, was developed within the COST Action CA17133 Circular City investigating the hypothesis that 'A circular flow system that implements NBS for managing nutrients and resources within the urban biosphere will lead to a resilient, sustainable and healthy urban environment'.⁸

The following Urban Circularity Challenges (UCCs) for shifting to circular management of resources can be addressed with NBS have been defined 7 UCC and shown in Figure 2 and Table 5^{7, 8, 9}:






Figure 2. Urban circularity challenges for shifting to circular management of resources that can be addressed with NBS⁷

⁷ Atanasova, N., Castellar, J.A.C., Pineda-Martos, R., Nika, C.E., Katsou, E., Istenič, D., Pucher, B., Andreucci, M.B., Langergraber, G., 2021. Nature-based solutions and circularity in cities. *Circ. Econ. Sustain.* 1, 319–332. <https://doi.org/10.1007/s43615-021-00024-1>.

⁸ Langergraber, G., Pucher, B., Simperler, L., Kisser, J., Katsou, E., Buehler, D., ... & Atanasova, N. (2020). Implementing nature-based solutions for creating a resourceful circular city. *Blue-Green Systems*, 2(1), 173-185. <https://doi.org/10.2166/bgs.2020.933>








⁹ Kasprzyk M., Szpakowski W., Poznańska E., Boogaard F.C., Bobkowska K., Gajewska M., 2022. Technical solutions and benefits of introducing rain gardens – Gdańsk case study, *Science of The Total Environment*, 835, 155487, <https://doi.org/10.1016/j.scitotenv.2022.155487>.

Table 5. Descriptions of challenges related to urban circularity and the role of NBS^{7, 8, 9}

	URBAN CIRCULARITY CHALLENGES	
Role of NBS	 - connection of UCC with particular facility  - lack of connection	
	UCC ₁	restoring and maintaining the water cycle
	UCC ₂	water and waste treatment, recovery, and reuse
	UCC ₃	nutrient recovery and reuse
	UCC ₄	material recovery and reuse
	UCC ₅	food and biomass production
	UCC ₆	energy efficiency and recovery
	UCC ₇	building system recovery

For each object presented in portfolio an individual assessment of urban circularity challenges was elaborated (Table 6).

Table 6. Exemplary assessment of urban circularity challenges for constructed wetland for domestic wastewater in Lesvos (HYDROUSA project)

URBAN CIRCULARITY CHALLENGES						
UCC1	UCC2	UCC3	UCC4	UCC5	UCC6	UCC7
						



www.nice-nbs.eu

PORTFOLIO



This project has received funding from the European Union's Horizon 2020 research and innovation programme under grant agreement No 101003765.

The 28 cases was found for domestic wastewater, 17 for industrial wastewater, 2 for greywater + storm water, 8 for direct of rainfall, 18 for surface runoff, 4 for surface water, 5 for sewage sludge, 5 for landfill leachate and reject water, 4 for combined sewer overflow.

Medium category	Object	Location
Domestic wastewater	Horizontal Subsurface Flow Treatment Wetland (HSSF)	1. Stężycza 2. Gorgona 3. Candidoni
	Vertical Subsurface Flow Treatment Wetland (VSSF)	1. Bolwerk 2. Mykonos 3. Lesvos
	Free Water Surface Treatment Wetland (FWS-TW)	1. Eskiltuna 2. Hasseleholmsvatten 3. Caraglio
	Hybrid Treatment Wetland (HTW)	1. Kniewo 2. Borucin / Łączyń 3. Almeria 4. Agramon 5. Chiuso Di Pesio 6. Jesi 7. Jougar 8. Casteluccio Di Norcia 9. Chorfech 10. Del Mar 11. Haderselev
	French Reed Bed (FRB)	1. Ohrei 2. Macouria 3. Les Halles 4. Misilya Jarba
	Aerated Treatment Wetland	1. Tarcenay 2. Bas-en-Basset
	High Rate Algal Pond (HRAP)	1. Chiclana de la Frontera 2. Merida
Industrial wastewater	Hybrid Treatment Wetland (HTW)	1. Nimr 2. Embetsu 3. Castellina in Chianti 4. Bolgheri 5. Santa Tome 6. New Boston
	One-stage Treatment Wetland	1. Vidigueira
	Aerated Treatment Wetland	1. San Rocoo di Piegara

	Bioremediation Cells	1. Riyadh
	Floating Treatment Wetland (FTW)	1. Sialkot
	Green roofs (GR)	1. Makandusi 2. Oregon 3. Richmond
	Living walls/green walls (LW/GW)	1. Beirut 2. Ferla 3. Amman 4. Marina di Ragusa
Greywater + stormwater	Green walls (GW) and green garden and green roof (GR)	1. Buffalo
	Hybrid Treatment Wetland (HTW)	1. Maharashtra
Direct of rainfall	Rain garden (RG) (basin, bioretention swale)	1. Albuquerque
	Green roofs (GR)	1. Manhattan 2. Washington 3. New York
	Living walls/green walls (LW/GW)	1. Valladolid 2. Paris 3. Kalisz (John Paul II Square) 4. Lima
Surface runoff	Rain garden (RG), green roofs (GR) (meadow, basin, bioretention swale, tree pits), Treatment Wetland (TW)	5. Copenhagen 6. Wrocław (courtyard among Jedności Narodowej, Rychtalska and Ustronie Street) 7. Wrocław 8. Wrocław (Gwiazdzista Street) 9. Kalisz (Podgórze 6 Street) 10. Gdańsk (Goszczyńskiego Street) 11. Gdańsk (9 Ugory Street) 12. Syracuse 13. Gdańsk (Kaczeńce Street)



		14. Gdańsk (3maja Street) 15. Gdańsk (O'Rourke Street) 16. Gdańsk (Stryjewskiego Street) 17. Toronto
	Water storage systems (reservoir)	1. Mściwojów
	Treatment Wetland (TW)	1. Zalenieki 2. Gidy
	Horizontal Subsurface Flow Treatment Wetland (HSSF)	1. Bogota
	Free Water Surface Treatment Wetland (FWS-TW)	1. Bologne
Surface water	Floating Wetland Island (FWI) or Floating Treatment Wetland (FTW)	1. Durham 2. Fairfax 3. London
	In-stream restoration (buffer zones)	1. Charlottesville 2. Dublin-CA 3. Aarhus 4. Aarhus
Sewage sludge	Sludge Treatment Reed Beds (STRB)	1. Gniewino 2. Al Awir 3. Helsing 4. Negrepelisse 5. Paslieres
Landfill leachate and reject water (LL and rejected water)	Treatment Wetland (TW)	1. Burnie 2. Copping 3. Tianjin 4. Sydney OP 5. Lunan Tangshan
Combined sewer overflow (CSO)	Vertical Flow Treatment Wetland (VFTW)	1. Challex 2. Gorla Maggiore
	Hybrid Treatment Wetland (HTW)	1. Carimate
	Treatment Wetland (TW)	1. Bergheim



HYBRID TREATMENT WETLAND FOR WASTEWATER TREATMENT < 50 PE



OBJECT INFORMATION

Name: 4 single family treatment wetlands with pre-filter and HSSF

Type of facility: HFW

Treated medium: domestic sewage

Description of the solution: Domestic sewage flowing from the building of the PVC sanitary sewer Ø160mm to the sedimentation tank, overflows to the pump. The sewage overflows mechanically and partially biologically in a circle of figures in a circle made of concrete. A pre-filter to which the WW is delivered periodically at an angle and evenly distributed over the filter, made in the sump. The cleaning pond is made in a trench and isolated from the ground with 1mm HDPE foil.



GEOGRAPHICAL COORDINATES

Latitude: 54° 17' 01" N

Longitude: 17° 55' 19" E

BASIC INFORMATION

Construction year: 2009

Constructor: Investor under GUT's guidance

Source of financing: Co-financed Ministry of Science and Higher Education, European Economic Agency Financial Mechanism and the Norwegian Financial Mechanism

Total cost: 2300 €

Facility operator: individuals

Maintenance cost: 250 € / year

Contact person: Magdalena Gajewska (mgaj@pg.edu.pl)

LOCATION

Country: Poland

City: Stężyca

Type of climate: Cfb

Average temperature: 8°C

Sum of precipitation: 759 mm



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
-	☆☆☆☆	☆☆☆	☆☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+	+	+	+		

TECHNICAL DATA

Area of the facility: 40m²

Volume: 24m³

Efficiency and effectiveness: removal effectiveness of the total nitrogen varied from 22.4 to 84.2% (loadings from 8.5 to 34.0 kg/ha·d) BOD removal varied from 25.6 to 99.1% (loadings from 11.2 to 115 kg/ha·d.)

Operating experience: good treatment effectiveness BOD 64.0-92.0%, TN 44.0-77.0%, TP 24.0-66.0%

ECOLOGICAL POTENTIAL

The application of TW for single-family effluent is an effective and sustainable solution for WW treatment in the rural areas. The monitoring results of the single family NBSs indicated that the one stage HSSF facilities working at the second stage of sewage treatment provided effective removal of BOD₅ and COD as well as TSS.


ADVANTAGES

1. During post-vegetation period (after two years of operations of the systems) the quality of the effluent improved significantly and in many cases meet the above mentioned requirements.

DISADVANTAGES

1. A long construction and development process (about 2 years) without full operational efficiency.

Configuration



Source: M. Gajewska



Funded by the Horizon 2020 Framework Programme of the European Union

This document was prepared as a part of NICE Project by the technical team from Gdansk University of Technology

2 STAGE HSSF FOR IRRIGATION, <500 P.E



OBJECT INFORMATION

Name: Constructed wetland for wastewater treatment and reuse on Gorgona Island

Type of facility: HSSF TW

Treated medium: urban wastewater

Description of the solution: Gorgona plant consists of a primary treatment system (grid and Imhoff tank) and of a secondary treatment system with HSSF CW disposed in two by two in parallel and followed in series by a wet grassland functioning as filter between treatment system and environment. During summer water can be taken for irrigation aims after basins 3 and 4 or after the wet grassland. The facility treats 20–80m³/day of wastewater produced by the Gorgona penitentiary, which can host up to 400 people.



GEOGRAPHICAL COORDINATES

Latitude: 43° 25' 51.50" N

Longitude: 9° 54' 13.43" E

LOCATION

Country: Italy

City: Isle of Gorgona

Type of climate: Csa

Average temperature: 15.8 °C

Sum of precipitation: 953mm

BASIC INFORMATION

Construction year: 1996

Constructor: IRIDRA

Source of financing: partially funded by the Italian Ministry of Justice

Facility operator: unskilled personnel

Total cost: 490 834 €

Maintenance cost: 2000 € annually

Contact person: Anacleto Rizzo

(rizzo@iridra.com)



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
-	☆☆☆☆	☆☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+	+	+	+		

TECHNICAL DATA

Area of the facility: 1350 m²

Volume: 1080 m³

Primary design factor: Inflow rate 20–80 m³/day; Population equivalent 400 p.e.; Population equivalent area 3.3 m²/p.e.

Efficiency and effectiveness: After 24 years of operation (from 1996 to 2020) of operation, the four horizontal subsurface flow cells were still working properly, complying with the “proper treatment” concept required by Italian law for treatment plants serving less than 2,000 p.e. (DL 152/06).

ECOLOGICAL POTENTIAL


Includes services such as nutrient cycling, primary production, soil-formation, habitat provision. These make it possible for the ecosystems to continue providing services such as food supply, flood regulation and water purification.

ADVANTAGES

1. Gorgona Island is highly appreciated as a result of the low cost and simple maintenance of the TW. Moreover, the prisoners always feel confident in reusing the treated wastewater without any concerns for safety.

DISADVANTAGES

1. The lifespan of a nature-based solution using a subsurface flow TW is often strongly affected by clogging. Guidelines and textbooks sometimes report that filling media should be refurbished after 8–10 years because of clogging.



Source: R. Bresciani et al. „Horizontal subsurface flow system for Gorgona penitentiary, Italy”

Source: K. Ćwik / Agencja – wybora.pl



Funded by the Horizon 2020 Framework
Programme of the European Union

This document was prepared as a part of
NICE Project by the technical team from
Gdansk University of Technology

TREATMENT WETLAND FOR DAIRY WASTEWATER



OBJECT INFORMATION

Name: TW for WW from agricultural cooperative firm fattoria della Piana

Type of facility: TW

Treated medium: dairy wastewater

Description of the solution: The plant is composed of diversified primary treatments, set on the basis of wastewater typology: equalization of milk production wastewater, a common three-chambered tank where all wastewaters is discharged, after which wastewaters is sent into an HF system with 4 tanks in parallel for a secondary treatment. The effluent is discharged back into Mammella Torrent creek.

BASIC INFORMATION

Construction year: 2011

Constructor: Cooperative Fattoria della Piana Agricultural firm

Facility operator: Cooperative Fattoria della Piana Agricultural firm

Total cost: 200 000€

Maintenance cost: 4000€ / year

Contact person: Anacleto Rizzo
(rizzo@iridra.com)



GEOGRAPHICAL COORDINATES

Latitude: 38° 31' 8.94" N

Longitude: 15° 58' 22.82" E

LOCATION

Country: Italy

City: Candidoni

Type of climate: Csa

Average temperature: 17.2 °C

Sum of precipitation: 607mm



Source: IRIDRA "Constructed wetland for treatment of wastewater from agricultural cooperative firm Fattoria Della Piana"



Source: fattoriadellapiana.it

Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆	☆☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+	+	+	+		

TECHNICAL DATA

Area of the facility: 2280m²

Volume: 1824 m³

Catchment: 2600000m²

Hydraulic load or HRT: On average, the daily wastewater quantity is 85m³/d. The wastewater comes from a number of sources: houses and a restaurant (maximum 12 residents and 100 restaurant users), the milk cooling plant (average 20m³/d), the dairy (20 tons per day of processed milk, which produces 20m³/d of wastewater) and milking (200 livestock, which produce 20m³/d); HRT=5.3 days.

ECOLOGICAL POTENTIAL


The dairy TW is a place, where biogas is produced, which is used to create energy. The facility purifies wastewater and air. Here, sewage with a high nutrient load is decomposed. This facility was a pilot project in which wastewater with such large differences in pH and content (fats, proteins) was treated.

ADVANTAGES

1. Utilization of wastewater for energy production at the same time treatment of wastewater.

DISADVANTAGES

1. Problems with working on wastewater with different pH levels.



Source: F. Massi et al. " Dairy Wastewater Treatment by a Horizontal Subsurface Flow Constructed Wetland in Southern Italy"



Funded by the Horizon 2020 Framework Programme of the European Union

This document was prepared as a part of NICE Project by the technical team from Gdansk University of Technology



HYBRID TREATMENT WETLAND+POND FOR < 50 PE

OBJECT INFORMATION

Name: Single family treatment hybrid

Type of facility: WWTP

Treated medium: domestic WW

Description of the solution: The adopted WW treatment technology provides for multi-stage WWTP processes in mechanical and biochemical processes. The treatment processes take place both in the mechanical part (sedimentation tank) and in the biological part (hydrophyte bed and polishing pond). The biological process of WW treatment is carried out in a single wetland bed with a VF of WW, and then it is polished in a pond.

BASIC INFORMATION

Construction year: 2009

Constructor: Investment under GUT's guidance

Source of financing: Co-financed Ministry of Science and Higher Education,

Total cost: 2300 €

Facility operator: individuals

Maintenance cost: 250 € / year

Contact person: Magdalena Gajewska
(mgaj@pg.edu.pl)



GEOGRAPHICAL COORDINATES

Latitude: 54° 16' 20" N

Longitude: 17° 55' 45" E

LOCATION

Country: Poland

City: Bolwerk

Type of climate: Cfb

Average temperature: 8°C

Sum of precipitation: 759 mm



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
-	☆☆☆☆	☆☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+	+	+	+		

TECHNICAL DATA

Area of the facility: 16 m²

Volume: 12 m³

Efficiency and effectiveness:

pollution removal efficiency - BOD₅ = 90%, COD = 85%, TN = 50%, TP = 50%

Operating experience: The wastewater treatment plant using the hydrophyte method of wastewater treatment reaches full efficiency after about 3 years of operation.

ECOLOGICAL POTENTIAL

The application of treatment wetlands for single-family effluent is an effective and sustainable solution for wastewater treatment in the rural areas. The removal of pollutants is high without using additional chemicals. In addition, this facility has low energy consumption.


ADVANTAGES

1. No formation of secondary (biological) sewage sludge.

DISADVANTAGES

1. As a result of transpiration, the amount of sewage discharged in the summer period may be significantly reduced even up to 50% of the initial volume.

Configuration



Source: M. Gajewska



Funded by the Horizon 2020 Framework Programme of the European Union

This document was prepared as a part of NICE Project by the technical team from Gdansk University of Technology

SUB-SURFACE VERTICAL FLOW BEDS FOR WASTEWATER REUSE



OBJECT INFORMATION

Name: Water cycle: the Mykonos experiment in the HYDROUSA project

Type of facility: SSVF TW

Treated medium: domestic sewage

Description of the solution: The treatment plant on the island is designed to treat wastewater so that the recovered water can be reused, for example, in the cultivation of crops. The wetland construction is designed with 4 types and consists of 4 VF. One VF has dimensions of 18,0x8,5m, which is about 150m². The entire vegetation area on the facility is 600m².



MYKONOS

BASIC INFORMATION

Construction year: 2010

Constructor: project HYDROUSA

Source of financing: Horyzont 2020 funds

Facility operator: private company

Total cost: 12 000 000 €`

Maintenance cost: 2 000-4 000 € / year

Contact person: Fabio Masi

(masi@iridra.com)

GEOGRAPHICAL COORDINATES

Latitude: 37° 26' 39" N

Longitude: 25° 22' 0.37" E

LOCATION

Country: Greece

City: Mykonos

Type of climate: Csa

Average temperature: 17.6 °C

Sum of precipitation: 739 mm



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆	☆☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+	+	+	+		

TECHNICAL DATA

Area of the facility: 850m²
Volume: 100m³
Catchment: 1630 km²
Primary design factor: 1000 PE
Hydraulic load: 100m³/day- summer,
 10m³/day - winter
Dominant plant species: *Iris*
Pseudocorus, *Scirpus Lacustris*, *Juncus*
Effusus, *Carex Acuta*, *Pharagmites*
Communis
Efficiency and effectiveness:
 BOD<10mg/l, TSS<10mg/

ECOLOGICAL POTENTIAL

The facility allows recovery of the nutrients from biomass. It also prevents eutrophication through wastewater treatment. Lastly, the purified water is reused in agriculture.

ADVANTAGES

1. The facility is able to remove 90% of pathogenic bacteria and 70% of TSS.

DISADVANTAGES

1. Poor levels of nitrogen removal.



Source: IRIDRA



Funded by the Horizon 2020 Framework
Programme of the European Union

This document was prepared as a part of
NICE Project by the technical team from
Gdansk University of Technology

SUB-SURFACE VERTICAL FLOW BEDS FOR WASTEWATER REUSE AND RESOURCE RECOVERY



OBJECT INFORMATION

Name: Water cycle: the Lesvos experiment in the HYDROUSA project

Type of facility: TW

Treated medium: domestic sewage

Description of the solution: The domestic wastewater produced by the town of Antissa is treated both to produce an effluent suitable for reuse in irrigation and to recover resources, such as nutrients and energy, that can be exploited elsewhere. The CW is designed with 4 types and consists of 4 VF beds. One VF bed has dimensions of 18,0x8,5m, which is about 150m². The entire vegetation area on the facility is 600m².



LOCATION

Country: Greece

City: Lesvos

Type of climate: Csa

Average temperature: 17.6 °C

Sum of precipitation: 739mm

GEOGRAPHICAL COORDINATES

Latitude: 39° 16' 27" N

Longitude: 26° 16' 40" E

BASIC INFORMATION

Construction year: 2010

Constructor: project HYDROUSA

Source of financing: Horyzont 2020 funds

Facility operator: HYDROUSA

Total cost: 12 000 000 €

Maintenance cost: 12 000 € / year

Contact person: Fabio Masi

masi@iridra.com



Source: F. Massi "Economia circolare nel ciclo delle acque e sicurezza alimentare: l'esperimento di lesbo nel progetto hydrousa"



Source: S. Prost-Boucle; N. Wepierre et al.. "Wastewater treatment in island locations"

Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆	☆☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+	+	+	+		

TECHNICAL DATA

Area of the facility: 950m²

Volume: 100m³

Inflow:

10 m³/d winter

100 m³/d summer

Efficiency and effectiveness:

BOD<10mg/l, TSS<10mg/

Dominant plant species: Phragmites

Australis, Typha latifolia, Iris

pseudacorus, Carex spp, Scirpus

lacustris

ECOLOGICAL POTENTIAL

This system delivers higher performance than activated sludge treatment, for less than 1/3 of the investment cost. The agri-forestry area produces more than 3 tonnes of vegetables, fruit, cereal grains and herbs per year.

ADVANTAGES

1. The facility is able to remove 90% of pathogenic bacteria and 70% of TSS.

DISADVANTAGES

1. Poor levels of nitrogen removal.



Source: F. Massi "Economia circolare nel ciclo delle acque e sicurezza alimentare: l'esperimento di lesbo nel progetto hydrousa"



Funded by the Horizon 2020 Framework Programme of the European Union

This document was prepared as a part of NICE Project by the technical team from Gdansk University of Technology

FREE WATER SYSTEM AS A TERRITORY TREATMENT



OBJECT INFORMATION

Name: Ekeby FWS TW

Type of facility: FWS-TW

Treated medium: domestic WW

Description of the solution: Ekeby wetland is situated on arable land consisting of a 5-15m layer of fine clay. The wetland area including canals is 300 000 m² and the wetland area is 280 000 m². It receives tertiary treated wastewater from the WWTP and the total volume is 300 000 m³ divided into eight ponds. The incoming water flows passively and it is distributed into a canal leading the water into five parallel ponds. The water is then collected in another distribution canal and enters subsequently three parallel ponds. Finally, the water is collected in a distribution canal and then released into the river Eskilstunaån.

BASIC INFORMATION

Construction year: 1999

Constructor: NCC

Source of financing: local funds

Total cost: 2 200 000 €

Facility operator: Eskilstuna Energi & Miljö

Maintenance cost: 19 200 € / year

Contact person: Sylvia Waara

(sylvia.waara@iridrh.se)



GEOGRAPHICAL COORDINATES

Latitude: 59° 23' 18" N

Longitude: 16° 27' 33" E

LOCATION

Country: Sweden

City: Eskilstuna

Type of climate: Cfb

Average temperature: 6.8 °C

Sum of precipitation: 626 mm



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆	☆☆	☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+	+	+			

TECHNICAL DATA

Area of the facility: 400 000m²

Volume: 300 000 m³

Primary design factor: Inflow rate 43 200 m³/day; P.E.= 108 424;

Population equivalent area 3.1 m²/ PE

Efficiency and effectiveness:

Most of the nitrogen was removed during April–October but 0–30% was also removed during November–March.

Dominant plant species: Phragmites Communis, Glyceria Maxima, Ceratophyllum Demersum

ECOLOGICAL POTENTIAL


The wetlands attract diverse bird fauna. The facility allows for eco-tourism as the paths are equipped with information boards, observation towers for bird watchers and a designated area with picnic tables. Moreover, the facility cleans sewage and air through the plant species found in Eskeby.

ADVANTAGES

1. The wetland in Eskilstuna is very cost-efficient plant for the reduction of nitrogen, phosphorus and bacteria.
2. The wetland has fairly low investment cost and operation expenses.

DISADVANTAGES

1. Plants used in the TW need about 3-4 times higher investment cost, that is 4500 - 6000 € since an external source of coal must be added, too, the running expenses will be much higher (about 10 times) than for a wetland.



Source: S. Waara



Funded by the Horizon 2020 Framework Programme of the European Union

This document was prepared as a part of NICE Project by the technical team from Gdansk University of Technology

TERTIARY WASTEWATER TREATMENT IN FREE WATER SYSTEM



OBJECT INFORMATION

Name: Magle FWS-TW

Type of facility: FWS-TW

Treated medium: domestic wastewater

Description of the solution: Magle FWS-TW was constructed in 1995 and is situated on land consisting of forest, meadow and a peat bog. Treated waste water is pumped 1.5 km to the inlet of the wetland and then flows by gravity. The water first runs into a long distribution pond, then passes through one of four parallel ponds from where it ends in a collecting pond. It passes flow metering and a sampling point and is discharged into a ditch and transported to the lake Finjasjön.

The average depth is 0.5 m, but in some places along the sides of the ponds the water depth is up to 2.5 m. The deep zones were constructed to improve denitrification and the more shallow zones designed to improve phosphorus retention and keep some areas oxygenated and vegetated.

LOCATION

Country: Sweden

City: Hassleholms

Type of climate: Cfb

Average temperature: 9.0 °C

Sum of precipitation: 652 mm

HASSELEHOLMSVATTEN



GEOGRAPHICAL COORDINATES

Latitude: 44° 15' 2" N

Longitude: 7° 49' 50" E

BASIC INFORMATION

Construction year: 1995

Constructor: Hassleholms Vatten

Source of financing: no data available

Total cost: 1 000 000€

Facility operator: Hassleholms Vatten

Maintenance cost: 22 000 € / year

Contact person: Sylvia Waara

(sylvia.waara@iridrh.se)



Source: S. Waara

Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆	☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+	+	+			

TECHNICAL DATA

Area of the facility: 90 000m²
Volume: 26 000 m³/day
Primary design factor: inflow rate- 12 000 m³/day; P.E.- 31 000; P.E. area- 9.7 m²/P.E.
Hydraulic Load: 57 mm/day
Detention Time: 7-8 days
Efficiency and effectiveness:
 The removal of total nitrogen during 1996–2009 in Magle was on average 24%, equivalent to 1,066 kg/ha/year. A slightly higher value, 30%, was obtained during 2015–2017.

ECOLOGICAL POTENTIAL


The wetlands attract diverse bird fauna. Magle is located in the outskirts of the city and has been designed to include opportunities for recreation and education. They enable inhabitants to understand the water cycle and the importance of an efficient wastewater treatment.

ADVANTAGES

1. Facility enables inhabitants to understand the water cycle and the importance of an efficient wastewater treatment.
2. For visitors, odours are rarely a problem, nor are mosquitos.

DISADVANTAGES

1. *Cladophora* cells are released, in the spring and summer, and enter the effluent, resulting in an increase of BOD₇, COD and suspended solids.



Source: S. Waara



Funded by the Horizon 2020 Framework Programme of the European Union

This document was prepared as a part of NICE Project by the technical team from Gdansk University of Technology



TREATMENT WETLAND AS TERRITARY STAGE

OBJECT INFORMATION

Name: TW for the tertiary treatment of WW from the municipality of Caraglio

Type of facility: conventional + NBS (FWS, SBR)

Treated medium: domestic wastewater

Description of the solution: The WWTP of Caraglio municipality (10 000 PE) treats the wastewater with a secondary activated sludge system (SBR). In order to guarantee a more constant removal efficiency of the WWTP under time-variable influent loads, a tertiary stage with FWS CW was designed. The FWS treats an average wastewater flow of 720 m³/day and has a surface area of 2100 m². The FWS was designed with different water depths (from 0.4 to 1.2 m), creating environments suitable for the placement of different types of vegetation.



GEOGRAPHICAL COORDINATES

Latitude: 44° 24' 56" N

Longitude: 7° 25' 54" E

LOCATION

Country: Italy

City: Caraglio

Type of climate: Cfb

Average temperature: 9.7°C

Sum of precipitation: 1635 mm

BASIC INFORMATION

Construction year: 2017

Constructor: IRIDRA

Total cost: 1 500 000 €

Facility operator: Azienda Cuneese dell'Acqua

Maintenance cost: 5 000-7 500 € / year

Contact person: Anacleto Rizzo

(rizzo@iridra.com)



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆	☆☆	☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+	+	+			

TECHNICAL DATA

Area of the facility: 2100 m²

Volume: 1050 m³

Primary design factor: 10 000 P.E.,
average daily flow rate: 720 m³/day

Efficiency and effectiveness:

Removal rates for SBR :

TSS – 94%, BOD₅ – 97%, COD – 95%,
TN – 83%, TP – 78%.

Operational experience: Reduction of
the quantity of sludge extracted from
biological reactors from 15 to 9 m² per
day.

ECOLOGICAL POTENTIAL

Potentials include: water supply
(groundwater supply, drinking and
irrigation use), use of plants present in
wetlands (e.g. raw materials for food,
cosmetics etc.), presence of free
animals such as migratory birds. It is
a great contribution to biodiversity.
Also, there is possibility of carrying out
recreational and educational activities.

ADVANTAGES

1. The facility can be utilized in rural areas
where access to land is typically better
than in urban areas.

DISADVANTAGES

1. FWS TWs are reportedly employed less
frequently due to the significant risk of
human exposure to pathogens.



Source: IRIDRA



Funded by the Horizon 2020 Framework
Programme of the European Union

This document was prepared as a part of
NICE Project by the technical team from
Gdansk University of Technology





HYBRID TREATMENT WETLAND >50 PE

OBJECT INFORMATION

Name: Hybrid treatment wetland in Kniewo

Type of facility: SSVF + SSHF

Treated medium: domestic sewage

Description of the solution: HTW was designed for 60 PE and consists of SSVF bed followed by SSHF bed. The assumed technology of the treatment wetland in Kniewo provides WW treatment in mechanical processes (sedimentation, flotation) and biochemical processes (microbiological decomposition of contaminants in oxidation and reduction processes as well as absorption and adsorption). The treatment processes take place both in the mechanical part (three chamber sedimentation tank with 3 days retention time) and in the biological part – HTW. After the HTW treated effluent is discharged to drainage system. As filling material in both beds (SSVF and SSHF) gravel of granulation 2–8 mm was used. Beds were planted with local species of common reeds (*Phragmites australis*) with density 4 pcs/m².

LOCATION

Country: Poland

City: Kniewo

Type of climate: Cfb

Average temperature: 8.7°C

Sum of precipitation: 771 mm



GEOGRAPHICAL COORDINATES

Latitude: 54° 39' 50" N

Longitude: 18° 07' 12" E

BASIC INFORMATION

Construction year: 2018

Constructor: Salesian Youth Center in Kniewo

Source of financing: private funds

Facility operator: Salesian Youth Center in Kniewo

Total cost: 10 000 €

Maintenance cost: 1 000–1 500 € / year

Contact person: Magda Kasprzyk
(magkaspr@pg.edu.pl)



Source: M. Kasprzyk

Ecosystem services

Provisioning	Regulating	Cultural	Supporting
-	☆☆☆☆	☆☆☆	☆☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+	+	+	+		

TECHNICAL DATA

Area of the facility:

VF bed - 72 m²

HF bed - 48 m²

Efficiency and effectiveness: TSS – 68%, COD – 94%, turbidity – 94%, NH₄-N – 96%, PO₄-P – 84%

Operating experience: Facility works properly. After 4 years of operation over 90% of area is cover by reed.

Dominant plant species: *Phragmites australis*

Type of substrate: gravel of granulation 2–8 mm

ECOLOGICAL POTENTIAL

Wetlands are the habitat of various plants and microorganisms, creating favorable conditions for various microbiological processes. High biodiversity is conducive to wastewater treatment processes and at the same time ensures their natural course. An additional advantage of using the technology of wetlands for wastewater treatment is the lack of secondary (biological) sewage sludge formation.

ADVANTAGES

1. Simple construction and operation process.
2. Overall low energy consumption.
3. No formation of secondary (biological) sewage sludge.

DISADVANTAGES

1. Improper construction can cause operational problems.
2. Requirement for a constant wastewater flow and usage of energy.



Source: M. Kasprzyk



Funded by the Horizon 2020 Framework Programme of the European Union

This document was prepared as a part of NICE Project by the technical team from Gdansk University of Technology

HYBRID TREATMENT WETLAND + POND

< 50 PE



OBJECT INFORMATION

Name: Single family TW in Borucin and Łączyno

Type of facility: SSVF I + SSVF II + pond

Treated medium: domestic sewage

Description of the solution: The adopted technology enables multi-stage WW treatment processes in mechanical and biochemical processes. The purification processes take place both in the mechanical and biological parts. The biological process of WW treatment is carried out in wetlands with VF, then the treated wastewater is purified in a pond. Purification in vertical beds takes place thanks to the processes of filtration, sorption, and biochemical oxidation and reduction reactions.



GEOGRAPHICAL COORDINATES

Borucin:

Latitude: 54° 17' 1" N

Longitude: 17° 58' 14" E

Łączyno:

Latitude: 54° 16' 7" N

Longitude: 18° 0' 22" E

BASIC INFORMATION

Construction year: 2009

Constructor: Investment under GUT's supervision

Source of financing: Co-financed by Ministry of Science and Higher Education,

Total cost: 2300 €

Facility operator: individuals

Maintenance cost: 250 € / year

Contact person: Magdalena Gajewska

(mgaj@pg.edu.pl)

LOCATION

Country: Poland

City: Borucin / Łączyno

Type of climate: Cfb

Average temperature: 7,9 °C

Sum of precipitation: 759 mm



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
-	☆☆☆☆	☆☆☆	☆☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+	+	+	+		

TECHNICAL DATA

Area of the facility: 18,5 m²

Volume: 15 m²

Efficiency and effectiveness:

pollution removal efficiency - BOD₅ = 90%, COD = 85%, TN = 50%, TP = 50%

Operating experience: The wastewater treatment plant using the hydrophyte method of wastewater treatment reaches full efficiency after about 3 years of operation.

ECOLOGICAL POTENTIAL

The wetland sewage treatment plant ensures waste-free management of domestic wastewater generated on the territory of an individual farm, treated sewage will be transformed into full-value fertilizer. During the growing season, they are used for irrigation of greenery.


ADVANTAGES

1. No formation of secondary (biological) sewage sludge.

DISADVANTAGES

1. As a result of transpiration, the amount of sewage discharged in the summer period may be significantly reduced even up to 50% of the initial volume.

Configuration



Source: M. Gajewska



Funded by the Horizon 2020 Framework Programme of the European Union

This document was prepared as a part of NICE Project by the technical team from Gdansk University of Technology



HIGH RATE ALGAE POND

OBJECT INFORMATION

Name: HRAP for Almería Metropolitan Area – East
Type of facility: HRAP + TW
Treated medium: domestic sewage
Description of the solution: This experimental plant was installed at El Toyo WWTP, a medium-size plant located in the outskirts of Almeria (Andalusia, Spain). The projects aimed at comparing under real conditions a conventional WWTP with an hybrid alternative treatment that combines a semi extensive wastewater treatment systems such as HRAP, a Dissolved Air Flotation Unit (DAFAST) unit to separate algae biomass from treated wastewater and an extensive wastewater treatment systems such as SSVF.

BASIC INFORMATION

Construction year: 2018
Constructor: URCI consultores
Source of financing: LIFE BIOSOLWARE and H2020 SABANA project
Facility operator: General Secretariat for Water. GIASA Regional Government of Andalusia.
Total cost: 1 500 000 €
Maintenance cost: 5 000-8 000 € / year
Contact person: Raul Cano
(raul.cano.herranz@fcc.es)



GEOGRAPHICAL COORDINATES

Latitude: 36° 50' 28" N
Longitude: 2° 24' 41" W

LOCATION

Country: Spain
City: Almeria
Type of climate: BSk
Average temperature: 17.4 °C
Sum of precipitation: 221mm



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
-	☆☆☆☆	☆☆☆	☆☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+	+	+	+		

TECHNICAL DATA

Area of the facility:

Microalgae raceway pond - 3000m²

Constructed wetland - 200m²

Volume: 900m³

Primary design factor: 50 000 PE capacity- 13,000 m³/day

Efficiency and effectiveness: >90% COD, >65% TP, >60% TN (microalgae raceway pond); >90% TSS and Turbidity (CW)

Hydraulic load or HRT:

Microalgae pond->3.5-5 days

Constructed Wetland->80L/m²/day

ECOLOGICAL POTENTIAL


Allows treatment of wastewater that can be made available for reuse. It also helps recover nutrients in biomass and prevents eutrophication through wastewater treatment. It is a very energy efficient system in comparison to conventional wastewater treatment.

ADVANTAGES

1. Low energy consumption.
2. Simple maintenance and operation compared to conventional wastewater treatment technologies.
3. Production of algae biomass and biogas.

DISADVANTAGES

1. Larger carbon footprint than conventional wastewater treatment technologies.



Source: urciconsultores.com/en/new-wastewater-treatment-plant-in-almeria



Funded by the Horizon 2020 Framework Programme of the European Union

This document was prepared as a part of NICE Project by the technical team from Gdansk University of Technology

HIGH RATE ALGAE POND



OBJECT INFORMATION

Name: HRAP SSVF + TW in Agramon

Type of facility: HRAP+SSVF

Treated medium: domestic sewage

Description of the solution: Demonstrative plant built in the small town of Agramón (Hellín, Spain). The project aimed at building a demonstrative HRAP with Dissolved Air Flotation Unit (DAFAST) unit and VFCW used as clarifiers to separate algae biomass from treated wastewater. The HRAP demo plant consists of a 10 000 m² raceway with SSVF consisting of four 50 m² beds.



AGRAMON

GEOGRAPHICAL COORDINATES

Latitude: 38° 25' 18" N

Longitude: 1° 38' 17" W

LOCATION

Country: Spain

City: Agramon / Albacete

Type of climate: Csa

Average temperature: 14.6 °C

Sum of precipitation: 379mm

BASIC INFORMATION

Construction year: 2022

Constructor: Aqualia FCC

Source of financing: H2020 SABANA project

Facility operator: Aqualia FCC

Total cost: 2 500 000 €

Maintenance cost: 6 000-13 000 € / year

Contact person: Angel Encinas

(angel.encinas.bogeat@fcc.es)



Source: A.Encinas

Ecosystem services

Provisioning	Regulating	Cultural	Supporting
-	☆☆☆☆	☆☆☆	☆☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+	+	+	+		

TECHNICAL DATA

Area of the facility:

Microalgae raceway pond - 10 000m²

Constructed wetland - 200m²

Volume: 3000m³

Hydraulic load or HRT: 8 days
(microalgae raceway pond) ;600
L/m²/day (CW)

Operating experience: Simple
maintenance and operation
compared to conventional
wastewater treatment technologies.

ECOLOGICAL POTENTIAL

Includes services such as water purification, carbon sequestration (algae) and reduced energy consumption (helping with climate regulation) and waste decomposition. This facility provides habitat for plants, insects and amphibians.

ADVANTAGES

1. Low energy consumption.
2. Simplicity of operation during first year of operation. Operational problems are limited to scarce mechanical equipment (pumps, valves, blowers).
3. Production of algae biomass and biogas.

DISADVANTAGES

1. Larger carbon footprint than conventional wastewater treatment technologies.



Source: A.Encinas



Funded by the Horizon 2020 Framework
Programme of the European Union

This document was prepared as a part of
NICE Project by the technical team from
Gdansk University of Technology

FRENCH SUB-SURFACE VERTICAL FLOW BEDS FOR WASTEWATER TREATMENT, 80 PE



OBJECT INFORMATION

Name: Garelli shelter natural WWTP system (80 PE)

Type of facility: FRB + SSHF

Treated medium: domestic WW

Description of the solution: The system has five basins, arranged in two treatment stages: SSVF and then SSHF; it is designed to manage the treatment of the grey and black waters of the facility, without the need of pre-treatment systems, except for a screen for mechanical filtering. The "French style" scheme consist of:

(i) pre-treatment with manual screen/degreaser;

(ii) first stage with three parallel SSVF where the three basins work by rotation with cycles of 2-3 days use and 46 days rest;

(iii) second stage with two parallel SSHF
The system works completely by gravity with no energy, due to a self-activating siphon that feeds the FRB. The FRB were chosen to limit the extension of the system and to avoid the extraction and management of sludge, which is difficult and costly at high altitudes.



GEOGRAPHICAL COORDINATES

Latitude: 44° 15' 2" N

Longitude: 7° 49' 50" E

BASIC INFORMATION

Construction year: 2014

Constructor: IRIDRA Company, Sinbio

Source of financing: Interreg project ALCOTRA

Total cost: 58 000 €

Maintenance cost: 2 000-3 000 € / year

Contact person: Fabio Massi

(massi@iridra.com)

LOCATION

Country: Italy

City: Chiuso di Pesio

Type of climate: Cfb

Average temperature: 8.5 °C

Sum of precipitation: 1347 mm



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆☆	☆☆☆☆☆	☆☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+					

TECHNICAL DATA

Area of the facility: 85m²; FRB - 45m²
HF - 40m²

Volume: 68m³

Primary design factor: 80 PE;
average flow: 2.9 (week) – 4.7 (weekend) m³/d

Efficiency and effectiveness:
TSS – 89% BOD₅ – 89% TKN – 46%

Dominant plant species: for FRB: Epilobium angustifolium, Carex rostrate; for HF Rumex alpinus and Deschampsia caespitosa

ECOLOGICAL POTENTIAL


The use of plants present in wetlands allows for raw materials for food, cosmetics and medical products such as, fodder, wood, paper production, fertilizers. Moreover, it is a great contribution to biodiversity. It can serve as a possible energy source.

ADVANTAGES

1. The TW demonstrates that the lifespan of such facilities can be maintained even in high altitude in demanding environment.

DISADVANTAGES

1. The main disadvantage is that the facility had numerous design constraints.




Source: R.Bresciani et al. „Guidelines on constructed wetland for wastewater treatment in the alpine environment”



Funded by the Horizon 2020 Framework
Programme of the European Union

This document was prepared as a part of
NICE Project by the technical team from
Gdansk University of Technology

HYBRID TREATMENT WETLAND FOR WASTEWATER AND REUSE IN INDUSTRY



OBJECT INFORMATION

Name: Hybrid HF-FWS constructed wetland in a large-scale wastewater treatment plant in Jesi, Italy

Type of facility: SSHF + FWS, SRB

Treated medium: domestic wastewater

Description of the solution: The whole system treats about 18 000 m³/d (around 60 000 PE) and a part of the effluent is reused in a nearby industrial area. All the new sections have been provided with an online monitoring system, in order to reduce as much as possible the energy consumption for the denitrification process leaving more role to the final wetland whenever it obtains sufficient performances. The hybrid TW system consists in a first sedimentation pond with a volume of 5000 m³, a 1ha HF and a 5ha FWS. The accumulated sludge in the sedimentation basin are periodically pumped in a wet woodland planted with *Populus alba*.



GEOGRAPHICAL COORDINATES

Latitude: 43° 21' 10" N

Longitude: 13° 15' 43" E

BASIC INFORMATION

Construction year: 2003

Constructor: Multiservizi Spa

Source of financing: private

Facility operator: Multiservizi Spa

Total cost: 1 774 685 €

Maintenance cost: 12 000-17 000 € / year

Contact person: Anacleto Rizzo

rizzo@iridra.com

LOCATION

Country: Italy

City: Jesi

Type of climate: Cfa

Average temperature: 15.6 °C

Sum of precipitation: 681mm



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
-	☆☆☆☆	☆☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+	+	+	+		

TECHNICAL DATA

Area of the facility: 65 000m² in total
sedimentation pond - 5000 m², HF - 10 000m², FWS - 50 000m²

Volume: 42 000m³

Primary design factor: 60 000 PE, WW inflow 13 000-19 000 m³/day

Dominant plants species: HF planted with *Phragmites australis*. Wet woodland planted with *Populus alba*.

Efficiency and effectiveness: The average removals during the first 3 years of operation are 76%, 10%, 50%, and 30% for TSS, BOD₅, NO₃⁻, and TN, respectively.

ECOLOGICAL POTENTIAL


Includes services such as nutrient cycling, primary production, soil-formation, habitat provision, capturing carbon compounds. These make it possible for the ecosystems to continue providing services such as food supply, flood regulation, water and air purification, researches on large scale NBS facilities.

ADVANTAGES

- 1.High treatment efficiencies in terms of organic and nutrient loads.
- 2.No or almost negligible energy consumption.
- 3.Simple construction and maintenance.

DISADVANTAGES

- 1.Huge undertaking in terms of land needed.
- 2.Many hydraulic calculations needed.



Source: F. Massi "Enhanced Denitrification by a Hybrid HF-FWS Constructed Wetland in a Large-Scale Wastewater Treatment Plant"



Funded by the Horizon 2020 Framework Programme of the European Union

This document was prepared as a part of NICE Project by the technical team from Gdansk University of Technology

HYBRID TREATMENT WETLAND FOR WASTEWATER



OBJECT INFORMATION

Name: TW in Jougar

Type of facility: TW

Treated medium: domestic WW

Description of the solution: A combined SSVF and SSHF TW systems, designed for rural domestic WW treatment and with theoretical HRT of 2 days and 3.6 days. Several water quality parameters including pH, BOD₅, COD, TSS, TKN and TP, and faecal bacteria's number in both raw and treated wastewaters were monitored during a macrophytes life cycle.



LOCATION

Country: Tunisia

City: Jougar

Type of climate: BWh

Average temperature: 19.4 °C

Sum of precipitation: 196mm

GEOGRAPHICAL COORDINATES

Latitude: 36° 29' 34" N

Longitude: 9° 56' 55" E

BASIC INFORMATION

Construction year: 2004

Constructor: Centre International des Technologies de l'Environnement de Tunis (CITET)

Source of financing: Tunisian government (SERST)

Facility operator: CITET

Total cost: 20 000 €

Maintenance cost: 600 € / year

Contact person: Soulwene Kouki
(kouso2004@yahoo.fr)



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
-	☆☆☆☆	☆☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+	+	+	+		

TECHNICAL DATA

Area of the facility: Sum -328m²

VF -121m² HF - 207m²

Volume: 492m³

Catchment: 170 000m²

Efficiency and effectiveness: The main treatment performance results showed the following average removal rates: BOD₅ (93 ± 2%), COD (89 ± 3%), TSS (98 ± 1.5%), TKN (38 ± 19%), TP (72 ± 16%).

ECOLOGICAL POTENTIAL


This facility is one of the pilot NBSs in Tunisia treating wastewater. Wetlands were used for researches that would enable the improvement of physicochemical and biological parameters of wastewater in the future.

ADVANTAGES

1. The facility serves a population of almost 1000 inhabitants, which equals to a one whole village.
2. CWs system had a good capacity to reduce BOD₅, COD, TSS and faecal bacteria.

DISADVANTAGES

1. The CWs system had a good capacity to reduce BOD₅, COD, TSS and faecal bacteria, but only moderate removal efficiencies of total nitrogen and phosphorus were recorded during the monitoring period.



Source: S. Kouki „Performances of a constructed wetland treating domestic wastewaters during a macrophytes life cycle:”



Funded by the Horizon 2020 Framework Programme of the European Union

This document was prepared as a part of NICE Project by the technical team from Gdansk University of Technology



INNOVATIVE – VFRB + VSSF + FWS FOR GROUND WATER RECHARGE

OBJECT INFORMATION

Name: TW system for wastewater treatment in the village of Castelluccio di Norcia
Type of facility: VFRB + VSSF + FWS
Treated medium: urban wastewater
Description of the solution: The plant represents an innovation in the french system of purification. In the first stage ,in VFRB, the solids accumulate on the surface. The second stage consists of two VSSF basins. The effluent is finally reused for groundwater recharge, by an infiltration area connected to a subirrigation trench.

LOCATION

Country: Italy
City: Castelluccio di Norcia
Type of climate: Cfb
Average temperature: 9.2 °C
Sum of precipitation: 1150mm



CASTELNUOVO DI NORCIA

GEOGRAPHICAL COORDINATES

Latitude: 42° 49' 2.64" N
Longitude: 13° 12' 1.26" E

BASIC INFORMATION

Construction year: 2012
Constructor: IRIDRA
Source of financing: region of Umbria
Facility operator: qualified personnel
Total cost: 395 000 €
Annual maintenance cost: 5531 €
Contact person: Fabio Masi
(masi@iridra.com)



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆☆	☆☆☆☆	☆☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+					

TECHNICAL DATA

Area of the facility: 3100 m²

Volume: 2170 m³

Catchment: 8.5 km²

Primary design factor: water quality targets: COD 160 mg L⁻¹; BOD₅ 40 mg L⁻¹; N-NH₄⁺ 25 mg L⁻¹; TSS 80 mg L⁻¹

Efficiency and effectiveness: The effluent concentrations of the FRB WWTP of Castelluccio di Norcia were stable below the water quality targets, with high mean removal efficiencies for COD, BOD₅, TN, N-NH₄⁺, TP and TSS.

ECOLOGICAL POTENTIAL

Includes services such as nutrient cycling, primary production, soil-formation, habitat provision. These make it possible for the ecosystems to continue providing services such as food supply, flood regulation and water purification.

ADVANTAGES


1. Does not require the primary treatment system (septic tank or Imhoff tank).

Consequently, FRB is an attractive solution to minimize the operational and maintenance costs of wastewater treatment from small settlement.

DISADVANTAGES

1. The FRB construction costs (364–394€ PE⁻¹) were slightly high.
2. The choice of a constructed wetlands system was dictated by strong fluctuation of the inhabitants, from a few dozen in the winter, to 1000 P E during summer and weekends.

Block scheme of the plant



Source: IRIDRA „Constructed wetlands system for wastewater treatment in the village of Castelluccio Di Norcia”



Funded by the Horizon 2020 Framework Programme of the European Union

This document was prepared as a part of NICE Project by the technical team from Gdansk University of Technology

MULTISTAGE TREATMENT WETLAND FOR AGRICULTURAL REUSE



OBJECT INFORMATION

Name: WWTP for agricultural water reuse from Chorfech village

Type of facility: TW

Treated medium: domestic WW

Description of the solution: The WW is primarily treated by an Imhoff tank in order to remove part of the solids to reduce the risk of clogging of the filter bed. The primary effluent is entering a hybrid TW system composed of three stages: HF wetland, VF wetland and finally a second HF wetland.

LOCATION

Country: Tunisia

City: Chorfech

Type of climate: Csa

Average temperature: 18.7 °C

Sum of precipitation: 444mm

GEOGRAPHICAL COORDINATES

Latitude: 36° 54' 59" N

Longitude: 10° 4' 43" E

CHORFECH



BASIC INFORMATION

Construction year: 2008

Constructor: IRIDRA

Source of financing: European Commission and the national partners of the project

Facility operator: no data available

Total cost: 72000€

Maintenance cost: 1000€ / year

Contact person: Anacleto Rizzo

rizzo@iridra.com



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆	☆☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+	+	+	+		

TECHNICAL DATA

Area of the facility: without the Imhoff tank about 1800 m²

Volume: 1590 m³

Efficiency and effectiveness:

Between May and June 2010, a monitoring campaign was carried out and the mean overall removal rates performed by the plant were respectively: 97% for TSS, 95% for COD and 97% for BOD₅, 71% for TN and 82% for TP.

ECOLOGICAL POTENTIAL


The WWTP implemented in Chorfech, is mainly meant as a demonstration of sustainable water management solutions (low-cost wastewater treatment).

ADVANTAGES

1. Increasing the available water for agricultural activities and solving the issue of uncontrolled wastewater discharge in the drainage channel nearby.

DISADVANTAGES

1. Clogging issues arise after the wine season.
2. Difficulties with calculating the issue of hydraulics in the facility.



Source: A. Ghrabi et al., "A multistage constructed wetland for wastewater treatment of small rural agglomeration in Tunisia"



Funded by the Horizon 2020 Framework Programme of the European Union

This document was prepared as a part of NICE Project by the technical team from Gdansk University of Technology

MULTISTAGE FREE WATER SURFACE WETLAND, 50 – 1000 PE



OBJECT INFORMATION

Name: Del Mar Fairgrounds TW

Type of facility: TW

Treated medium: domestic WW

Description of the solution: The treatment facility includes backstretch conveyance infrastructure, lift stations, a settling (East) pond, a TW system (West Pond), and a WW treatment facility. Designing a TW system that features both VF and HF TWs in an optimal sequence was an ideal design solution given the limited space within the Fairgrounds. Combined with proper maintenance and plant harvesting, this treatment wetland system removes 50% - 75% of nutrients from effluent.



GEOGRAPHICAL COORDINATES

Latitude: 38° 55' 49" N

Longitude: 6° 24' 21" W

BASIC INFORMATION

Construction year: 2020

Constructor: Great Ecology

Source of financing: Start-up funding

Facility operator: 22nd District Agricultural Association

Total cost: 1 500 000 €

Maintenance cost: 10 000-13 000 € / year

Contact person: info@greatecology.com

LOCATION


Country: United States of America

City: Del Mar, CA

Type of climate: Csc

Average temperature: 16.4 °C

Sum of precipitation: 379 mm



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
-	☆☆☆☆	☆☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+	+	+	+		

TECHNICAL DATA

Area of the facility: 44 500 m²

Volume: 65 000m³

Efficiency and effectiveness: The facility fulfils the assumed infiltration and outflow functions.

Operational experience: Great Ecology was part of an interdisciplinary team led by Fuscoe Engineering to tackle the challenge of treating surface water runoff from the Del Mar Fairgrounds to meet Regional Board discharge requirements.

ECOLOGICAL POTENTIAL

The constructed wetlands system is visually appealing, which is important given its prominent location on the Del Mar racetrack. The content of water and plants have a positive effect impact on the microclimate.

ADVANTAGES

1. Pre-treatment of water.
2. Providing a habitat for birds and small animals.
3. Absorbing air pollution and reducing heat in the summer.


DISADVANTAGES

1. Necessary operational works, ensuring i.e. patency of the inflow and proper development of plants.

BEFORE



AFTER



Source: greatecology.com



Funded by the Horizon 2020 Framework Programme of the European Union

This document was prepared as a part of NICE Project by the technical team from Gdansk University of Technology



ELECTORATIVE BACTERIA BASED SYSTEM

OBJECT INFORMATION

Name: Imetland system, Electroactive bacteria based system WWTP

Type of facility: Electroactive bacteria based system

Treated medium: domestic wastewater

Description of the solution: The treatment system was designed to treat the wastewater produced by 200 p.e., in 2018 at Ørby, Haderslev in the rural area of Southern Denmark. The wastewater treatment plant receives primary treated waters from 40 households. Each house has its own sedimentation tank of at least 2m³ capacity and all the wastewater generated by the houses is transported to the treatment plant in separate sewer, meaning that run off or storm waters do not come into the sewers and therefore do not reach the treatment plant. The wastewater is treated using a planted electroactive based system, of two parallel beds, followed by an anodic oxidation disinfection system to finally be disposed by infiltration.

BASIC INFORMATION

Construction year: 2018

Constructor: Kilian Water ApS

Source of financing: H2020 EU project

Total cost: ca 300.000 € (incl. VAT)

Facility Operator: Local association

Maintenance cost: 500 € per year

Contact person: Carlos A. Arias

(carlos.arias@bio.au.dk)

HADERSELEV



GEOGRAPHICAL COORDINATES

Latitude: 55° 18' 18" N

Longitude: 9° 37' 40" E

LOCATION

Country: Denmark

City: Haderslev

Type of climate: Cfb

Average temperature: 9,2°C

Sum of precipitation: 814 mm



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆	☆☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+	+	+	+		

TECHNICAL DATA

Area of facility: 120 m² in total

Two beds of 40 m², filled with electro-conductive material working in parallel, fed by a pump on the surface, with equal volume.

Pumping well, anodic oxidation disinfection system, to dispose the water in a ground infiltration system.

Houses served: 40, ca 200 p.e.

Design flow 23 m³/d, but daily flow can change according to houses occupation.

Efficiency and effectiveness of facility: pollution removal rates: BOD₅ = 99 %; COD = 92 %; TSS = 94 %; TKN = 70 %; TN = 70 %; TP = 55 %

Operating experience: simple maintenance and operation, low energy requirement and online monitoring via Wi-Fi.

ECOLOGICAL POTENTIAL

The TW integrated to the landscape, important in rural areas. The system benefits the presence of pollinators and discharges disinfected water lowering health risks to nearby coastal waters. In addition, this facility has low energy demand that can even be optimize by the installation of solar panels.



ADVANTAGES

1. Using electro bacteria based systems reduces the footprint.
2. Very low energy consumption (only a pump for feeding pulses).
3. Disinfection using solar power technology.

DISADVANTAGES

1. Electro-conductive material can be hard to find and might be expensive.
2. If operated saturated, nitrification is limited, but can be overcome by operating unsaturated.

Source: Carlos A. Arias



Funded by the Horizon 2020 Framework Programme of the European Union

This document was prepared as a part of NICE Project by the technical team from Gdansk University of Technology

SUB-SURFACE VERTICAL FLOW FRENCH BEDS FOR RAW WASTEWATER TREATMENT 20 000 PE



OBJECT INFORMATION

Name: French SSVF beds in Orhei municipality

Type of facility: FTW 20 000 PE

Treated medium: raw domestic WW

Description of the solution: Facility settled for the following treatment scheme:

1. A mechanical screw screen and grit.
2. A removal chamber, a flow equalization and pre-aeration tank.
3. A wetland system, divided in four lines, each of them composed of two stages in series: the first stage is a system with a VFRB for raw sewage and a classical VFTW system for the second stage.
4. A final disinfection pumping system for discharge into Raut river.



GEOGRAPHICAL COORDINATES

Latitude: 47° 22' 15" N

Longitude: 28° 46' 49" E

LOCATION

Country: Moldova

City: Orhei

Type of climate: Cfa

Average temperature: 10.9 °C

Sum of precipitation: 575mm

BASIC INFORMATION

Construction year: 2012-2013

Constructor: World Bank, Global Environment Facility Project – P.I.U. Moldova Government

Source of financing: local and UE funds

Facility operator: untrained personnel

Total cost: 85 000 € / year

Contact person: Anacleto Rizzo

(rizzo@iridra.com) or Fabio Masi

(masi@iridra.com)



Source: F.Massi et al. „Large scale application of French reed beds: municipal wastewater treatment for a 20 000 inhabitant town in Moldova.”

Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆☆	☆☆☆☆☆	☆☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+	+	+	+		

TECHNICAL DATA

Area of the facility: 34 948 m²

Volume: 36900 m³

Catchment: 50 000 m²

Efficiency and effectiveness: The Orhei French VFTW was able to meet the effluent water quality standards under very low temperatures (minimum registered temperature during the monitoring was -27°C), showing constant efficient removal of TSS, COD, and BOD5 independent of the different seasons and only a partly inhibited nitrification in winter.

ECOLOGICAL POTENTIAL


Includes services such as nutrient cycling, primary production, soil-formation, habitat provision. These make it possible for the ecosystems to continue providing services such as food supply, flood regulation and water purification.

ADVANTAGES

1. The facility is a great example of a solution that can be implemented in a medium or even a large scale.
2. The medium to large scale of the Orhei facility makes these co-benefits of high potential impact.

DISADVANTAGES

1. Higher investment costs to locate the treatment system in proximity of the reuse site.
2. Higher land occupation to meet local disinfection standards for reuse.



Source: F.Massi et al. „French vertical-flow treatment wetland in Orhei municipality, Moldova”



Funded by the Horizon 2020 Framework Programme of the European Union

This document was prepared as a part of NICE Project by the technical team from Gdansk University of Technology



FRENCH TREATMENT WETLAND WITH RECIRCULATION LOOP

OBJECT INFORMATION

Name: Bois d'Opale II

Type of facility: French TW with recirculation loop

Treated medium: domestic wastewater

Description of the solution: This treatment system was designed to treat the wastewater of a 480 p.e. residential area with a single stage composed of two cells of VF filters with water recirculation.

BASIC INFORMATION

Construction: 2011

Constructor: SEVEA;

Designer : Ecobird;

Source of financing: local funds

Total cost: 286 440 € (incl. VAT)

Maintenance cost: 4 816 € per year

Contact person: Stéphane Troesch
(s.troesch@ecobird.fr)

GEOGRAPHICAL COORDINATES

Latitude: 4°58'08.5"N

Longitude: 52°27'08.9"W

LOCATION

Country: France (Guyane)

City: Macouria

Type of climate: Af

Average temperature: 26,2°C

Sum of precipitation: 2560 mm



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆	☆☆☆	☆☆☆☆☆

TECHNICAL DATA

Area of facility: 392 m²

Catchment area: 1 200 m²

Volume: 235 m³

Hydraulic data: Dry weather 72 m³/d

Efficiency and effectiveness of facility:
guaranteed pollution removal rates: BOD₅ = 60 %; COD = 60 %; TSS = 50 %


Operating experience: simple maintenance and operation

UCC

1	2	3	4	5	6	7
+	+	+	+	+		

ECOLOGICAL POTENTIAL

The TW provides as water purification, nutrient cycling, habitat for insects and aesthetic value by being consistent with the surrounding landscape.



ADVANTAGES

1. This type of treatment system allows the application of raw wastewater directly without pretreatment.
2. Recirculating the water on the filter allows relevant efficiencies for a single stage.

DISADVANTAGES

1. Energy consumption due to water recirculation.
2. Plants must be removed more than once a year (tropical climate).

Source: S. Troesch



FRENCH TREATMENT WETLANDS

OBJECT INFORMATION

Name: Les Halles WWTP

Type of facility: French TW

Treated medium: domestic wastewater

Description of the solution: This treatment system was designed to treat the wastewater of 800 p.e. in such a way that the treatment of phosphorus and nitrogen is achieved without electricity. For this purpose, a succession of TW was implemented and consist in: a BiHofilter®, VFTW, trickling filters, filtering ditches and an apatite filter (P removal).



BASIC INFORMATION

Construction year: 2013

Constructor: SAVEA

Source of financing: local funds / Water Agency

Total cost: 884 442 € (incl. VAT)

Facility operator: Communauté de communes des Monts du Lyonnais

Maintenance cost: 5 000 € per year

Contact person: Stéphane Troesch
(s.troesch@ecobird.fr)

GEOGRAPHICAL COORDINATES

Latitude: 45°42'45.0"N

Longitude: 4°26'12.5"E

LOCATION

Country: France

City: Les Halles (district: Auvergne-Rhône-Alpes)

Type of climate: Cfb

Average temperature: 10°C

Sum of precipitation: 830 mm



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆	☆☆☆	☆☆☆☆☆

TECHNICAL DATA

Area of facility (filtration): 2 031 m² in total
 BiHofilter®: 961 m²; VFTW: 400 m²; VTCW saturated: 420 m²; Trickling filter: 15 m²;
 Filtering ditch: 92 m²; Trickling filter: 15 m²;
 Filtering ditch: 74 m²; Apatite filter: 54 m²

Catchment area: 9 600 m²

Volume of filtration: 2 234 m³ in total
 BiHofilter®: 1 009 m³; VFTW: 360 m³; VFTW saturated: 567 m³; Trickling filter: 17 m³;
 Filtering ditch: 102 m³; Trickling filter: 17 m³;
 Filtering ditch: 74 m³; Apatite filter: 89 m³

Hydraulic data: Dry weather: 154 m³/d;

Wet weather: 339 m³/d

Efficiency and effectiveness of facility:

pollution removal rates: BOD₅ = 99 %; COD = 96 %; TSS = 99 %; TKN = 97 %; TN = 83 %; TP = 91 %

Operating experience: simple maintenance and operation



ADVANTAGES


1. This type of treatment system allows the application of raw wastewater directly without pretreatment.
2. Energy-saving wastewater treatment plant operating without electricity with high removal efficiencies.

UCC

1	2	3	4	5	6	7
+	+	+	+	+		

ECOLOGICAL POTENTIAL

The TW provides water purification, nutrient cycling and aesthetic value by being consistent with the surrounding landscape. In addition, this facility has no energy consumption and provides a habitat for insects.



Discharge to the stream Le Charavet

DISADVANTAGES

1. A station without electricity requires a large footprint and a sloping site

Source: S. Troesch



Funded by the Horizon 2020 Framework Programme of the European Union

This document was prepared as a part of NICE Project by the technical team from Gdansk University of Technology

FRENCH TREATMENT WETLAND AND DISINFECTION POND



OBJECT INFORMATION

Name: The Misilya-Jarba WWTP

Type of facility: French TW and disinfection pond

Treated medium: domestic wastewater

Description of the solution: This treatment system was designed to treat the wastewater of 3600 p.e. using VF treatment filters (BiHofilter® configuration combining unsaturated and saturated layers within a single stage) followed by a disinfection lagoon before the treated water is infiltrated.



BASIC INFORMATION

Constructor: JV Brothers co/Arabia CC/SAVEA

Designer: Ecobird

Source of financing: AFD

Total cost: 1 900 000€ (incl. VAT)

Facility operator: Maythaoun Joint Water and Sanitation Service Council

Maintenance cost: 7 544 €/y

Contact person: Stéphane Troesch
(s.troesch@ecobird.fr)

GEOGRAPHICAL COORDINATES

Latitude: 32°23'31.3"N

Longitude: 35°17'35.3"E

LOCATION

Country: Palestine

City: Misilya-Jarba
(district: West Bank)

Type of climate: Csa

Average temperature: 21°C

Sum of precipitation: 540 mm



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆	☆☆☆	☆☆☆☆☆

TECHNICAL DATA

Area of facility: 9 855 m² in total
 Vertical filters: 4325 m²; Pond: 5530 m²
Catchment area: 34 190 m²
Volume: 9 680 m³ in total
 Vertical filters: 6 900 m³; Pond: 2780 m³
Hydraulic data: Dry weather: 267 m³/d; Wet weather: 320 m³/d
Efficiency and effectiveness of facility:
 guaranteed discharge levels: BOD₅ = 20 mg/L;
 TSS = 30 mg/L; TN: 50 mg/L
Operating experience: simple maintenance and operation

UCC

1	2	3	4	5	6	7
+	+	+	+	+		

ECOLOGICAL POTENTIAL

The FTW provides water purification, nutrient cycling, habitat for insects and aesthetic value by being consistent with the surrounding landscape.



ADVANTAGES

1. This type of treatment system allows the application of raw wastewater directly without pretreatment.
2. The unsaturated and saturated VF filter ensure 50% of TN removal within a single recirculated stage.
3. The lagoon allows a disinfection of the water before infiltration with energy consumption.

DISADVANTAGES

1. Disinfection with a lagoon requires a large footprint.
2. Energy consumption (solar panel) for recirculation loop of treated water on the 1st stage.

Source: S. Troesch



Funded by the Horizon 2020 Framework Programme of the European Union

This document was prepared as a part of NICE Project by the technical team from Gdansk University of Technology



AERATED TREATMENT WETLANDS

OBJECT INFORMATION

Name: ATW in Tarcenay, France

Type of facility: ATW

Treated medium: domestic wastewater

Description of the solution: ATWs are an advanced type of TWs, which allow more efficient removal of contaminants from wastewater owing to the higher availability of oxygen. This subsurface flow system is aerated mechanically from below, with an appropriate distribution system of air. This system is ideal for treating wastewater with high organic matter loads and for minimizing the land footprint of the TW. The WWTP (old pond) needed to be up-scaled and retrofitted while respecting higher outlet requirements. The Rhizosph'air process (patented by Syntea, Naturally Wallace and Rietland) involves two components: a vertical unsaturated filter receiving raw wastewater, followed by a horizontal saturated filter with forced aeration.



GEOGRAPHICAL COORDINATES

Latitude: 47° 16' 41" N

Longitude: 6° 10' 05" E

BASIC INFORMATION

Construction year: 2016

Constructor: Municipality of Tarcenay

Source of financing: municipality funds

Total cost: 830 000 €

Facility operator: Municipality of Tarcenay

Maintenance cost: 14 000 €

Contact person: Pascal Molle

(pascal.molle@inrae.fr)

LOCATION

Country: France

City: Tarcenay

Type of climate: Cfb

Average temperature: 10.6°

Sum of precipitation: 1230mm



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆	☆☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+	+	+	+		

TECHNICAL DATA

Area of the facility: 1400 m²

Volume: 112 m³

Hydraulic load: 0,28 m³/day

Forced Aeration: 3 hours/day, divided into four phases during the day

Primary design factor: 1400 P.E.; inflow rate 293 m³/day; population equivalent area 1 m² / P.E.

Operating experience: Operation and maintenance approaches for this case are similar to French VFTWs. They include two visits per week for treatment system inspection and control (screening and batch feeding system, alternation of filters, etc.). Once a year, plants (*Phragmites australis*) need to be harvested and once every 10–15 years the organic deposit layer needs to be removed to be used in agriculture by land application. The fact that the system is compact (1 m²/PE) translates to less harvesting time per year than a standard system.

ECOLOGICAL POTENTIAL

Owing to the simplicity of the operation, the community can manage the treatment plant.

Consequently, they use it for educational and visionary purposes related to green infrastructure. Sheep are used to maintain the green areas.

ADVANTAGES

1. The facility requires less land than other NBS solutions.

DISADVANTAGES

1. Usage of delicate technology that entails extra energy consumption.



Source: Anacleto Rizzo



Funded by the Horizon 2020 Framework Programme of the European Union

This document was prepared as a part of NICE Project by the technical team from Gdansk University of Technology





AERATED TREATMENT WETLAND AND SLUDGE DRYING REED BEDS

OBJECT INFORMATION

Name: Bas-en-Basset WWTP

Type of facility: Aerated TW
(Rhizosph'air) and SDRB for P sludge

Treated medium: domestic wastewater

Description of the solution: This treatment system is designed to treat the wastewater of 4500 p.e. The low nitrogen and phosphorous outlet consent are 10 mg/L in TKN, 15 mg/L in TN and 2 mg/L in TP. For the treatment of organic and more specifically nitrogen a Rhizosph'air® (aerated TW) was implemented. The treatment of phosphorus is done by ferric chloride and completed by SDRB for the phosphorous sludge management.



GEOGRAPHICAL COORDINATES

Latitude: 45°18'32.3"N

Longitude: 4°06'52.9"E

BASIC INFORMATION

Construction year: 2019

Constructor: SAVEA

Source of financing: local funds

Total cost: 1 752 560 € / 2 103 000 € (incl. VAT)

Facility operator: Syndicat des eaux Loire Lignon

Maintenance cost: 40 000 € / year

Contact person: Stéphane Troesch
(s.troesch@ecobird.fr)

LOCATION

Country: France

City: Bas-en-Basset
(district: Auvergne-Rhône-Alpes)

Type of climate: Cfb

Average temperature: 11°C

Sum of precipitation: 544 mm



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆	☆☆☆	☆☆☆☆☆

TECHNICAL DATA

Area of facility: Rhizosph'air®: 4 568 m²; SDRB: 440 m²

Volume: Rhizosph'air®: 7 537 m³; SDRB: 242 m³

Hydraulic data: Dry weather: 875 m³/d; Wet weather: 1275 m³/d

Efficiency and effectiveness of facility: guaranteed discharge levels: BOD₅ = 10 mg/L; COD = 60 mg/L; TSS = 15 mg/L; TKN = 10 mg/L; TN = 15 mg/L; TP = 2 mg/L

Operating experience: plant performing better than expected with outlet concentrations lower than consent threshold



ADVANTAGES

1. Treatment of raw sewage directly on TW without pretreatment.
2. The Rhizosph'air® can reach very low concentrations of nitrogen at the outlet (15 mg N/L) through sequential aeration within the same stage.
3. The addition of ferric chloride allows to reach very low TP concentration.
4. Compactness of the system in comparison with extensive TW.
5. A reliable phosphorous sludge management with SDRB.

UCC

1	2	3	4	5	6	7
+	+	+	+	+		

ECOLOGICAL POTENTIAL

1. Wastewater treatment and sewage sludge management using natural methods.
2. Effective removal of biogenic compounds from wastewater.
3. Recovery of biogenic compounds from sewage sludge.



DISADVANTAGES

1. The energy consumption, due to the Rhizosph'air®, is more important than a classic TW solution but still 3 to 4 times lower than an activated sludge plant.
2. Additional maintenance due to blowers, and aeration networks.

Source: S. Troesch



Funded by the Horizon 2020 Framework Programme of the European Union

This document was prepared as a part of NICE Project by the technical team from Gdansk University of Technology



HIGH RATE ALGAE POND

OBJECT INFORMATION

Name: HRAP in Chiclana
Type of facility: HRAP
Treated medium: domestic sewage
Description of the solution: This HRAP plant was installed next to El Torno WWTP (Chiclana de la Frontera, Cadiz) as part of the ALL-GAS project. The aim of the project was to demonstrate the sustainable large-scale production of biofuels based on low-cost microalgae cultures using municipal wastewater. The 2.2 ha plant was designed to produce algae biomass with a yield close to 100 t/ha/yr to generate enough biomass for biogas production. The project also consisted of biomass separation, processing for downstream biofuel production and purification, as well as filling points for vehicles.



CHICLANA

GEOGRAPHICAL COORDINATES

Latitude: 36° 25' 50.655" N
Longitude: 6° 9' 22.401" W

BASIC INFORMATION

Construction year: 2017
Constructor: INCOVER
Source of financing: FP7 ALL-GAS
Facility operator: Aqualia FCC
Total cost: 5 000 000 €
Maintenance cost: 15 000-25 000 €
Contact person: Raul Cano
(raul.cano.herranz@fcc.es)

LOCATION

Country: Spain
City: Chiclana de la Frontera
Type of climate: CSa
Average temperature: 18.2°C
Sum of precipitation: 600mm



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
-	☆☆☆☆	☆☆☆	☆☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+	+	+	+		

TECHNICAL DATA

Area of the facility: 22 000 m²

Volume: 6 600 m³

Hydraulic load or HRT: 6 days

Operating experience: All the planted filters remove about 90 % of the pathogens. Solar disinfection technology (AUTARCON) removes the rest. The 5 planted filters takes more than 95 % of the nutrients without using the recycling technology yet. The production obtained is extremely high (> 5 kg DM/m²) and it has never been done before with wastewater.

ECOLOGICAL POTENTIAL

Allows treatment of wastewater that can be made available for reuse. It also helps recover nutrients in biomass and prevents eutrophication through wastewater treatment. It is a very energy efficient system in comparison to conventional wastewater treatment.

ADVANTAGES

1. Low energy consumption.
2. Simple maintenance and operation compared to conventional wastewater treatment technologies.
3. High efficiency of total Nitrogen and total Phosphorus removal.

DISADVANTAGES

1. Larger carbon footprint than conventional wastewater treatment technologies.



Source: incoover-project.eu/news/case-study-resources-recovery-municipal-wastewater-using-high-rate-algae-ponds-evaporative



Funded by the Horizon 2020 Framework Programme of the European Union

This document was prepared as a part of NICE Project by the technical team from Gdansk University of Technology



HIGH RATE ALGAE POND

OBJECT INFORMATION

Name: HRAP in Merida, Spain
Type of facility: HRAP, VF
Treated medium: domestic sewage
Description of the solution: At the start of the trials, the bioreactors were filled with urban WW as a sole source of nutrients and left to be populated by the sewage-born phytoplankton. The fitness and growth of the phytoplankton population (dominated by the green microalga *Micractinium*) were monitored by photosynthesis measuring techniques. The cultures showed suitable photosynthetic activity. In these trials, photosynthesis measuring techniques, i.e., oxygen evolution and chlorophyll fluorescence techniques, were validated to monitor large-scale bioreactors using municipal WW remediation for biomass production, which can be used for agricultural purposes as biofertilizer/biostimulant. The projects aimed at comparing under real conditions a conventional oxidation ditch with HRAP with DAFAST unit and VFCW used as clarifiers to separate algae biomass from treated wastewater.

LOCATION

Country: Spain
City: Merida
Type of climate: CSa
Average temperature: 26.5 °C
Sum of precipitation: 734mm



MERIDA

GEOGRAPHICAL COORDINATES

Latitude: 38° 55' 49.18" N
Longitude: 6° 24' 21.68" W

BASIC INFORMATION

Construction year: 2020
Constructor: Aqualia FCC
Source of financing: H2020 SABANA project
Facility operator: Aqualia FCC
Total cost: 2 500 000€
Maintenance cost: 50 000-80 000€ / year
Contact person: Angel Encinas
(angel.encinas.bogeat@fcc.es)



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
-	☆☆☆☆	☆☆☆	☆☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+	+	+	+		

TECHNICAL DATA

Area of the facility: 20 000m²-
microalgae raceway pond
200m² - constructed wetland
Volume: 6 000m³
Retention time: 4-5 days
Operating experience: Simple
maintenance and operation
compared to conventional
wastewater treatment technologies.
Dominant algae species: *Micractinium*
sp.

ECOLOGICAL POTENTIAL


Includes services such as water
purification, carbon sequestration
(algae) and reduced energy
consumption (helping with climate
regulation) and waste
decomposition. This facility provides
habitat for plants, insects and
amphibians.

ADVANTAGES

1. Low energy consumption.
2. Simplicity of operation during first year
of operation.
3. Production of algae biomass and biogas.

DISADVANTAGES

1. Larger carbon footprint than
conventional wastewater treatment
technologies.
2. Operational problems are to scarce
mechanical equipment (pumps,
valves, blowers).



Source: J. Masojidek et al. „Photosynthesis Monitoring in Microalgae Cultures Grown on Municipal Wastewater as a Nutrient Source in Large-Scale Outdoor Bioreactors



Funded by the Horizon 2020 Framework
Programme of the European Union

This document was prepared as a part of
NICE Project by the technical team from
Gdansk University of Technology

TREATMENT WETLAND FOR OIL WASTE WATER



OBJECT INFORMATION

Name: Nimr Water Treatment Plant

Type of facility: TW

Treated medium: water from oil exploration and production

Description of the solution: In the middle of a desert landscape in Oman, the world's largest commercial reed bed treatment plant for the cleaning of polluted water from oil production has been operating since 2008. The technology used is: passive hydro-cyclones for oil in water separation, FWS wetland for water polishing and hydrocarbons breakdown and evaporation ponds for treated effluent disposal (zero-discharge system). Also, partial reuse of the treated effluent for irrigation of crops with market value has already started. By using natural flow processes, no energy-intensive pumps are required to treat the polluted water throughout the system. The water is then distributed by gravity into 4 terraces.

LOCATION

Country: Oman

City: Nimr

Type of climate: Bsh

Average temperature: 25.4°C

Sum of precipitation: 173 mm



GEOGRAPHICAL COORDINATES

Latitude: 18° 34' 19" N

Longitude: 55° 49' 45" E

BASIC INFORMATION

Construction year: 2011-2044

Constructor: Bauer resources and Petroleum Development Oman

Operator: Petroleum Bauer Resources

Source of financing: Governmental sources

Total cost: about 100 000 000 \$

Contact: Dr. Roman Breuer

(roman.breuer@ecosys-wetlands.com)



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆	☆☆☆	☆☆☆☆☆

TECHNICAL DATA

Area of the facility: 13.5 km²

Primary design factor: treatment capacity of 175 000 m³/day

Efficiency and effectiveness: The oil content in the produced water is reduced from 500 mg/l when entering the NWTP to less than 0.5 mg/l when leaving the wetland system. Treatment efficiency >99.9%).

Dominant plant species: *Phragmites australis*

UCC

1	2	3	4	5	6	7
+	+	+	+			

ECOLOGICAL POTENTIAL

The facility enables the production of table salt in the process of evaporation from tanks intended for this purpose. Plant species growing within the wetlands are a source of building material that can be used as biomass fuel. The oil-infused water is detoxified and purified, and the recovered oils are used as a full salable product.

ADVANTAGES

1. This facility enables access to fresh water for a population of 80 000 people.
2. The system operates with minimum external power. Overall it allows to save 15% of treatment cost and 60% of CO₂ emissions.

DISADVANTAGES

1. Multi-branch investment requiring advanced knowledge in the field of hydraulics, environmental protection, chemistry.
2. Risk of clogging of the hydraulic system due to many organic components from fuel extraction.



Source:
wetsystems.com.au/portfolio-items/nimr-water-treatment-plant-oman



Funded by the Horizon 2020 Framework
 Programme of the European Union

This document was prepared as a part of
 NICE Project by the technical team from
 Gdansk University of Technology

HYBRID SUB-SURFACE TREATMENT WETLAND FROM DAIRY INDUSTRY



OBJECT INFORMATION

Name: Hybrid sub-surface TW in northern Hokkaido-Japan

Type of facility: TW

Treated medium: milking parlor WW

Description of the solution: A hybrid sub-surface flow TW was designed and constructed in November 2006 at Embetsu. It consists of three beds (VF-VF-HF) constructed in series (Fig.below). VF beds were designed as per the design recommendations of Paul Cooper. Facility works in seasonal variations on the purification and removal efficiencies of hybrid sub-surface TW system (VF-VF-HF).



LOCATION

Country: Japan

City: Embetsu

Type of climate: Dfb

Average temperature: 7.2°C

Sum of precipitation: 1105 mm

GEOGRAPHICAL COORDINATES

Latitude: 44° 45' 00" N

Longitude: 141° 48' 00" E

BASIC INFORMATION

Construction year: 2006


Constructor: Graduate School of Agriculture

Source of financing: grants by Research Council of Ministry of Agriculture, Forest and Fisheries

Total cost: 40 000\$

Maintenance cost: 600\$ / year

Contact person: Pradeep Kumar Sharma (pradeep2910@gmail.com)



Source: P. K. Sharma et al. "Seasonal efficiency of a hybrid sub-surface flow constructed wetland system in treating milking parlor wastewater at northern Hokkaido"

Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆	☆☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+	+	+			

TECHNICAL DATA

Area of the facility: 656m²

Volume: 460m³

Catchment: Parlor milking water and some precipitation

Hydraulic loading rates: 7.9 and 7.3 mm/d were observed during cold and warm periods. It fluctuated from 4.7 to 17.4 mm/d during cold period and 1.8 to 14.2 mm/d during warm period

ECOLOGICAL POTENTIAL


Wastewater from the dairy is not transported to a receiver such as a river or the sea, but is used to grow cane and rice. The wastewater contains the nutrients necessary to ensure the proper life cycle of these crops.

ADVANTAGES

1. Regardless of extremely adverse climate conditions and high nutrient loads, hybrid sub-surface CWs can efficiently achieve higher purification and removal rates of >95% for TSS and total coliform, >89% for COD and BOD₅, >76% for TN and >72% for TP during both cold and warm periods.

DISADVANTAGES

1. These systems has limitations of relatively large area requirement, bad odor and are difficult to operate in extremely colder climates.



Source: researchgate.net, Pradeep Kumar Sharma



Funded by the Horizon 2020 Framework Programme of the European Union

This document was prepared as a part of NICE Project by the technical team from Gdansk University of Technology

MULTISTAGE TREATMENT WETLAND FOR WINERY WASTEWATER



OBJECT INFORMATION

Name: Cecchi winery TW

Type of facility: TW

Treated medium: industrial WW

Description of the solution: The winery WW has been treated with a multi-stage wetland system since 2001. The technology used is:

1st stage - a VFRB wetland raw wastewater of 1,200m².

2nd stage - 4 parallel HFTW of 960m² (240m² each).

3rd stage - a single-bed FWS wetland of 850m²; optional sand filter of 50m² before discharge into Gena River.



BASIC INFORMATION

Construction year: 2001

Upgraded: 2019

Constructor: Casa Vitivinicola Cecchi e.F.-Dott.ssa Miria Bracali

Source of financing: Casa Vitivinicola Cecchi & F.

Facility operator: Winery employees

Total cost: 59 470 € / year

Contact person: Anacleto Rizzo

(rizzo@iridra.com)

GEOGRAPHICAL COORDINATES

Latitude: 43° 25' 4.14" N

Longitude: 11° 13' 5.96" E

LOCATION

Country: Italy

City: Municipality of Castellina in Chianti

Type of climate: Csa

Average temperature: 12.9°C

Sum of precipitation: 921 mm



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆	☆☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+	+	+			

TECHNICAL DATA

Area of the facility: 3060 m²

Volume: 2750m³

Catchment: 4000000m²

Efficiency and effectiveness: Flow 100 m³/d (mean value during peak vintage season) but average 70m³/d (volumes changed in 2009 after upgrading)

ECOLOGICAL POTENTIAL

Includes services such as nutrient cycling, primary production, soil-formation, habitat provision. These make it possible for the ecosystems to continue providing services such as food supply, flood regulation and water purification.

ADVANTAGES


1. Low-cost, low-maintenance and energy saving technology shows it is an effective solution for winery wastewater.

DISADVANTAGES

1. Difficulties in calculating the issue of hydraulics in the facility.

Refurbished CW beds in horizontal subsurface flow systems.

Third stage recovered FWS from the original CW WWTP of 200



Source: A. Rizzo et al. "Online Monitoring of a Long-Term Full-Scale Constructed Wetland for the Treatment of Winery Wastewater in Italy"



Funded by the Horizon 2020 Framework Programme of the European Union

This document was prepared as a part of NICE Project by the technical team from Gdansk University of Technology

MULTISTAGE TREATMENT WETLAND FOR WINERY WASTEWATER



OBJECT INFORMATION

Name: Ornellaia and Masseto Winery

Type of facility: multistage TW

Treated medium: winery WW

Description of the solution: Project of TW for the wine producing firm "Tenuta dell' Ornellaia", Italy. The system consists of SSVF as a first stage followed by a second SSHF stage with recirculation to the first stage and then by a single FWS. It treats wastewater from the company, which allows water to be reused for irrigation.



GEOGRAPHICAL COORDINATES

Latitude: 43° 12' 41.2" N

Longitude: 10° 36' 41.9" E

LOCATION

Country: Italy

City: Bolgheri, Leghorn province

Type of climate: Csa

Average temperature: 15.8 °C

Sum of precipitation: 953 mm

BASIC INFORMATION

Construction year: 2001

Constructor: IRIDRA company

Source of financing: private

Facility operator: winery employees

Total cost: 773 000 €

Maintenance cost: 2000 € / year

Contact person: Anacleto Rizzo

(rizzo@iridra.com) or Fabio Masi

(masi@iridra.com)



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆	☆☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+	+	+			

TECHNICAL DATA

Area of the facility: 1316m²

Volume: about 568m³

Catchment: 970 000m²

Hydraulic load: organic loading rate (kg COD /ha/d): 236

The flow rate during the winemaking period is about 42m³/d

ECOLOGICAL POTENTIAL


The facility enables waste decomposition. It is crucial as winery's sewage discharge is high in organic load. The facility supports biodiversity by planting various species. Nutrient cycling process can be observed.

ADVANTAGES

1. Easy maintenance of the facility.
2. Elevated improvement regarding economic, naturalistic and environmental aspects.

DISADVANTAGES

1. Difficulties with calculating hydraulics issue in the facility.
2. SSVF beds present light clogging problems after the season with black sludge layer.



Source: F. Massi „winery high organic content wastewaters treated by constructed wetlands in mediterranean climate”



Source: F. Massi



Funded by the Horizon 2020 Framework Programme of the European Union

This document was prepared as a part of NICE Project by the technical team from Gdansk University of Technology

TREATMENT WETLAND FOR EFFLUENT FINAL POLISHING



OBJECT INFORMATION

Name: Bhaco TW for effluent final polishing

Type of facility: FWS

Treated medium: metallurgical industry WW

Description of the solution: Bahco metallurgical industry for tool making needed an effluent final-stage treatment. A large land area was available in the factory facilities and costs for maintenance and operation of wastewater treatment are limiting factors in Argentina. In addition, sewage from the factory also required a final treatment. A FWS wetland was constructed. This type of TW was selected due to the efficiency in metal removal and the low costs for operation and maintenance. Although FWSs requires a large area, this is not a problem in this case. Industrial wastewater containing metals and sewage from the factory are treated together, both after a primary treatment (25 m³/day of sewage + 75 m³/day of industrial WW). Sewage improves the ability of macrophytes to take up heavy metals from wastewater

LOCATION

Country: Argentina

City: Santa Tome

Type of climate: Cfa

Average temperature: 19.1°C

Sum of precipitation: 1188 mm



GEOGRAPHICAL COORDINATES

Latitude: 31° 67' 46" S

Longitude: 60° 76' 91" E

BASIC INFORMATION

Construction year: 2002

Constructor: Bahco metallurgical industry

Operator: Bahco metallurgical industry

Source of financing: company funds

Total cost: 2 000 000 \$

Maintenance cost: 8 000- 10 000 \$

Contact person: M.A. Maine; message:

<https://www.researchgate.net/profile/Maria-Maine1>



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆	☆☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+	+	+			

TECHNICAL DATA

Area of the facility: 2 000 m²

Volume: 1 000 m³

Design flow: 100 m³/day of WW

HRT: 7-10 days

Efficiency and effectiveness: Treated effluent meets the Argentinian law limits for discharge. FWS performance improved with wetland maturity.

Type of substrate: The wetland was rendered impermeable with 6 layers of compacted bentonite, in order to achieve a hydraulic conductivity of 10⁻⁷ m/s. A layer of 1 m of soil was placed on top of the bentonite layer. Several locally available macrophyte species were planted into the wetland.

Dominant plant species: *Typha domingensis*

Operational experience: Although this FWS wetland was faced with accidental events, it was capable of recovering its performance, demonstrating its robustness. FWS and the discharge pond provide an additional ecosystem service with a high diversity of macrophytes and have become the habitat for diverse wildlife, such as ducks, geese, coots, capybaras, turtles.

The effluent, after passing through the wetland, was led to a 1.5 ha pond in the factory facilities. Phreatic water meters were placed around the wetland to monitor groundwater quality, as a security measure.

ECOLOGICAL POTENTIAL

FWS and the discharge pond provide an additional ecosystem service with a high diversity of macrophytes and have become the habitat for diverse wildlife, such as ducks, geese, coots, capybaras, turtles. The content of water and plants has a positive effect impact on the microclimate. The constructed wetlands system is also visually appealing.

ADVANTAGES

1. The facility helps to reduce run-off. It absorbs air pollution and serves as a pretreatment of water.

DISADVANTAGES

1. The main disadvantage is that the facility needs many operational works such as ensuring the patency of inflow.



Funded by the Horizon 2020 Framework Programme of the European Union

This document was prepared as a part of NICE Project by the technical team from Gdansk University of Technology

AGRICULTURAL LEACHATE TREATMENT WETLAND SYSTEM



OBJECT INFORMATION

Name: Crosswinds Marsh Wetland Interpretive Preserve
Type of facility: TW
Treated medium: post agricultural leachate
Description of the solution: One of the largest self-sustaining wetland mitigation projects in the USA, Crosswinds Marsh in New Boston, Michigan is also a recreational park and wildlife refuge that is part of the Wayne County Park system. The park was created to allow Detroit Metropolitan Wayne County Airport (DTW) to meet environmental regulations during a major airport expansion sited on top of an existing wetland. By remediating nearby land that was historically wetland that has been converted to primarily agricultural use, the park far exceeds requirements and accommodates multiple public uses, including passive recreation, fishing, and environmental learning opportunities.



NEW BOSTON, MI

GEOGRAPHICAL COORDINATES

Latitude: 42° 05' 38" N
Longitude: 83° 26' 27" W

BASIC INFORMATION

Construction year: 1995
Constructor: ABC Paving; W.H. Canon, Inc. L. Lawyer Construction
Source of financing: governmental funding
Total cost: 18 100 000 €
Maintenance cost: 15 000- 20 000 €
Facility operator: SmithGroup, Department of City Detroit Parks & Recreation
Contact person: Cassie Goodwin (smithgroup.com/people/cassie-goodwin)

LOCATION

Country: United States of America
City: New Boston, MI
Type of climate: Dfa
Average temperature: 10.0 °C
Sum of precipitation: 922mm



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆	☆☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+	+	+			

TECHNICAL DATA

Area of the facility: 4.25 km²

Efficiency and effectiveness: The facility captures runoff waters that may pose a risk of flooding nearby villages. Moreover, the system filters surface runoff water from the city and airport, improving its quality.

Operating experience: Continuous yearly monitoring and an aggressive management plan to control invasive species are critical to the success of habitat restoration.

ECOLOGICAL POTENTIAL

The site allows for the capture and treatment of surface runoff water that comes from the city, as well as the purification and use of gray sewage for watering plants. The park is home to many native species of animals and birds, whose numbers are constantly monitored. In addition, this facility is a meeting place for residents and a destination for tourists.

ADVANTAGES

1. Decreased upstream and downstream flooding.
2. Restored over 4.25km² of historical wetland habitat that had been drained for agriculture and residential use.

DISADVANTAGES

1. The constant need to monitor the hydrological situation, including the occurrence of flooding, as well as chemical and biological monitoring of the inflowing water bodies.



Source: landscapeperformance.org/case-study-briefs/crosswinds-marsh-wetland-interpretive-preserve



Funded by the Horizon 2020 Framework
Programme of the European Union

This document was prepared as a part of
NICE Project by the technical team from
Gdansk University of Technology



TREATMENT WETLAND FOR TREATMENT AND REUSE OF WINERY WASTEWATER



OBJECT INFORMATION

Name: TW in Vidigueira

Type of facility: one-stage TW

Treated medium: winery WW

Description of the solution: A facility that treats industrial WW from Vidigueira wineries with high saturation of organic components. The sewage is initially cleaned mechanically by separating the grapes on the grates. Then passes through the reed beds system. Treated sewage is directed to the tank. It can be used for watering crops. It can be classified as a one-stage TW.



LOCATION

Country: Portugal

City: Vidigueira

Type of climate: Cfb

Average temperature: 17.6°C

Sum of precipitation: 1100 mm

BASIC INFORMATION

Construction year: 2001

Ampliation: 2012

Constructor: Wine factory

Source of financing: private

Facility operator: Wine factory

Total cost: 200 000 €

Maintenance cost: 2500 € / year

Contact person: Herdade Cortes de Cima

(www.cortesdecima.com)

GEOGRAPHICAL COORDINATES

Latitude: 38° 09' 39.7" N

Longitude: 7° 43' 27.3" E



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆	☆☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+	+	+			

TECHNICAL DATA

Area of the facility: 1900 m²

Volume: 1900 m³

Catchment: 135000 m²

Efficiency and effectiveness:

$\text{NH}_4^+ < 10 \text{ mg/l}$, $\text{TP} < 10 \text{ mg/l}$, $\text{NO}_3^- < 50 \text{ mg/l}$

Operating experience: Simple to build, needs space that is not lacking in agricultural areas.

ECOLOGICAL POTENTIAL

Includes services such as circulation of nutrients primary production, soil formation, habitat provision. These enables the ecosystems to continue providing services such as food supply, flood regulation and water purification.

ADVANTAGES

1. Low construction and maintenance cost.
2. Use of energy-saving technologies.

DISADVANTAGES

1. Difficulties in calculating the hydraulics parameters of the facility.



Source: cortesdecima.com



Funded by the Horizon 2020 Framework Programme of the European Union

This document was prepared as a part of NICE Project by the technical team from Gdansk University of Technology

SUB-SURFACE VERTICAL FLOW TREATMENT WETLAND FOR AGROINDUSTRY



OBJECT INFORMATION

Name: SSVF TW for swine WW in San Rocco di Piegara

Type of facility: SSVF TW

Treated medium: swine WW

Description of the solution: The SSVF TW treats the swine WW produced by the pig farm situated in San Rocco di Piegara (Roverè Veronese). The NBS consists the FBA™ (Forced Bed Aeration™) technology to aerate the 5 VF beds, increasing the treatment efficiencies and reducing the requested area. The facility is designed to treat the swine WW produced by 3 000 pigs (WW flow 38 m³/d).



SAN ROCCO DI PIEGARA

GEOGRAPHICAL COORDINATES

Latitude: 45° 33' 41.16" N

Longitude: 11° 4' 31.46" E

BASIC INFORMATION

Construction year: 2017

Constructor: S.A.S.A. – Societa' Allevamento Suini Di Saviola Luca E C. S.N.C.

Source of financing: private

Facility operator: S.A.S.A.

Total cost: 2500000€

Maintenance cost: 5000€ / year

Contact person: Anacleto Rizzo
(rizzo@iridra.com)

LOCATION

Country: Italy

City: San Rocoo di Piegara

Type of climate: Cfa

Average temperature: 14.1°C

Sum of precipitation: 1101 mm



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆	☆☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+	+	+			

TECHNICAL DATA

Area of the facility: 2240 m²

Volume: 2000 m³

Catchment: 43000 m²

Efficiency and effectiveness: The TW has shown high average removal efficiencies: TSS 66.3%; COD 90.7%; NH₄⁺ 89.5%; TKN 82.8%; TN between 64.3% and 70.9%; TP 77.2%. Moreover, the aerated SSVF TW of San Rocco di Piegara is an example of the system capable of reproducing conditions similar to the best results reported in the literature.

ECOLOGICAL POTENTIAL

The pig farm is a facility where two products: biogas (used as a source of energy) and compost (used as a natural fertilizer) are obtained at the same time. Solution (aerated SSVF TW) implemented in the pig farm is dedicated to the treatment of swine WW.

ADVANTAGES

1. Aerated SSVF TW allows to propose a full scale system to treat swine WW in condition of limited available area.

DISADVANTAGES

1. Very high TSS, COD, nutrient load and salinity make calculations difficult.



Source: A. Rizzo et al., "Aerated constructed wetlands for swine wastewater treatment: experiences from the start-up of a full scale system in Italy"



Funded by the Horizon 2020 Framework Programme of the European Union

This document was prepared as a part of NICE Project by the technical team from Gdansk University of Technology



BIOREMEDIATION BY NBS

OBJECT INFORMATION

Name: Riyadh Bioremediation Facility

Type of facility: bioremediation facility

Treated medium: industrial WW

Description of the solution: The facility is the largest of its kind in the world. The previously derelict site is an integral component of the environmental restoration of the Wadi Hanifah watershed, where large quantities of untreated industrial and urban wastewater had constituted a public health hazard and jeopardized downstream wetland ecosystems. The facility is primarily composed of 134 bioremediation cells organized into 3 main groups. It relies on a food-chain-based approach in which primary producers (algae and higher-order plants) and consumer organisms (fish, birds, insects, etc.) break down urban wastewater components. A low-tech, eco-centric infrastructure of bioremediation cells, weirs, pools, riparian planting and complementary features provide the habitat required to support this ecosystem. The treated effluent augments the hydrological regime of the wadi or is recycled to accommodate other urban functions, including a new city-wide river park system.



GEOGRAPHICAL COORDINATES

Latitude: 24° 35' 27" N

Longitude: 46° 42' 21" E

LOCATION

Country: Saudi Arabia

City: Riyadh

Type of climate: BWH

Average temperature: 26.2°C

Sum of precipitation: 66m

BASIC INFORMATION

Construction year: 2009

Constructor: Badan Agricultural and Contracting Company

Source of financing: local funding

Total cost: 32 000 000\$

Facility operator: Arriyadh Development Authority

Maintenance cost: 600 000\$ / year

Contact person: Jean Trottier

(jean.trottier@umanitoba.ca)



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆	☆☆	☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+					

TECHNICAL DATA

Area of the facility: 1 km in length

Catchment area: 4000m²

Primary design factor: The designed flow rate is approximately 2.4m³/s with a retention time of approximately 31 hours. The biocells currently process an average of 350 000m³ of wastewater per day.

Operating experience: Removes an average of:
33% of TP,
13.5% of TN,
89% of fecal coliforms,
79% of total coliforms,
94% of total suspended solids.

ECOLOGICAL POTENTIAL

The facility is inhabited by creatures that can be collected and used for handcraft purposes. The structure cleans sewage and the surrounding air, aerates sewage, eliminates harmful pathogens from black sewage. It provides food, indirectly due to the source of water it is for crops.

ADVANTAGES

1. Saves around \$27 million per day, the cost of 253,000 barrels of oil that would be required for desalinization and reduces reliance on seawater as a water source.

DISADVANTAGES

1. May pose a threat to humans and reveal the fauna due to the pathogens collected from feces discharged from the city to the bioremediation facility.



Source landscapeperformance.org/case-study-briefs/wadi-hanifah-comprehensive-development-plan




Funded by the Horizon 2020 Framework
Programme of the European Union

This document was prepared as a part of
NICE Project by the technical team from
Gdansk University of Technology



FLOATING TREATMENT WETLAND FOR TANNERY WASTEWATER



OBJECT INFORMATION

Name: Treatment of tannery WW
Wastewater in a FTW

Type of facility: FTW

Treated medium: tannery WW

Description of the solution: The Sialkot discharges millions of gallons of untreated effluent into drains each day. In order to devise a cost-effective system for the treatment of tannery WW, a FTW was established to treat the effluent using local plants through phytoremediation. The efficiency of the FTW was tested with three different plant species. Wastewater from a tannery drain was pumped into the FTW tank with a flow of 0.5 litre per minute and was given a retention time of six days.



GEOGRAPHICAL COORDINATES

Latitude: 32° 35' 12" N

Longitude: 74° 23' 30" E

BASIC INFORMATION

Construction year: 2018-2019

Constructor: Adeel Younas

Source of financing: WWF-Pakistan

Total cost: 20 000 €

Facility operator: Adeel Younas

Maintenance cost: 600-1 000 €/ year

Contact person: Love Kumar, e-mail:

(lovekumar@ufl.edu)

LOCATION

Country: Pakistan

City: Sialkot

Type of climate: Cwa

Average temperature: 23.4°

Sum of precipitation: 1004 mm



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆	☆☆	☆☆☆

UCC

1	2	3	4	5	6	7
+	+					

TECHNICAL DATA

Area of the facility: 5m²

Volume: 4.31m³

Primary design factors: wastewater flow: 0.72 m³/day, detention time: 6 days

Dominant plant species: water hyacinth water lettuce, *Typha latifolia*

Operating experience: Each of plants were grown separately and operating for three months in the FTW tank.

ECOLOGICAL POTENTIAL


The sustainability of the tannery sector is important for the GDP of Pakistan. The tannery sector utilizes a large amount of water and discharges polluted water. In order to devise a cost-effective system for the treatment of tannery wastewater, a floating treatment wetland model was set up to treat effluent using local plant species .

ADVANTAGES

1. A cost-effective way and an alternative to expensive treatment methods.

DISADVANTAGES

1. High impact of solid particles introduced with the WW. High probability of clogging the hydraulic system.



Source: A.Youns and J.Shafiq „Treatment of Industrial Wastewater in a Floating Treatment Wetland: A Case Study of Sialkot Tannery”



Funded by the Horizon 2020 Framework Programme of the European Union

This document was prepared as a part of NICE Project by the technical team from Gdansk University of Technology



ROOFTOP HF TW FOR GREYWATER REUSE

OBJECT INFORMATION

Name: Rooftop wetland for greywater treatment and its agricultural reuse
Type of facility: rooftop wetland
Treated medium: greywater
Description of the solution: The company IRIDRA designed a rooftop wetland for the treatment and reuse of the graywater from the Singita Sasakwa Lodge for agricultural purposes. The system was designed as a HF wetland of a surface area of 23m² and with an estimated treatment capacity of 4m³/d in order to treat the greywater produced by all the activities of the resort (bathrooms, kitchen, pool, etc.).



MAKANDUS

GEOGRAPHICAL COORDINATES

Latitude: 3° 5' 15.5" S
Longitude: 34° 29' 30.271" E

BASIC INFORMATION

Construction year: 2015
Constructor: IRIDRA/Singita Sasakwa Lodge
Source of financing: private
Facility operator: Singita Sasakwa Lodge
Total cost: 5300 €
Maintenance cost: 500 €
Contact person: Fabio Masi
(masi@iridra.com)

LOCATION

Country: Tanzania
City: Makandusi, Serengeti
Type of climate: Aw
Average temperature: 26.1°C
Sum of precipitation: 1114 mm

NBS UNDER CONSTRUCTION

ROOFTOP BASIN



LECA FILLING



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆	☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+			+	+	+

TECHNICAL DATA

Area of the facility: 23 m²
Volume: 10.35 m³
Catchment: 130 m²
Primary design factor: wastewater capacity 4m³/day
Hydraulic retention time: 0.8 day
Type of substrate: LECA® (Light Expanded Clay Aggregates)

ECOLOGICAL POTENTIAL

Includes services such as nutrient cycling, primary production, soil-formation, habitat provision. These make it possible for the ecosystems to continue providing services such as food supply, flood regulation and water purification.


ADVANTAGES

1. The subsurface flow avoided the development of odors and mosquitoes and allowed the public to access and visit the wetland area.
2. Lightweight clay aggregates used to reduce weight of the system for both building materials and filling media.

DISADVANTAGES

1. The facility relies on pumping system.
2. The location of the wetland on the roof is dangerous - system failure and torrential rains may violate the load-bearing capacity of the building.

Resort in Grumentu community, Serengeti (Tanzania)



Source: F. Massi et al., "Green architecture and water reuse: examples from different countries"



Funded by the Horizon 2020 Framework Programme of the European Union

This document was prepared as a part of NICE Project by the technical team from Gdansk University of Technology

ROOF HYBRID FOR GREYWATER



OBJECT INFORMATION

Name: Tri-City wastewater treatment plant
Type of facility: LiveRoof hybrid
Treated medium: greywater
Description of the solution: The Tri-City Water Pollution Control Plant uses physical, biological and chemical treatment to clean approximately 32 000 m³ of wastewater per day, created by the cities of Gladstone, Oregon City and West Linn. Following the treatment process, clean water is released into the Willamette River. The roofs are irrigated with greywater, and the water treatment personnel monitor the water quality of the runoff from the roofs.

OREGON CITY, OR



GEOGRAPHICAL COORDINATES

Latitude: 45° 37' 68.3" N
Longitude: 122° 58' 98.2" W

BASIC INFORMATION

Construction year: 2010
Constructor: American Hydrotech Inc.
Source of financing: government project
Total cost: 10 000 000 \$
Facility operator: Tri-City service district
Maintenance cost: 10 000-15 000\$/year
Contact person: Green roofs company (aramis@greenroofs.com)

LOCATION

Country: United States of America
City: Oregon City, OR
Type of climate: Csb
Average temperature: 11.3°C
Sum of precipitation: 1486 mm



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆	☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+			+	+	+

TECHNICAL DATA

Area of the facility: 1 319 m²

Volume: 235 m³

Daily WW inflow: 32 000 m³ per day

Dominant plant species: succulents

Operating experience: The green roof is irrigated from air conditioning condensate, which prevents this water from entering the wastewater system and provides an additional cooling benefit to the building.

ECOLOGICAL POTENTIAL

Green roofs improve the quality of greywater such that it can subsequently be reused for irrigation of ornamental plants or can be drained to existing sewer lines. Green roofs can mitigate stormwater runoff quantity and improve its quality. In addition, they facilitate the provision of a sustainable built urban environment.

ADVANTAGES

- 1.Green roofs reduce urban heat island effect.
- 2.Green roof provides an additional insulation in the winter and during the summer reduces heat load to the building.

DISADVANTAGES

- 1.Necessary operational works, ensuring i.e. patency of the inflow and proper development of plants.



Source: LiveRoof Texas



Funded by the Horizon 2020 Framework Programme of the European Union

This document was prepared as a part of NICE Project by the technical team from Gdansk University of Technology

GREEN ROOF AS A WASTEWATER TREATMENT PLANT



OBJECT INFORMATION

Name: Green roof at Richmond wastewater treatment plant

Type of facility: LiveRoof hybrid

Treated medium: sanitary sewage

Description of the solution: Richmond's wastewater treatment plant serves approximately 58 000 customers in the city and is the largest of its kind in Virginia. Located along the south bank of the James River, the plant can treat up to 265 000 m³ a day of sanitary sewage and stormwater before returning it to the river.



GEOGRAPHICAL COORDINATES

Latitude: 37° 31' 12.7" N

Longitude: 77° 25' 23.2" W

LOCATION

Country: United States of America

City: Richmond, VA

Type of climate: CfA

Average temperature: 14.8 °C

Sum of precipitation: 1122mm

BASIC INFORMATION

Construction year: 2011

Constructor: International Roofing

Source of financing: government project

Facility operator: RIVERBEND NURSERY

Total cost: 80 000 \$

Maintenance cost: 3 000-5 000\$

Contact person: Green roofs company

(aramis@greenroofs.com)



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆	☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+			+	+	+

TECHNICAL DATA

Area of the facility: 557.4 m²

Daily WW inflow: 265 000 m³ / day

Dominant plant species: sedum, alliums, and euphorbia

Operating experience: The next goal is to install a green roof on the new Ultraviolet Disinfection Facility, a 2,000 square foot surface, for an estimated cost of \$35,000.

ECOLOGICAL POTENTIAL

Green roofs improve the quality of greywater so that it can subsequently be reused for irrigation of ornamental plants or can be drained to existing sewer lines. Green roofs can mitigate stormwater runoff quantity and improve its quality. In addition, they facilitate the provision of a sustainable built urban environment.

ADVANTAGES

- 1.Green roofs reduce urban heat island effect.
- 2.Green roof provides an additional insulation in the winter and during the summer reduces heat load to the building.

DISADVANTAGES

- 1.Necessary operational works, ensuring i.e patency of the inflow and proper development of plants.



Source: greenroofs.com/projects/richmond-waste-water-treatment-plant-effluent-filtration-building



Funded by the Horizon 2020 Framework Programme of the European Union

This document was prepared as a part of NICE Project by the technical team from Gdansk University of Technology

LIVING WALLS FOR GREYWATER REUSE



OBJECT INFORMATION

Name: LW for greywater treatment and reuse in Jewett Hall

Type of facility: Living wall

Treated medium: greywater from a dormitory

Description of the solution: The project for the LWs for Jewett Hall regards the construction of LWs and GFs, designed with the aim of treating and reusing light greywater (from showers and washbasins) produced by the dormitory, and will be reused for toilet flushing. The LWs are divided into the East Living Wall, and the West Living Wall, for a total surface area of approximately 80 m², while the GF covers a surface area of approximately 105 m². Therefore, the NBS of Jewett Hall is expected to treat up to 2.9 m³/d of greywater, about 1060 m³/year.

BASIC INFORMATION

Construction year: 2021-2022

Constructor: IRIDRA

Source of financing: NAWAMED project, EU ENI CBC MED program

Total cost: 10 000€

Facility operator: American University of Beirut (AUB)

Maintenance cost: 1 000-2 000€

Contact person: Anacleto Rizzo
(rizzo@iridra.com)

BEIRUT



GEOGRAPHICAL COORDINATES

Latitude: 33° 54' 02" N

Longitude: 35° 29' 09" E

LOCATION

Country: Lebanon

City: Beirut

Type of climate: Csa

Average temperature: 20.5°C

Sum of precipitation: 845 mm



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆	☆☆	☆☆☆☆☆

TECHNICAL DATA

Area of the facility: GF– 105 m²
 LW– 84 m²

Primary design factors:

LW - OTR: - 17 g O₂/m²*d

HLR: 100–700 l/m²*d

OLR: 50 g COD/m²/d

GF - OTR: 30 gO₂/m²d

HLR: 80 l/m²*d

OLR: 30 g COD/m²/d

Average daily hydraulic load:

2.9 m³/d

Efficiency and Effectiveness:

Expected outlet concentrations:

BOD₅ < 15 mg/l

COD < 100 mg/l

UCC

1	2	3	4	5	6	7
+	+			+	+	+

ECOLOGICAL POTENTIAL

LWs have zero or reduced energy consumption, making the costs for consumed energy almost negligible. Moreover, the facilities provide excellent environmental integration. They provide additional benefits typical of living walls such as thermal insulation, improvement of air quality and building aesthetics.

ADVANTAGES

1. LWs are ideal for treating slightly polluted water in situ and reusing it for activities that do not require drinking water.

DISADVANTAGES

1. High possibility of clogging the hydraulic network supplying greywater to the facility.



Source: IRIDRA



Funded by the Horizon 2020 Framework
 Programme of the European Union

This document was prepared as a part of
 NICE Project by the technical team from
 Gdansk University of Technology

LIVING WALL FOR GREYWATER REUSE



OBJECT INFORMATION

Name: LW for the treatment of greywater for the Valle dell'Anapo comprehensive state institute

Type of facility: living wall

Treated medium: greywater from a school

Description of the solution: The project was to construct a LW for the treatment and reuse of the greywater at a middle school.

The treatment of greywater from the school sinks is carried out through a LW adapted to provide TW processes, and the treated water is accumulated in an underground deposit. To avoid any hygienic-sanitary problem, a U.V. disinfection chamber was installed. The water is then reused for toilet flushing and irrigation.



GEOGRAPHICAL COORDINATES

Latitude: 37° 07' 07" N

Longitude: 14° 56' 12" E

BASIC INFORMATION

Construction year: 2022

Constructor: IRIDRA

Source of financing: NAWAMED project, EU ENI CBC MED program

Total cost: 59 000€

Facility operator: Ferla municipality

Maintenance cost: 8 000-10 000€/year

Contact person: State Institute in the Municipality of Ferla, Sicily

(svimed.nawamed@gmail.com)

LOCATION

Country: Italy

City: Ferla

Type of climate: Csa

Average temperature: 16.0°C

Sum of precipitation: 621 mm



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆	☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+			+	+	+

TECHNICAL DATA

Area of the facility: 30 m²

Primary design factors:

OTR: 17 gO₂/m²*d

HLR: 100 – 700 l/m²*d

Hydraulic load: 1.3 m³/d

Operating experience: The system involves the collection of water (mostly from washbasins) in a small tank, followed by a pumping system to feed the GW. The water percolates through the pots through a piping system, and a tank collects it for subsequent reuse.

ECOLOGICAL POTENTIAL

The plant species hosted by the pots promote bacterial biodiversity and allow the water to distribute itself evenly in the pots, guaranteeing purifying efficacy and having an aesthetic and cooling function.

ADVANTAGES

1. The structure is an integral part of the building's facade. Protection of the external parts of the wall and reduction of heating of the interior of the building under the LW.

DISADVANTAGES

1. The facility is exposed to supplying water only through rainfall (uncertainty of occurrence, which may damage the green wall) or tap water.



Source: IRIDRA



Funded by the Horizon 2020 Framework Programme of the European Union

This document was prepared as a part of NICE Project by the technical team from Gdansk University of Technology



LIVING WALLS FOR GREYWATER REUSE



OBJECT INFORMATION

Name: Pilot installation for greywater treatment and reuse in Univeristy of Jordan

Type of facility: Living wall

Treated medium: greywater from a dormitory

Description of the solution: The project aims at implementing the real scale pilot installations for greywater rainwater treatment and reuse, including GW. The technique that will be used for the treatment of the greywater in GWs derives from the constructed wetlands technology. The NBS are divided in three different areas, providing a green wall surface of about 218 m², and treating and recovering a total greywater flow rate equal to about 4.2 m³/d, the reusable greywater amounts to about 1000 m³/year.

BASIC INFORMATION

Construction year: 2022/2023

Constructor: IRIDRA

Source of financing: NAWAMED project, EU ENI CBC MED program

Total cost: 134 805€

Facility operator: University of Jordan

Maintenance cost: 2 000€ / year

Contact person: Anacleto Rizzo
(rizzo@iridra.com)

AMMAN



GEOGRAPHICAL COORDINATES

Latitude: 32° 00' 58" N

Longitude: 35° 52' 10" E

LOCATION

Country: Jordan

City: Amman

Type of climate: BSk

Average temperature: 17.2°C

Sum of precipitation: 187 mm



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆	☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+			+	+	+

TECHNICAL DATA

Area of the facility: 218 m²

Type of substrate: 10 mm round, washed gravel; sand 0.2-5 mm ($D_{60} = 1$ mm)

Efficiency and Effectiveness:

Category - toilet flushing

BOD₅ < 15 mg/l;

COD < 100 mg/l

Category - parking and lawn irrigation

BOD₅ < 30 mg/l

COD < 100 mg/l

ECOLOGICAL POTENTIAL

LWs have zero or reduced energy consumption, making the costs for consumed energy almost negligible. Moreover, the facilities provide excellent environmental integration. They provide additional benefits typical of green roofs such as thermal insulation, improvement of air quality and building aesthetics.


ADVANTAGES

1. LWs are ideal for treating slightly polluted water in situ and reusing it for activities that do not require drinking water.


DISADVANTAGES

1. High possibility of clogging the hydraulic network supplying greywater to the facility.

FEEDING SYSTEM
Scale 1:25



SECTION A-A
Scale 1:25



Source: IRIDRA



Funded by the Horizon 2020 Framework Programme of the European Union

This document was prepared as a part of NICE Project by the technical team from Gdansk University of Technology

LIVING WALLS FOR GREYWATER REUSE



OBJECT INFORMATION

Name: Living walls at Marina di Ragusa
Type of facility: LW
Treated medium: greywater
Description of the solution: The LW for greywater treatment and reuse system has been developed as demonstration project. The aim was environmental and economic sustainability obtained through the purification of grey water, and recovery and reuse for fit-for-purpose uses such as toilet flushing or irrigation produced by the showers of Margarita Beach. The LW aims to save about 350 litres of drinking water per day.

BASIC INFORMATION

Construction year: 2018
Constructor: AConsumelessMed project
Source of financing: private and initiative co-funded by the European Regional Development Fund
Total cost: 10 000€
Facility operator: unskilled personnel
Maintenance cost: 200€ / year
Contact person: Anacleto Rizzo
(rizzo@iridra.com)



GEOGRAPHICAL COORDINATES

Latitude: 36° 46' 54.98" N
Longitude: 14° 33' 31.06" E

LOCATION

Country: Italy
City: Marina di Ragusa, Sicily
Type of climate: Csa
Average temperature: 16.5°C
Sum of precipitation: 541 mm



Source: A. Rizzo et al.. "Living walls at Marina Di Ragusa, Italy"

Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆	☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+			+	+	+

TECHNICAL DATA

Area of the facility: 9 m²

Volume: 4.5 m³

Flow: 350 l/day

Primary design factor: 3m² /PE

Operating experience:

No monitoring campaign was established. On the other hand, the treated greywater was successfully reused throughout the tourist summer season of 2018, highlighting proper treatment.

ECOLOGICAL POTENTIAL

The LW was designed to be hotspot of biodiversity in the urban environment. Evapotranspiration of plants placed in the NBS supports the reduction of the urban heat island effect. Moreover, the facility purifies air. The installation of a construction was an occasion to renew the aesthetics, as well as to increase the green and sustainable image of the beach resort.

ADVANTAGES

- 1.The facility is relatively cheap and fulfils the assumed functions.
- 2.It does not take up much horizontal area in the city (in comparison to wetlands).

DISADVANTAGES

- 1.Further tests should be carried out to obtain in depth knowledge out treatment processes in the facility.



Source: A. Rizzo et al.. "Living walls at Marina Di Ragusa, Italy"



Funded by the Horizon 2020 Framework Programme of the European Union

This document was prepared as a part of NICE Project by the technical team from Gdansk University of Technology

GREEN ROOF AND RAIN GARDEN FOR WATER REUSE IN IRRIGATION




OBJECT INFORMATION

Name: Green roof and rain garden at the McKinley High School

Type of facility: rain garden and green roof

Treated medium: rainwater

Description of the solution: A wide variety of green infrastructure tools were incorporated into the school renovation to support its onsite stormwater management program. Importantly, these attractive features also are accessible green spaces which function as outdoor learning laboratories for the students. The green infrastructure solution features two main components: GR, a 219m² extensive green roof with 138m² of vegetative area and four inches of growing medium and RG, a 158m² RG along the outside of the courtyard.



GEOGRAPHICAL COORDINATES

Latitude: 42° 93' 73" N

Longitude: 78° 87' 88" W

BASIC INFORMATION

Construction year: 2012

Constructor: LP Ciminelli Inc., Joseph A Sanders & Sons Inc.

Source of financing: programme of Education Building

Total cost: 30 000 000\$

Facility operator: Vegtal I.D.

Maintenance cost: 600 \$ / year

Contact person: Green roofs company

(aramis@greenroofs.com)

LOCATION

Country: United States of America

City: Buffalo, NY

Type of climate: Dfa

Average temperature: 9.4 °C

Sum of precipitation: 1087 mm



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆☆	☆☆☆☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+			+	+	+

TECHNICAL DATA

Area of the facility: 377 m²

Catchment: 377 m²

Type of substrate: rubberform recycled rubber paver tiles

Efficiency and effectiveness: The facility fulfils the assumed functions of infiltration and outflow. 100m³ reduced run-off provided by the GR.

ECOLOGICAL POTENTIAL

Permeable pavements and a 11.5 m³ stormwater harvesting system allow water to be collected to support the courtyard water feature and can be re-used for irrigation of the school's extensive landscaping.

ADVANTAGES

- 1.GRs reduce urban heat island effect.
- 2.GR provides an additional insulation in the winter and during the summer reduces heat load to the building.

DISADVANTAGES

- 1.Necessary operational works, ensuring i.e patency of the inflow and proper development of plants.



Source: landscapeperformance.org/case-study-briefs/buffalo-public-school-305-mckinley-high-school



Funded by the Horizon 2020 Framework
Programme of the European Union

This document was prepared as a part of
NICE Project by the technical team from
Gdansk University of Technology

TREATMENT WETLAND FOR WASTEWATER REUSE IN URBAN HOSTEL



OBJECT INFORMATION

Name: Wastewater Reuse in an Urban College Hostel in India

Type of facility: TW

Treated medium: domestic WW

Description of the solution: Three treatment lines have been implemented at NBS facility:

The first line - 40 m³/d of domestic wastewater through an anaerobic primary treatment and then discharges the effluent to the sewer line.

The second line treats 40 m³/d of greywater through SSVF TW.

The third line treats 100 m³/d of domestic wastewater through an anaerobic primary and secondary treatment as well as three VFCW for tertiary treatment.



GEOGRAPHICAL COORDINATES

Latitude: 18° 31' 28" N

Longitude: 73° 49' 28" E

LOCATION

Country: India

City: Maharashtra, Pune

Type of climate: Aw

Average temperature: 24.3 °C

Sum of precipitation: 1200mm

BASIC INFORMATION

Construction year: 2015

Constructor: College of Engineering Pune

Source of financing: 7th Framework Programme of the European Commission and DST Government of India

Facility operator: College of Engineering Pune (staff trained by IRIDRA company)

Total cost: 160 000 €

Annual maintenance cost: 2 500 € / year

Contact person: Fabio Masi

(masi@iridra.com)



Source: F. Massi et al. „College of engineering Pune hostel campus: an Indian experience of sustainable wastewater treatment and reuse”



Source: R. Bresciani „Case study of sustainable sanitation projects. Wastewater reuse in an Urban College Hostel Pune, Maharashtra, India”

Ecosystem services

Provisioning	Regulating	Cultural	Supporting
-	☆☆☆☆	☆☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+		+	+		

TECHNICAL DATA

Area of the facility: 538m²

Volume: 511 m³

Primary design factor:

WW - 1054 PE; HLR 252 l/m²

Efficiency and effectiveness:

- OM and particulate have been sufficiently processed,
- nutrients have shown quite low performances

ECOLOGICAL POTENTIAL


Includes services such as nutrient cycling, primary production, soil-formation, habitat provision. These make it possible for the ecosystems to continue providing services such as food supply, flood regulation and water purification.

ADVANTAGES

1. Can be operated by unskilled labour if properly trained on the functioning of the plant.
2. No need of any chemicals for the process and no parameters have to be controlled during operation, except the periodical analysis on the inlet and outlet.

DISADVANTAGES

1. To limit odours and mosquitoes, the distribution pipes are laid under a thin gravel layer.
2. To reduce the excavation volumes, the basins are partially over ground, surrounded by a brick wall that can also constitute a sitting arrangement for students but it is used without proper safety measures.



Source: F. Massi et al. „College of engineering Pune hostel campus: an Indian experience of sustainable wastewater treatment and reuse”



Funded by the Horizon 2020 Framework Programme of the European Union


This document was prepared as a part of NICE Project by the technical team from Gdansk University of Technology

WATER MANAGEMENT SYSTEM



OBJECT INFORMATION

Name: Pete V. Domenici U.S. Courthouse Landscape Retrofit
Type of facility: water management system
Treated medium: direct rainfall
Description of the solution: The facility reconnects the site with its historical and geographic context through an evocative and sustainable design. Located in the downtown district, the design converts a water-intensive turf landscape into one that enhances environmental efficiency while providing a dignified setting for court operations. Design strategies include rainwater harvesting, stormwater management, energy-efficient lighting, solar panels, native and drought-tolerant plants, and extensive use of repurposed materials.



GEOGRAPHICAL COORDINATES

Latitude: 35° 05' 30" N
Longitude: 106° 38' 58" W

BASIC INFORMATION

Construction year: 2013
Constructor: AIC General Contractor Inc.
Source of financing: U.S. General Services Administration
Total cost: 2 800 000\$
Facility operator: U.S. General Services Administration
Maintenance cost: 25 000-35 000\$
Contact person: Chris Martin
(chris.martin@asu.edu)

LOCATION

Country: United States of America
City: Albuquerque, NM
Type of climate: BWk
Average temperature: 14.4°C
Sum of precipitation: 211 mm

BEFORE



AFTER



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆☆	☆☆☆☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+					+

TECHNICAL DATA

Area of the facility: 18 600 m²

Operating experience: Generates an estimated 43,100 kWh of solar power annually, 99% of the net energy needed for outdoor lighting.

Efficiency and effectiveness:

Reduces potable water use for irrigation by 86% compared to an established baseline.

ECOLOGICAL POTENTIAL


The main task of the facility is to manage rainwater in such a way as to reduce the shortage of water used to water plants around the facility. In addition, plants purify the incoming water and recharge groundwater.

ADVANTAGES

1. Irrigation water is supplemented by rainwater collected from the roof and stored in 2 underground cisterns (60 m³).

DISADVANTAGES

1. Grass, which is demanding in care, was partially sown as part of the facility's vegetation.



Source: landscapeperformance.org/case-study-briefs/pete-v-domenici-us-courthouse-landscape-retrofit



Funded by the Horizon 2020 Framework
Programme of the European Union

This document was prepared as a part of
NICE Project by the technical team from
Gdansk University of Technology



GREEN ROOF AT A SLOPE

OBJECT INFORMATION

Name: Kansas State University Memorial Stadium Green Roof
Type of facility: green roof
Treated medium: direct rainfall
Description of the solution: These roofs are semi-intensive GRs with sandy substrates — the sandy soil or growing media — laid at depths of circa 15cm over insulated, steeply sloped surfaces up to 40%. The facility’s substrates are held in place by a durable plastic geo-web system, which is secured to the upper part of each roof via stainless steel cables attached to eye-bolts at the top of each. The east roof substrate consists of expanded shale to reduce its weight. Both were seeded and planted with mostly species native to the Flint Hills ecoregion.



GEOGRAPHICAL COORDINATES

Latitude: 39° 11’ 14” N
Longitude: 96° 35’ 01” W

LOCATION

Country: United States of America
City: Manhattan, KS
Type of climate: Cfa
Average temperature: 13.2 °C
Sum of precipitation: 1045 mm

BASIC INFORMATION

Construction year: 2015-2016
Constructor: Blueville Nursery
Source of financing: foundations:
- the Mary K. Jarvis Endowment (K-State landscape architecture program),
- Jeffrey L. Bruce & Company LLC, the K-State Green Action Fund,
- the Pollinator Partnership, the Garden Club of America, Buildex,
- the Landscape Architecture Foundation (LAF)
Total cost: 2 500 000\$
Facility operator: City of Syracuse
Maintenance cost: 3 000\$ – 8 500\$/year
Contact person: Lee R. skabelund
(lskab@k-state.edu)



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆☆	☆☆☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+			+	+	+

TECHNICAL DATA

Area of the facility: 4 000m²

Volume: 600m³

Efficiency and effectiveness:

Created a healthy soil ecosystem. GR soil biomass increased from an average of 49.5 nanomoles per gram of substrate in 2017 to 77.4 nanomoles per gram in 2019. Organic matter increased from an average of 1.1% in 2017 to 1.65% in 2019.

ECOLOGICAL POTENTIAL

The facility captures the precipitation directly at the point where it is extracted. The surface runoff from the roof is reduced providing relief of the sewage system. Moreover, it acts as an insulator.


ADVANTAGES

1. The facility allows : reduction in expenses for gardeners, using drinking water for watering, lowering electricity bills. The green roof acts as an insulator.


DISADVANTAGES

1. Instead of sowing plants that do not need a lot of water, it was decided to irrigate vegetation that can die without constant watering.


Common roof




Green Roof



Temperature (C)



Temperature (C)



0 5 10 20 30 40 Meters

Source: landscapeperformance.org/case-study-briefs/Kansas-state-University-memorial-stadium-green-roofs



Funded by the Horizon 2020 Framework
Programme of the European Union

This document was prepared as a part of
NICE Project by the technical team from
Gdansk University of Technology



GREEN ROOF AS A RECREATIONAL SPACE

OBJECT INFORMATION

Name: ASLA headquarters Green Roof
Type of facility: green roof
Treated medium: direct rainfall
Description of the solution: The 280 m² green roof was installed in May of 2006. It is one of seven green roofs demonstration projects in the Anacostia River Watershed of DC. ETEC monitored water quality and quantity on this roof for 5 rain events in the fall of 2006 and the spring of 2007. The sampling and monitoring of the green roof was performed in accordance with the standard operations for collection and measurement promulgated by the U.S EPA. The location of the project in an urban area that faces significant issues related to combined sewer outflows and a degraded watershed makes the demonstration value of the project.

LOCATION

Country: United States of America
City: Washington, D.C.
Type of climate: Cfa
Average temperature: 13.0°C
Sum of precipitation: 1198 mm



GEOGRAPHICAL COORDINATES

Latitude: 38° 59' 03" N
Longitude: 77° 01' 17" W

BASIC INFORMATION

Construction year: 2006
Constructor: Blueville Nursery
Source of financing: Chesapeake Bay Foundation, National Fish and Wildlife Foundation, U.S. Environmental Protection Agency Chesapeake Bay Program. **Total cost:** 350 000 \$
Facility operator: American Society of Landscape Architects
Maintenance cost: 5 000-8 000\$
Contact person: Michael Van Valkenburgh Associates
website: <https://www.mvvainc.com/>



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆☆	☆☆☆☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+			+	+	+

TECHNICAL DATA

Area of the facility: 280 m²

Catchment area: 280 m²

Dominant plant species: the sedums, the phloxes, *Silene caroliniana*

Efficiency and effectiveness: The most effective is to reduce runoff from the rooftop and catch the precipitation where it occurs. Facility allows for reduction of ammonia, nitrates, as well as the content of dissolved content in the effluent.

ECOLOGICAL POTENTIAL

The green roof enables the production of nutrients. Plants purify rainwater and air. The temperatures measured between the traditional roof and the green roof differ from each other - the green roof reduces the surface heating temperature.

ADVANTAGES

1. Keeps the roof surface temperature as much as 6.5°C degrees cooler than on neighboring conventional black roofs on the hottest summer days.

DISADVANTAGES

1. Require irrigation the plants several times a week to maintain their beauty.



Source: landscapeperformance.org/case-study-briefs/asla-headquarters-green-roof



Funded by the Horizon 2020 Framework
Programme of the European Union

This document was prepared as a part of
NICE Project by the technical team from
Gdansk University of Technology

ROOFTOP FARM FOR REUSE OF STORMWATER




OBJECT INFORMATION

Name: Javits Center expansion rooftop farm

Type of facility: rooftop farm

Treated medium: direct of rainfall

Description of the solution: The project includes a one-acre green roof farm, all-season greenhouse, a 929 m² orchard and food forest with dozens of fruit-bearing trees, and 1302 m³ underground cistern for recovering and recycling rainwater runoff. Economic activity generated includes: 4,000 full time jobs; 2,000 part time jobs; 3,100 construction jobs; 200,000 more hotel room nights a year; and \$393 million in new economic activity a year.



GEOGRAPHICAL COORDINATES

Latitude: 40° 45' 27.87" N

Longitude: 74° 00' 11.98" W

BASIC INFORMATION

Construction year: 2021

Constructor: Lendlease Construction LMB Inc. & Turner Construction

Source of financing: Commercial Buildings

Total cost: 1 500 000 000 \$

Facility operator: Brooklyn Grange

Maintenance cost: 2 000 000 \$

Contact person: Green roofs company
(aramis@greenroofs.com)

LOCATION

Country: United States of America

City: 11th Avenue, New York

Type of climate: Cfa

Average temperature: 11.9°C

Sum of precipitation: 1139 mm



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆☆	☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+			+	+	+

TECHNICAL DATA

Area of the facility: 19 403 m²

Efficiency and effectiveness: Designed to reduce runoff by 25% and remove 80% of total suspended solids from water.

Operational experience:

There are five honeybee hives on the green roof and four hives at The Farm.

Two underground tanks with a 1 300 m³-holding capacity capture and treat rainwater to irrigate all of the plants on the rooftop, reducing the need for potable water for irrigation by at least 50%.

ECOLOGICAL POTENTIAL


After being filtered, the harvested rainwater from the cisterns will be used to irrigate crops and trees. Roof and sealed surfaces have light-colored materials that comply with the Solar Reflectance Index to reduce urban heat island effect. The facility provides a natural habitat for birds and other small animals.

ADVANTAGES

1. This facility reduces stormwater runoff and absorbs air pollutants.

DISADVANTAGES

1. Constant maintenance works are necessary to ensure patency of the inflow and proper development of plants.



Source: greenroofs.com/projects/javits-center-expansion-rooftop-farm



Funded by the Horizon 2020 Framework Programme of the European Union

This document was prepared as a part of NICE Project by the technical team from Gdansk University of Technology



HYDROPONIC SYSTEM

OBJECT INFORMATION

Name: GreenShades

Type of facility: hydroponic system

Treated medium: direct of rainfall

Description of the solution: Green Shades is a hydroponic system that allows the installation of vegetated awnings or tensile structures covered in vegetation. The water supply and return pipes as well as the electrical cables are routed along the structure. Each plant canopy is fitted with two drip pipes that form the terminals for the irrigation system. Water is collected in an installation room. A disused kiosk was used for the installation of the irrigation system equipment. One irrigation pipe runs from the kiosk to the awnings and another runs parallel to it, but in the opposite direction, returning to the installation.



VALLADOLID

GEOGRAPHICAL COORDINATES

Latitude: 41° 64' 96" N

Longitude: 72° 88' 46" W

LOCATION

Country: Spain

City: Valladolid

Type of climate: CSa

Average temperature: 12.5°C

Sum of precipitation: 490 mm

BASIC INFORMATION

Construction year: 2021

Constructor: SingularGreen


Source of financing: Urban GreenUp Project (Horizon2020)

Total cost: 344 605€

Facility operator: Tierra Ingenieria y Paisajismo

Maintenance cost: 2 000-5 000€ / year

Contact person: info@singulargreen.com



Source: singulargreen.com/en/green-shades-valladolid

Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆☆	☆☆☆☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+			+	+	+

TECHNICAL DATA

Area of the facility: 21m x 4m long triangular textile vegetal canopy

Catchment area: 145 m²

Efficiency and effectiveness: cooling power of 112 frigories/m²

Operating experience: 1m² of vegetated surface generates the oxygen required by a person throughout the year, and filters harmful gases,. It absorbs NO_x and CO₂.

ECOLOGICAL POTENTIAL

This system opens up a new range of possibilities and benefits for urban landscaping. It brings added value to increasingly urbanised cities. It reduces the temperatures by 2°C in and therefore improves the environment.

ADVANTAGES

1. It generates shadows for the enjoyment of the public space without taking away space from the users.

DISADVANTAGES

1. Carrying out all the necessary maintenance work: start-up and monthly maintenance of the irrigation system, pest control, pruning.

THE SCHEME OF HYDROPONIC SYSTEM



Source: singulargreen.com/en/green-shades-valladolid



Funded by the Horizon 2020 Framework
Programme of the European Union

This document was prepared as a part of
NICE Project by the technical team from
Gdansk University of Technology



LIVING WALL


OBJECT INFORMATION

Name: Musee de quai branly LW

Type of facility: LW

Treated medium: direct of rainfall

Description of the solution: There are plants that grow on damp rock walls. The plants are established without soil, in a layer of recycled polyamide felt that acts as a growing medium for the roots and carries a dilute nutrient solution from drip irrigation tubes at the top edge of the wall. The felt is attached to sheets of expanded PVC hung on a tubular steel frame that separates the vegetated surface from the building facade. A gutter along the bottom of the wall catches and recycles the irrigation water.



GEOGRAPHICAL COORDINATES

Latitude: 48° 51' 39" N

Longitude: 2° 17' 52" E

BASIC INFORMATION

Construction year: 2005

Constructor: Greenroofs.com LLC

Source of financing: public funding

Total cost: 640 000 €

Facility operator: Musee de quai Branly

Maintenance cost: 6 000-10 000€ / year

Contact person: Linda Velazquez

(linda@greenroofs.com)

LOCATION

Country: France

City: Paris

Type of climate: Cfb

Average temperature: 11.7 °C

Sum of precipitation: 720 mm



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆☆	☆☆☆☆☆	☆☆☆☆☆

TECHNICAL DATA

Area of the facility: 799 m²

Volume: 300 m³

Primary design factor:

$V_{\text{water}} = 350\text{l/day}$

Type of substrate: The climbing and crawling plants coming from humid regions, do not grow in the soil. Instead, they develop in the foam-rocks, tree trunks or creek pebbles, where they anchor their roots.

Operating experience: The technique of vertical culture overcomes weight problems and is suitable for all walls, regardless of their height.

UCC

1	2	3	4	5	6	7
+	+			+	+	+

ECOLOGICAL POTENTIAL

The LW is a popular place in Paris, which is a marketing point for the city. Plants help to increase biodiversity. Moreover, the installation contributes to reducing the heat-stress effect. Plants clean the polluted air in the city.

ADVANTAGES


1. The use of vertical space in the city is a great idea to develop the urban fabric (an ergonomic solution that does not require the use of horizontal surfaces, i.e. roads, sidewalks, squares, etc.).

DISADVANTAGES

1. Rainwater is not enough to irrigate the LW - tap water is needed, which generates costs and consumes drinking water unnecessarily.



Source: greenroofs.com/projects/musee-du-quai-branly-greenwall



Funded by the Horizon 2020 Framework Programme of the European Union

This document was prepared as a part of NICE Project by the technical team from Gdansk University of Technology



GREEN BUS STOP

OBJECT INFORMATION

Name: Green bus stop at John Paul II Square in Kalisz
Type of facility: green bus stop
Treated medium: direct of rainfall
Description of the solution: It is one of six such facilities in the city. The investment is carried out thanks to the activity of the residents who submitted the task to the Civic Budget. This bus stop is located in a highly sealed environment. Arrangement of objects: one pot with plants at the two shorter edges of the stop, from the back - planting plants in the ground. The frame on the back wall enables to surround the stop with climbing plants.

BASIC INFORMATION

Construction year: 2020
Constructor: Department of Municipal Management and Environmental Protection, Kalisz City Hall
Source of financing: local funds-participatory budgeting
Total cost: 290€
Facility operator: Department of Municipal Management and Environmental Protection, Kalisz City Hall
Maintenance cost: 50€ / year
Contact person: Izabela Grześkiewicz (igrzeskiewicz@um.kalisz.pl)



GEOGRAPHICAL COORDINATES

Latitude: 51° 45' 52.2" N
Longitude: 18° 5' 33.0" E

LOCATION

Country: Poland
City: Kalisz
Type of climate: Cfb
Average temperature: 9.6°C
Sum of precipitation: 666 mm



Source: I. Grześkiewicz

Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆☆	☆☆☆☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+			+	+	+

TECHNICAL DATA

Area of the facility: 8m²

Volume: 2m³

Primary design factor: $P_{max}=30\text{mm}$

Dominant plant species: Hemerocallis 'Stella de'oro'; Miscanthus sinensis 'Zebrinus'; Campsis radicans 'Flamenco'; Parthenocissus tricuspidata

ECOLOGICAL POTENTIAL

Green bus stops clean the air through the vital activities of plants planted in the facility. The green area causes the local air temperature reduction around the bus stop.

ADVANTAGES


1. Simplicity of structure design.
2. Relatively cheap solution.
3. It is a perfect way to arrange bus shelters. They do not need to be replaced with new and expensive ones, but it is enough to green them with a green support frame.

DISADVANTAGES

1. In periods of long shortage of rainwater, the facility must be watered with tap water.
3. Every 6 months (in spring and autumn), gardening is necessary, e.g. additional plantings, checking the condition of plants.

PROBLEMS

The execution of the ground-level part of the green stop (back of the facility) is ineffective in terms of supplying it with surface runoff. The curb is above the concrete level. It should be located at the ground level or slightly lower so that the water can flow freely to the ground. In this situation, the water stops in front of the curb and flows by gravity to the drain.



Source: I. Grześkiewicz



Funded by the Horizon 2020 Framework Programme of the European Union

This document was prepared as a part of NICE Project by the technical team from Gdansk University of Technology

FOG COLLECTORS WITH SEDIMENTATION TANK



OBJECT INFORMATION

Name: Eliseo Collazos Fog Water Farm-Park and Gardens

Type of facility: fog collectors with sedimentation tank

Treated medium: fog

Description of the solution: A gravity-fed irrigation system leads water from fog harvesters to a sedimentation tank to storage cisterns to a drip irrigation system that runs through the public farm-park. Six fog collectors with a total of 132 m² of fog wicking fabric use a mesh textile with a gutter to harvest water droplets that amount to an average of 3 000 liters of water per day, or 90 000 liters per month during the six- to nine-month foggy season. Seven water storage cisterns store up to 35 000 liters of water at a time. During the dry (non-foggy) season, water collected in the 7 water tanks can provide Eliseo Collazos' green spaces with more than the 6 000 liters of water needed per month for irrigation.



GEOGRAPHICAL COORDINATES

Latitude: 11° 49' 24" S

Longitude: 15° 06' 06" W

BASIC INFORMATION

Construction year: 2017

Constructor: Traction Design

Source of financing: local funds

Total cost: 90 000\$

Facility operator: Community of Eliseo Collazos

Maintenance cost: 1000 - 1500\$

Contact person: Traction Design Company
(operations@tractiondesign.org)

LOCATION

Country: Peru

City: Lima

Type of climate: BWh

Average temperature: 18.9 °C

Sum of precipitation: 203 mm



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆☆	☆☆☆☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+			+	+	+

TECHNICAL DATA

Area of the facility: 132m²

Efficiency and effectiveness:

Collects 90 000 liters of water per month during the foggy season, fulfilling 100% of home garden irrigation needs.

Operating experience:

Average fog catchment rate:
7 000 L/6 000 L per month equal to 116.67% of water need being met during dry season

ECOLOGICAL POTENTIAL

The NBS provides high-quality water necessary for growing plants. The condensed fog tanks provide a backup source of drinking water, which is lacking in this latitude. The creation of this type of facility brought residents closer together - the project has a social impact. Moreover, it plays an educational role.

ADVANTAGES

1. The construction of the facility is very simple.
2. Providing residents with water collections and developing horticulture and agriculture.

DISADVANTAGES

1. Danger of biofilm accumulation on the material. There are no factors for the development of pathogens on such a substrate.



Source: landscapeperformance.org/case-study-briefs/eliseo-collazos



Funded by the Horizon 2020 Framework
Programme of the European Union

This document was prepared as a part of
NICE Project by the technical team from
Gdansk University of Technology



GREEN ROOF

OBJECT INFORMATION

Name: CopenHill – green roof
Type of facility: green roof
Treated medium: direct of rainfall
Description of the solution: Copenhill Urban Mountain is a public space on the site of the incinerator building. SLA's design of a green rooftop park for Copenhagen's new waste-to-energy plant combines hiking trails, playgrounds, vantage points, climbing walls and runoff fitness – along with a 500 meter ski slope designed by BIG. All of it created within a wild mountain nature with plants, rockscapes, 7 000 bushes and 300 trees.

BASIC INFORMATION

Construction year: 2019
Constructor: BJARKE INGELS GROUP, SLA, ZINCO GMBH
Source of financing: governmental funds
Total cost: 670 000 000 \$
Facility operator: Amager Resource Center, Copenhagen Municipality
Maintenance cost: 600 000- 800 000\$ / year
Contact person: info@zinco-greenroof.com



Source: www.greenroofs.com/projects/copenhill



GEOGRAPHICAL COORDINATES

Latitude: 55° 41' 5" N
Longitude: 12° 37' 13" E

LOCATION

Country: Denmark
City: Copenhagen
Type of climate: Cfb
Average temperature: 8.9°C
Sum of precipitation: 728 mm



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆☆	☆☆☆☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+					+

TECHNICAL DATA

Area of the facility: 10 000 m²

Catchment area: 10 000 m²

Operating experience: Whirring furnaces, steam, and turbines convert 440,000 tons of waste annually into enough clean energy to deliver electricity and district heating for 150,000 homes.

ECOLOGICAL POTENTIAL

Copenhill Urban Mountain is a public space on the site of the incinerator building. In summer, the structure is expected to guarantee biodiversity and become a refuge for birds and insects.

ADVANTAGES

1. Its primary function is to harvest rainwater while at the same time rewilding a biodiverse landscape while absorbing heat, removing air particulates and minimizing stormwater runoff.

DISADVANTAGES

1. Probability of frequent device failures. They consume a significant amount of energy production.
2. The need to employ highly qualified staff, which is costly.



Source: www.greenroofs.com/projects/copenhill



Funded by the Horizon 2020 Framework Programme of the European Union

This document was prepared as a part of NICE Project by the technical team from Gdansk University of Technology



POCKET PARK

OBJECT INFORMATION

Name: Pocket Park - courtyard among Jedności Narodowej, Rychtalska and Ustronie street

Type of facility: pocket park

Treated medium: stormwater, urban runoff

Description of the solution: The pocket park was created in line with the GrowGreen project in cooperation with the city of Wrocław, financed from the EU budget of the HORIZON2020 project. The analyzed area is located in a district with an intense downtown development. The park was built in consultation with the habitants. The solutions proposed under construction are comprehensive. The investment was created in the "design and build" mode, avoiding many complexities related to the construction law. Monitoring conducted by the Wrocław University of Environmental and Life Sciences.



GEOGRAPHICAL COORDINATES

Latitude: 51° 7' 37.2" N

Longitude: 17° 2' 53.6" E

LOCATION

Country: Poland

City: Wrocław

Type of climate: Cfb

Average temperature: 10°C

Sum of precipitation: 700 mm

BASIC INFORMATION

Construction year: 2019

Constructor: GrowGreenWRO

Source of financing: UE HORIZON2020 Project

Total cost: 2300000€

Facility operator: City Hall in Wrocław

Maintenance cost: 3000€ / year

Contact person:

GrowGreenWRO@um.wroc.pl



Source: K. Ćwik / Agencja - wyborcza.pl

Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆☆	☆☆☆☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+					+

TECHNICAL DATA

Area of the facility: 1356 m²

Volume: Bioswale - 3 m³

Raingarden - 1.5 m³

Catchment: 3750 m²

Efficiency and effectiveness: high level of both due to visible changes

ECOLOGICAL POTENTIAL

The pocket park captures and purifies the surface runoff water. It improves the microclimate by reducing evaporation from the surface of the area. The facility reduces drought by infiltrating the deeper layers of soil.

ADVANTAGES

1. Short time of constructing the object.
2. Visible positive changes in the environment and functioning of the estate.
3. Pocket parks allow for comprehensive activities in land development.

DISADVANTAGES

1. The need for multi-sector cooperation.
2. No consistent slope of the terrain taking into account the direction of surface runoff into the basins of the facility.



Source: K. Ćwik / Agencja – wyborcza.pl



Funded by the Horizon 2020 Framework Programme of the European Union

This document was prepared as a part of NICE Project by the technical team from Gdansk University of Technology

TREE PITS



OBJECT INFORMATION

Name: Tree pits in Wrocław

Type of facility: tree pits

Treated medium: stormwater, urban runoff

Description of the solution: Water storage systems around trees are specialized substrates structural or additional modules (usually made of plastic) with a specialized substrate selected for them, built in the vicinity of trees. From these systems, there is water after rainfall is absorbed (soaked up) by tree roots under control of the system. A properly functioning system should have a positive effect on the system root of plants: reduce the problem of water stress, excessive soil compaction and its too small volume in relation to the roots' need.

BASIC INFORMATION

Construction year: 2013

Constructor: Green City Life

Total cost: 46000€

Facility operator: PKP S.A. Spatial Development Department in Wrocław

Maintenance cost: 4000€ / year

Contact person: Head of the Department of Spatial Development - Agnieszka Stopyra (agnieszka.stopyra@pkp.pl)

GEOGRAPHICAL COORDINATES

Latitude: 51° 05' 58.2" N

Longitude: 17° 02' 12.1" E

LOCATION

Country: Poland

City: Wrocław

Type of climate: Cfb

Average temperature: 10°C

Sum of precipitation: 700 mm



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆☆	☆☆☆☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+					+

TECHNICAL DATA

Area of the facility: 2000m²

Volume: 128m³(only tree pits)

Catchment: 10000m²

Retention capacity: 200l/m²

Efficiency and effectiveness: Water's pollutants removal - high efficiency

ECOLOGICAL POTENTIAL


Tree pits intercept rainwater and surface runoff, retaining it in the soil. For effective infiltration, high-permeability fillings are used, which allows water to be drained into the underground reservoir and reused.

ADVANTAGES

1. Quick and easy installation - no hardware repair required.
2. Limitation of fees for drainage of rainwater.
3. Compensation modules made of recyclable polypropylene.
4. Possibility of dismantling gratings around trees enabling to maintain system.

DISADVANTAGES

1. The use of elements of modular systems increases the cost of investment.
2. The average age of trees growing in the vicinity of built-up surfaces will be estimated at 7 years, while trees growing in green belts live on average 4 times longer.



General cross-section through pit:

1. concrete
2. metal grate
3. fertile soil
4. geotextile
5. anti-compression module
6. drainage layer
7. natural soil

Source: K. Lejuć et al.
„Katalog Dobrych Praktyk – drogi”



Funded by the Horizon 2020 Framework
Programme of the European Union

This document was prepared as a part of
NICE Project by the technical team from
Gdansk University of Technology

WILDFLOWER MEADOW FOR RUNOFF PURIFICATION



OBJECT INFORMATION

Name: Wildflower meadow at Gwiaździsta street in Wrocław

Type of facility: wildflower meadows

Treated medium: stormwater, surface runoff

Description of the solution: A flower meadow was created on the initiative of the residents of the estate. Annual and perennial plants have been sown. An alternative to classic grass lawns.



BASIC INFORMATION

Construction year: 2019

Constructor: Łąki Kwietne Business

Source of financing: local funds

Total cost: 5000 €

Facility operator: Housing Association of Wrocław-Południe

Maintenance cost: 1000€ / year

Contact person: Grzegorz Walkiewicz
grzegorz.walkiewicz@laka.org.pl

GEOGRAPHICAL COORDINATES

Latitude: 51° 05' 50'' N

Longitude: 17° 01' 18'' E

LOCATION

Country: Poland

City: Wrocław

Type of climate: Cfb

Average temperature: 10°C

Sum of precipitation: 700 mm



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆☆	☆☆☆☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+					+

TECHNICAL DATA

Area of the facility: 1000m²

Dominant plant species: Malva mauritiana, Calendula, Centaurea, Papaver, Coreopsis

Type of substrate: fertile brown soil

ECOLOGICAL POTENTIAL


A flower meadow increases a retention of the estate area. It cleans water and air through the presence of certain plant species. The flowers attract insects that pollinate plants.

ADVANTAGES

1. It does not require professional or demanding care.
2. Low financial cost.
3. The facility increases the retention capacity of the area.

DISADVANTAGES

1. Necessary watering from the water supply system during periods of drought.



Source: tuwroclaw.com



Funded by the Horizon 2020 Framework Programme of the European Union

This document was prepared as a part of NICE Project by the technical team from Gdansk University of Technology

RAIN GARDEN FOR ROOF RUNOFF



OBJECT INFORMATION

Name: Rain garden on Podgórze 6 street

Type of facility: rain garden

Treated medium: urban runoff

Description of the solution: The main purpose of the facility is to redirect the road and roof slope runoff from the drainage system to the designed construction. The runoff is directed through the downpipe from the front part of the roof through the green area separated by the existing road elements. This treatment relieves the city sewage system.



GEOGRAPHICAL COORDINATES

Latitude: 51° 45' 33.1" N

Longitude: 18° 4' 49.2" E

BASIC INFORMATION

Construction year: 2020

Constructor: Factory of water construction and land improvement BUDWIM

Source of financing: local funds

Total cost: 3600€

Facility operator: City Administration of Residential Buildings in Kalisz

Maintenance cost: 100€

Contact person: Izabela Grzeskiewicz, e-mail: igrzeskiewicz@um.kalisz.pl

LOCATION

Country: Poland

City: Kalisz

Type of climate: Cfb

Average temperature: 9.6 °C

Sum of precipitation: 666 mm



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆☆	☆☆☆☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+					+

TECHNICAL DATA

Area of the facility: 52m²

Volume: about 15.6m³

Catchment: 200m²

Primary design factor: $P_{max}=60\text{mm}$
lub volume of runoff 0.2/m²

Type of substrate: gravel, pebble,
wood chips(soil-making processes)

ECOLOGICAL POTENTIAL

The rain garden captures and purifies the surface runoff water. It improves the microclimate of the area by reducing evaporation from the surface of the area. The garden reduces drought by infiltrating the deeper layers of soil.

ADVANTAGES

1. Small area of investment. Costs are relatively low but change is valid.
2. The rain garden was made by people who had never done this type of projects before and manage it.
3. Limitation of fees for drainage of rainwater.

DISADVANTAGES

1. Lack of accurate calculations, i.e. volume of runoff, catchment area.
2. Lack of laboratory and scientific correlation to make some researches in chemistry, hydrologic, hydraulic and economic topics.



Source: supervisor of the Office of the Kalisz city Revitalization Izabela Grześkiewicz



Funded by the Horizon 2020 Framework
Programme of the European Union

This document was prepared as a part of
NICE Project by the technical team from
Gdansk University of Technology



RAIN GARDEN FOR STREET RUNOFF

OBJECT INFORMATION

Name: Rain garden at the intersection of Goszczyńskiego and Zakopiańska Street

Type of facility: rain garden

Treated medium: urban surface runoff

Description of the solution: The rain garden consists of seven cascades, it is fed by rainwater collected from the surface of the roadway. Three inlets in the curb allow surface runoff of rainwater to the facility, where it is collected and taken up by the root systems of planted plants. The inlets are in the form of a depression in the curb, a concrete drain trough, a curb with a drainage channel. On the road of the fortified inlet from the roadway there are transverse troughs, acting as a preliminary settling tank.



GDAŃSK

GEOGRAPHICAL COORDINATES

Latitude: 54° 20' 57.50" N

Longitude: 18° 36' 51.8" E

BASIC INFORMATION

Construction year: 2021

Constructor: Gdańskie Wody

Source of financing: urban investment

Total cost: 45 500€

Facility operator: Gdański Zarząd Dróg i Zieleni

Maintenance cost: 1000€ / year

Contact person: Magdalena Gajewska

(mgaj@pg.edu.pl) or

Agnieszka Kowalkiewicz

(a.kowalkiewicz@gdanskiewody.pl)

LOCATION

Country: Poland

City: Gdańsk

Type of climate: Cfb

Average temperature: 9 °C

Sum of precipitation: 511 mm



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆☆	☆☆☆☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+					+

TECHNICAL DATA

Area of the facility: 412 m²

Volume: 82,3 m³

Catchment: 8,5 ha

Efficiency and effectiveness: The facility fulfills the assumed functions of flood protection and drainage

Dominant plant species: Acorus calamus, Typha, Iris sibirica, Carex

ECOLOGICAL POTENTIAL


The garden provides habitats by increasing biodiversity. Flowering plants, butterflies and birds inhabiting the garden perform an aesthetic function. The regulatory function of the garden consists in cleaning the surface runoff (vegetation, settling tank) and delaying the outflow from the catchment.

ADVANTAGES

1. Effective delay of runoff from the catchment.
2. Preliminary treatment of water and relieving rainwater drainage.
3. Aesthetic values for residents of nearby housing estates.

DISADVANTAGES

1. Necessary operational works, ensuring patency of the inflow and proper development of plants.
2. Low probability of supplying all basins due to the large volumes of captured water in the first depressions in the facility.



Source: Gdańskie Wody Sp. z o.o.



Funded by the Horizon 2020 Framework
Programme of the European Union

This document was prepared as a part of
NICE Project by the technical team from
Gdansk University of Technology



RAIN GARDEN FOR STREET RUNOFF


OBJECT INFORMATION

Name: Box rain garden eMOCja center (9 Ugory Street)

Type of facility: cascade of box rain gardens

Treated medium: direct of rainfall

Description of the solution: The rain garden consists of three box gardens connected with cascades, it is fed by rainwater collected from the roof surface. In the last of the containers there is an emergency overflow. Excess water is directed to a nearby street. The facility collects rainwater, which relieves the municipal rainwater drainage system, has a positive effect on the microclimate. Next to the boxes there is a bench with an adjacent container for decorative greenery.



GEOGRAPHICAL COORDINATES

Latitude: 54° 21' 51.61" N

Longitude: 18° 41' 57.57" E

BASIC INFORMATION

Construction year: 2020

Constructor: Gdańskie Wody

Source of financing: urban investment

Total cost: 1 750€

Facility operator: Gdańskie Wody

Maintenance cost: 100€

Contact person: Magdalena Gajewska

(mgaj@pg.edu.pl)

or Agnieszka Kowalkiewicz

(a.kowalkiewicz@gdanskiewody.pl)

LOCATION

Country: Poland

City: Gdańsk

Type of climate: Cfb

Average temperature: 9 °C

Sum of precipitation: 420 mm



Source: Gdańskie Wody sp. z o.o.

Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆☆	☆☆☆☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+					+

TECHNICAL DATA

Area of the facility: 5 m²

Volume: 2,3 m³

Catchment: Polder area, pumping station to Martwa Wisła river

Efficiency and effectiveness: The facility fulfils the assumed functions

ECOLOGICAL POTENTIAL

The regulatory function of the garden is cleaning the surface runoff and delaying the outflow from the catchment. The supporting function is providing habitats. It has a positive effect on the biodiversity.

ADVANTAGES

1. Due to the location of the garden at the medical center, it can have a therapeutic function.
2. Rainwater retention in the landscape.
3. Increase in flood protection of the city.

DISADVANTAGES

1. Necessary operational works, ensuring i.e patency of the inflow and emergency overflow and plant care.



Source: Gdańskie Wody sp. z o.o.

Funded by the Horizon 2020 Framework Programme of the European Union


This document was prepared as a part of NICE Project by the technical team from Gdansk University of Technology



RAINGARDEN AND BIOSWALE FOR STREET RUNOFF

OBJECT INFORMATION

Name: Rain Garden and bioretention basin in Syracuse, NY
Type of facility: rain garden and bioswale
Treated medium: surface runoff
Description of the solution: The bioretention basin is situated between the sidewalk and existing tree line on the vacant lot parcel and is designed to capture stormwater from West Newell Street via existing catch basins. The drainage area extends on West Newell Street from Vale Street to Baldwin Avenue. The bioretention area is planted with native plants and serves as a community beautification feature as well as stormwater management.



GEOGRAPHICAL COORDINATES


Latitude: 43° 01' 62.2" N
Longitude: 76° 15' 57.3" W

BASIC INFORMATION

Construction year: 2017
Constructor: D.E. Tarolli Inc, J&J Landscaping, LLC
Source of financing: Commercial Building
Total cost: 93 645\$
Facility operator: City of Syracuse
Maintenance cost: 1000\$ / year
Contact person: Project Coordinator (jedwalsh@ongov.net)

LOCATION

Country: United States of America
City: Syracuse, NY
Type of climate: Dfb
Average temperature: 8.6 °C
Sum of precipitation: 1254 mm



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆☆	☆☆☆☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+					+

TECHNICAL DATA

Area of the facility: 320 m²

Volume: 250 m³

Catchment: 1913 m²

Efficiency and effectiveness: The facility fulfils the assumed functions of infiltration and outflow. Runoff reduction of 602 m³/year.

ECOLOGICAL POTENTIAL

The bioretention area serves as a community beautification feature as well as stormwater management. Five apple trees were also planted. All runoff from the block stretch of West Newell Street is drained into a green infrastructure practice, instead of the combined sewer system.

ADVANTAGES

1. Flood protection of communication routes nearby.
2. Integration of retention facilities with urban greenery.

DISADVANTAGES

1. Necessary operational works, ensuring i.e patency of the inflow and proper development of plants.



Source: savetherain.us



Funded by the Horizon 2020 Framework
Programme of the European Union

This document was prepared as a part of
NICE Project by the technical team from
Gdansk University of Technology



RAIN GARDEN ROOF RUNOFF


OBJECT INFORMATION

Name: Rain garden at Kaczeńce Street

Type of facility: rain garden

Treated medium: direct of rainfall

Description of the solution: The rain garden consists of many basins connected with an overflow. It is powered by runoff collected from the surface roofs' surface. The facility collects and infiltrates rainwater, which relieves the municipal rainwater drainage system, has a positive effect on biodiversity and microclimate. Excess water is directed by an emergency spillway to rainwater sewer network.



GEOGRAPHICAL COORDINATES

Latitude: 54° 21' 51.61" N

Longitude: 18° 41' 57.57" E

BASIC INFORMATION

Construction year: 2018

Constructor: Gdańskie Wody

Source of financing: urban investment

Total cost: 85 000€

Facility operator: Gdańskie Wody

Maintenance cost: 400€

Contact person: Magdalena Gajewska

(mgaj@pg.edu.pl)

or Agnieszka Kowalkiewicz

(a.kowalkiewicz@gdanskiewody.pl)

LOCATION

Country: Poland

City: Gdańsk

Type of climate: Cfb

Average temperature: 9 °C

Sum of precipitation: 420 mm



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆☆	☆☆☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+					+

TECHNICAL DATA

Area of the facility: 449m²

Volume: 224,5m³

Catchment: Polder area, pumping station to Martwa Wisła

Efficiency and effectiveness: The facility fulfils the assumed functions of flood protection and drainage

ECOLOGICAL POTENTIAL


Relieving the rainwater drainage system increases flood protection. The moistening of the soil increases, which improves the microclimate. The rain garden helps with sustainable rainwater management.

ADVANTAGES

1. Retention of rainwater in the landscape.
2. Preliminary treatment of water and relieving rainwater drainage.
3. Aesthetic value for residents of nearby housing estate.

DISADVANTAGES

1. Necessary operational works, ensuring i.e. patency of the inflow and proper development of plants.



Source: gdanskiewody.pl



Funded by the Horizon 2020 Framework
Programme of the European Union

This document was prepared as a part of
NICE Project by the technical team from
Gdansk University of Technology



RAIN GARDEN FOR ROAD RUNOFF

OBJECT INFORMATION

Name: Rain garden at 3 Maja street, Gdańsk

Type of facility: rain garden

Treated medium: direct of rainfall

Description of the solution: The RG consists of three independently supplied basins connected by cascades. It is powered by rainwater collected from the surface of the roadway. Three inlets in the curb allow to discharge rainwater surface runoff to the facility, where it is collected and transported through the root systems of planted vegetation.

BASIC INFORMATION

Construction year: 2020

Constructor: Gdańskie Wody

Source of financing: city funds

Total cost: 55 500 €

Facility operator: Gdański Zarząd Dróg Zieleni

Maintenance cost: 1 500 €

Contact person: Magdalena Gajewska

(mgaj@pg.edu.pl);

Agnieszka Kowalkiewicz

(a.kowalkiewicz@gdanskiewody.pl)



GEOGRAPHICAL COORDINATES

Latitude: 54° 20 '55.3" N

Longitude: 18° 38 '31.2" E

LOCATION

Country: Poland

City: Gdańsk

Type of climate: Cfb

Average temperature: 9 °C

Sum of precipitation: 449 mm



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆☆	☆☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+					+

TECHNICAL DATA

Area of the facility: 758,7m²

Volume: 98,2m³

Primary design factor: P_{\max} (p=10%, t=45min) = 30mm

Efficiency and effectiveness: The facility fulfills the assumed functions of flood protection and drainage.

ECOLOGICAL POTENTIAL


The infiltration process taking place in the basins improves the state of soil moisture, which affects the cooling of the nearby environment, which is especially desirable during the increasingly frequent heat, which is the result of climate change.

ADVANTAGES

1. Flood protection of communication routes.
2. Pre-treatment of water and relieving rainwater drainage.
3. Integration of retention facilities with urban greenery.

DISADVANTAGES

1. Necessary operational works, ensuring the patency of the inflow and proper development of plants.
2. Road salts used in winter can destroy vegetation.



Source: Gdańskie Wody



RAIN GARDEN FOR PARKING LOT RUNOFF

OBJECT INFORMATION

Name: Rain garden at O'Rourke Street

Type of facility: rain garden

Treated medium: surface runoff (from the nearby surfaces)

Description of the solution: The rain garden consists of 2 flow basins. It is fed by rainwater collected from the surface of sidewalks, parking lots and streets. The facility collects and infiltrates rainwater, which relieves the municipal rainwater drainage system. It has a positive effect on biodiversity, microclimate and protects nearby residential buildings from flooding.

BASIC INFORMATION

Construction year: 2018

Constructor: Gdańskie Wody

Source of financing: city funds

Total cost: 21 200 €

Facility operator: Gdański Zarząd Dróg i Zieleni

Maintenance cost: 1500 € / year

Contact person: Magdalena Gajewska (mgaj@pg.edu.pl); Agnieszka Kowalkiewicz (a.kowalkiewicz@gdanskiewody.pl)



GEOGRAPHICAL COORDINATES

Latitude: 54° 22' 58.96" N

Longitude: 18° 37' 32.44" E

LOCATION

Country: Poland

City: Gdańsk

Type of climate: Cfb

Average temperature: 9 °C

Sum of precipitation: 517 mm



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆☆	☆☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+					+

TECHNICAL DATA

Area of the facility: 200,86m²

Volume: 56,3m³

Primary design factor: $P_{\max}(p=10\%, t=45\text{min})=30\text{mm}$

Efficiency and effectiveness:

The facility fulfills the assumed functions of flood protection and drainage.

ECOLOGICAL POTENTIAL


Reduced evaporation resulting from decrease in ambient temperature has a positive effect on the water balance. The load of pollution from surface runoff is taken over by the small retention object, and the water is subjected to sub-purification process.

ADVANTAGES

1. Infiltration of the rainwater into the ground.
2. Preliminary treatment of water and relieving rainwater drainage.
3. Reduction of the temperature of the environment during summer months (improving microclimate).

DISADVANTAGES

1. Necessary operational works, ensuring eg. patency of the inflow and proper development of plants.
2. Road salts used in winter can destroy vegetation.



Source: Gdańskie Wdoy



Funded by the Horizon 2020 Framework Programme of the European Union

This document was prepared as a part of NICE Project by the technical team from Gdansk University of Technology



RAIN GARDEN FOR PARKING RUNOFF

OBJECT INFORMATION

Name: Rain garden on Stryjewskiego at 13 Street

Type of facility: rain garden

Treated medium: surface runoff

Description of the solution: The rain garden consists of a depression in the terrain with plantings of properly selected plants. It is sustained with rainwater collected from the surface of the parking lot. It does not have an emergency spillway to the rainwater drainage. The facility collects and purifies rainwater, which relieves the urban rainwater drainage system.



GEOGRAPHICAL COORDINATES

Latitude: 54° 21' 35.65" N

Longitude: 18° 42' 29.94" E

BASIC INFORMATION

Construction year: 2018

Constructor: Gdańskie Wody

Source of financing: city funds

Total cost: 12 600 €

Facility operator: Gdański Zarząd Nieruchomości Komunalnych

Maintenance cost: 1 500 € / year

Contact person: Magdalena Gajewska (mgaj@pg.edu.pl); Agnieszka Kowalkiewicz (a.kowalkiewicz@gdanskiewody.pl)

LOCATION

Country: Poland

City: Gdańsk

Type of climate: Cfb

Average temperature: 9 °C

Sum of precipitation: 420 mm



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆☆	☆☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+					+

TECHNICAL DATA

Area of the facility: 150 m²

Volume: 35 m³

Primary design factor: $P_{\max}(p=10\%, t=45\text{min})=30\text{mm}$

Efficiency and effectiveness:

The facility fulfils the assumed functions of flood protection and drainage.

ECOLOGICAL POTENTIAL

The load of pollution from the runoff on the surface of the parking lots is taken over by the low retention facility. The water is subjected to the process of sub-purification. Vegetation can contribute to increasing infiltration and reducing evaporation.

ADVANTAGES

1. Effective drainage of the parking lot.
2. Preliminary treatment of water and relieving rainwater drainage.
3. Aesthetic value for residents of a nearby housing estate.

DISADVANTAGES

1. Necessary operational works, ensuring i.e patency of the inflow and proper development of plants.
2. Road salts used in winter can destroy vegetation.



Source: Gdańskie Wody



Funded by the Horizon 2020 Framework
Programme of the European Union

This document was prepared as a part of
NICE Project by the technical team from
Gdansk University of Technology



GREEN PARK

OBJECT INFORMATION

Name: University of Toronto
Scarborough Campus Valley Land Trail
Type of facility: green park
Treated medium: surface runoff
Description of the solution: It is a 500m long trail that provides safe and easy access to the Highland Creek watershed. The trail balances environmental and social responsibility through universally accessible and inclusive design. Also it provides opportunity for engagement and study, serving as a foraging site for the university's culinary program and a living laboratory for natural science programs. Deemed an environmentally unique habitat by the Toronto Regional Conservation Authority



GEOGRAPHICAL COORDINATES

Latitude: 43° 47' 05" N
Longitude: 79° 11' 19" W

BASIC INFORMATION

Construction year: 2019
Constructor: Brown&Company Engineering
Source of financing: University funds
Total cost: 2 500 000\$
Facility operator: University of Toronto Scarborough Campus
Maintenance cost: 30 000 – 50 000\$
Contact person: Jenny Hill
(researchgate.net/profile/Jenny-Hill-2)

LOCATION

Country: Canada
City: Toronto
Type of climate: Dfb
Average temperature: 8.7 °C
Sum of precipitation: 845 mm



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆☆	☆☆☆☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+					+

TECHNICAL DATA

Area of the facility: 20 000 m²

Dominant plant species:

trees: *Aspen, White Oak*;

bushes: *native fruit shrubs*

Operating experience: Projected to intercept over 6 800 m³ of stormwater over the next 20 years (from 2019)

ECOLOGICAL POTENTIAL

Edible plant species can be found in the park. Through many planted trees and shrubs, the facility captures large amounts of CO₂ and constitutes a flood barrier for the campus. The facility is a habitat for many species of wild animals, which increases species diversity.

ADVANTAGES

1. Park serve as havens for various plant, animal, and insect species, fostering biodiversity in urban areas
2. plants in the park absorb carbon dioxide (CO₂) and other pollutants from the air.

DISADVANTAGES

1. Park require regular maintenance, including landscaping, irrigation, and waste management
2. Large park areas on university campuses may limit available space for infrastructure expansion



Source: landezine.com/university-of-toronto-scarborough-valley-land-trail-by-schollen-and-company



Funded by the Horizon 2020 Framework Programme of the European Union

This document was prepared as a part of NICE Project by the technical team from Gdansk University of Technology



RETENTION RESERVOIR

OBJECT INFORMATION

Name: Mściwojów Reservoir

Type of facility: Retention and flood control tank with biological water purification function

Treated medium: Floodplain waters from the Wierzbak and Zimnik rivers, surface runoff waters from the catchment

Description of the solution: The water reservoir in Mściwojów was built on the Wierzbak and Zimnik rivers. There is a unique self-purification system on a European scale, consisting in the creation of natural backwaters overgrown with special vegetation, which filter the water of the pre-reservoir flowing into the reservoir.



GEOGRAPHICAL COORDINATES

Latitude: 51° 01' 40"N

Longitude: 16° 16' 35"E

BASIC INFORMATION

Construction year: 1991

Constructor: "BUDEX" s.c in Lublin

Source of financing: local funds

Total cost: 6 000 000 €

Facility operator: Polish Waters; branch of the Legnica Catchment Board

Maintenance cost: 6 000-10 000€ / year

Contact person: Jan Kazak UPW

(jan.kazak@upwr.edu.pl)

Agnieszka Najdecka - Polish Waters

(agnieszka.najdecka@wody.gov.pl)

LOCATION

Country: Poland

City: Mściwojów

Type of climate: Cfb

Average temperature: 10 °C

Sum of precipitation: 700 mm



Source: J.Dąbrowska „Mściwojów Reservoir – study of small retention reservoir with an innovative water self-purification system”

Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆	☆☆	☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+					

TECHNICAL DATA

Area of the facility: 345900 m²
Volume: maximum 1.35 million m³
Catchment: 47 km²
Average Hydraulic Retention Time: 65 days
Operating experience: Wide range of works during operation (periodic and commission inspections, maintenance, current repairs, overhauls).

ECOLOGICAL POTENTIAL


It treats the contaminated waters and municipal sewage, which will go to the surface runoff and the ground through the infiltration process. Due to the agricultural purpose of the land near and the possibility of fishing in this area, the reservoir "produces" food.

ADVANTAGES

1. The building purifies water from heavy metals, biogenic compounds and others by filtration in the ground.
2. Increasing soil retention in areas directly adjoined to the reservoir, and stabilizing the depth of the water table in up to 50m from the reservoir.

DISADVANTAGES

1. Complex design - large technical parameters of the tank (cubic capacity, size of the catchment, etc.).
2. A difficult aspect of maintaining the stability of the building - ensuring safety against flooding of nearby areas.



Source: J. Dąbrowska „Shore zone in protection of water quality in agricultural landscape – the Mściwojów Reservoir, southwestern Poland”



Funded by the Horizon 2020 Framework Programme of the European Union

This document was prepared as a part of NICE Project by the technical team from Gdansk University of Technology

HSSF FOR TREATMENT OF STORMWATER FROM FARMYARD



OBJECT INFORMATION

Name: Treatment wetland in Mezaciruli

Type of facility: TW

Treated medium: surface runoff

Description of the solution: A pilot-scale SSHF TW was installed at the farm Mezaciruli to improve stormwater quality collected from the farmyard and demonstrate applicability of TW as a convenient treatment option for contaminated surface runoff. The system consists of a sedimentation pond as a pretreatment plant, a water pump, a water distribution well, and a horizontal subsurface flow TW with the surface area of 160 m².

BASIC INFORMATION

Construction year: 2014

Constructor: farm Mezaciruli

Source of financing: Project NUTRINFLOW (Interreg Central Baltic Programme 2014-2020)

Total cost: 240 000 €

Facility operator: farm Mezaciruli

Maintenance cost: 5 000 € / year

Contact person: Juris Cirulis

(www.celotajs.lv)



GEOGRAPHICAL COORDINATES

Latitude: 56 34' 27.7" N

Longitude: 23° 29' 38.9" E

LOCATION

Country: Latvia

City: Zalenieki county, Jelgava region

Type of climate: Dfb

Average temperature: 6.8 °C

Sum of precipitation: 671 mm



Source: J. Cirulis



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆	☆☆☆	☆☆☆☆☆

TECHNICAL DATA

Area of the facility: 4000 m²

Catchment: 74000 m²

Volume: 5400 m³

Hydraulic and hydrological data:

Average concentration of suspended solids at the inlet was 83.36 mg/L.

Effectiveness and efficiency: Color and turbidity of the incoming water visually differs from the water leaving the wetland, which are the parameters that indicate a better quality of the treated medium.

UCC

1	2	3	4	5	6	7
+	+					

ECOLOGICAL POTENTIAL


This facility cleans the water of solid particles and purifies the air through the presence of dense flora. It also absorbs nitrogen and phosphorus compounds and is a storehouse for silt. Moreover, it delays the peak of the flood wave. The site is a habitat for many animal species (mainly birds and insects).

ADVANTAGES

1. Contributes to the reduction of plant nutrients and suspended matter in runoff from agricultural lands.
2. The facility reduces the risk of flooding as it receives a significant part of surface runoff.

DISADVANTAGES

1. Dredging the bottom of the reservoir once a year results in high costs, large logistics and projects.
2. For water supply in the case of construction of an underground flow wetland the use of a water pump may be necessary, which causes additional operating expenses.



Source: L. Grinberga



Funded by the Horizon 2020 Framework Programme of the European Union

This document was prepared as a part of NICE Project by the technical team from Gdansk University of Technology

BUFFER POND AND TREATMENT WETLAND




OBJECT INFORMATION

Name: The Servier Laboratories WWTP

Type of facility: Buffer pond and TW

Treated medium: stormwater, surface runoff

Description of the solution: This treatment system was designed to treat stormwater (12 000 m³) using a buffer pond followed by a vertical flow constructed wetland for the treatment of runoff water before discharging it in the receiving body.



BASIC INFORMATION

Construction year: 2013/2014

Constructor: SOGEA Nord Ouest;

Designer: EcoBIRD

Source of financing: Servier laboratories

Total cost: 900 000 € (excl. VAT)

Facility operator: The Servier Laboratories

Maintenance cost: < 8 000 € per year (incl. VAT)

Contact person: Stéphane Troesch
(s.troesch@ecobird.fr)

GEOGRAPHICAL COORDINATES

Latitude: 47°58'36.3"N

Longitude: 1°50'52.6"E

LOCATION


Country: France

City: Gidy (district: Centre-Val de Loire)

Type of climate: Cfb

Average temperature: 11°C

Sum of precipitation: 645 mm



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
-	☆☆☆☆	☆☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+					

TECHNICAL DATA

Area of facility: 13 600 m² in total

Pond: 11 000 m²; VFCW: 2 600 m²

Catchment area: 23 000 m²

Volume: 24 340 m³ in total

Pond: 22 000 m³; VFCW: 2 340 m³

Water flow: Treatment of 100-year rainfall: 12000 m³


Efficiency and effectiveness of facility:

guaranteed discharge levels and removal rates: BOD₅ = 7 mg/L or 70 %; COD = 30 mg/L or 65 %; TSS = 25 mg/L or 90 %; TN = 3 mg/L; TP = 0.7 mg/L; Pb = 1 mg/L or 65 %; Total hydrocarbons = 1 mg/L or 70 %

Operating experience: simple maintenance and operation

ECOLOGICAL POTENTIAL

The treatment system provides ecosystem services such as water purification, nutrient cycling, habitat for insects and aesthetic value.



ADVANTAGES

1. Simple and efficient surface water runoff management and treatment.
2. Limited Maintenance constraints and costs.

DISADVANTAGES

1. Land availability.

Source: S. Troesch



Funded by the Horizon 2020 Framework Programme of the European Union

This document was prepared as a part of NICE Project by the technical team from Gdansk University of Technology



HSVF TW in Bogota

OBJECT INFORMATION

Name: TW in Bogota

Type of facility: HSVF

Treated medium: urban runoff

Description of the solution: This project stays within the framework of the University's (Facultad de Ingeniería, Pontificia Universidad Javeriana) environmental management plan of its physical resources office. To gauge the system's performance (its hydraulic attenuation), it is monitored by means of two triangular sharp-crested weirs, a series of piezometers and ultrasonic level sensors. The location of the weirs is: the entrance of settling tank and the exit of the facility. Initial results showed that the TW delays runoff hydrographs between 11 and 53 minutes, outflow runoff peaks vary between 37% and 78% of those observed for inflow. The facility retains up to 46% of total rainfall volume.

LOCATION

Country: Colombia

City: Bogotá

Type of climate: Am

Average temperature: 13.1°C

Sum of precipitation: 797 mm



GEOGRAPHICAL COORDINATES

Latitude: 4° 35' 56" N

Longitude: 74° 04' 51" E

BASIC INFORMATION

Construction year: 2013

Constructor: INDRACOL S.A.S


Source of financing: internal funds

Facility operator: Pontificia Universidad Javeriana

Total cost: 315 569 \$

Maintenance cost: 619 \$

Contact person: Maria Angelica Suarez
(m.suarezj@javeriana.edu.co)



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆	☆☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+					

TECHNICAL DATA

Area of the facility: 85 m²

Volume: 145 m³

Catchment: 18 942 m²

Efficiency and effectiveness: At the outlet of the TW/RT there is evidence of a decrease in turbidity SST and BOD₅, however, no changes have been found for chlorides and TDS.

ECOLOGICAL POTENTIAL

Making researches about: wastewater inflow and outflow, efficiency of the NBS. Increasing biodiversity by planting some plants where a lot of creatures have good living conditions. The facility improves the microclimate of the environment and captures biogenic and carbon compounds. It purificates the runoff.

ADVANTAGES

1. The outlet water meets the requirements to be used for washing surfaces.

DISADVANTAGES

1. The water that arrives from the soccer field does not have the expected quality.



Source: S.Galarza-Molina et al.
„Constructed-
Wetland/Reservoir-Tank
system Used for Rainwater
Harvesting in Bogota,
Colombia”



Funded by the Horizon 2020 Framework
Programme of the European Union

This document was prepared as a part of
NICE Project by the technical team from
Gdansk University of Technology



TREATMENT WETLAND FOR AGRICULTURE

OBJECT INFORMATION

Name: TW Treating Agricultural Drainage Water in Northern Italy

Type of facility: FWS

Treated medium: agricultural runoff

Description of the solution: The study was carried out on a non-waterproofed pilot scale TW located on an experimental agricultural farm of the Canale Emiliano Romagnolo. The NBS treats tile drainage water coming from a 12.5 ha experimental farm that grows different crops eg. fruit trees, vegetables, and cereals. The area of the FWS represents around 3% of the total farm surface, and it is divided into four 8–10 m wide meanders that create a 470-m-long water course.



GEOGRAPHICAL COORDINATES

Latitude: 44° 34' 22" N

Longitude: 11° 31' 44" E

BASIC INFORMATION

Construction year: 2001

Constructor: Green4Water

Source of financing: Ministry of Education, University and Research in Italy

Total cost: 100 000 €

Facility operator: Canale Emiliano Romagnolo

Maintenance cost: 7 000 € / year

Contact person: Stefano Anconelli
(anconelli@consorziocer.it)

LOCATION

Country: Italy

City: Bologna

Type of climate: Cfa

Average temperature: 14.3 °C

Sum of precipitation: 825 mm



Source: S.Lavarnic et al. „Long-Term Monitoring of a Surface Flow Constructed Wetland Treating Agricultural Drainage Water in Northern Italy”

Source: I. Braschi et al. „Miglioramento della qualità dell'acqua tramite fitodepurazione delle acque dei reticoli permiscui”

Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆	☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+					

TECHNICAL DATA

Area of the facility: 5850 m²

Catchment: 125 000 m²

Volume: 1500 m³

Dominant plant species: *Phragmites australis*, *Typha latifolia*, *T. angustifolia*, *Salix alba*, *Populus alba*

Operating experience: The operation of the SFCW depends mostly on the frequency and volume of precipitation.

ECOLOGICAL POTENTIAL


Wastes from the facility are used to grow plants. Moreover, the planted species of reeds help the biodiversity. The facility improves the microclimate of the environment and captures biogenic and carbon compounds.

ADVANTAGES

1. The water flow in the system is gravitational and therefore operating costs are low, especially since only occasional maintenance works are needed every few weeks.

DISADVANTAGES

1. Two pumps convey water from the ditch towards the inlet once water in the ditch reaches a certain level. Probability of clogging the pumps.



Source: I. Braschi et al. „Miglioramento della qualità dell'acqua tramite fitodepurazione delle acque dei reticoli pormiscui”



Funded by the Horizon 2020 Framework
Programme of the European Union

This document was prepared as a part of
NICE Project by the technical team from
Gdansk University of Technology



FLOATING TREATMENT WETLAND ISLANDS


OBJECT INFORMATION

Name: FWI in Durham(NC), USA

Type of facility: FWI

Treated medium: surface runoff

Description of the solution: FWIs are hydroponic systems that fully vegetated are essentially wetlands that float on the surface of open water. To test whether FWIs provide a benefit for nutrient and TSS removal, two ponds in Durham. In late March 2010, FWIs were installed as retrofits at both the “Museum” pond and “DOT” pond. FWIs act as a hydroponic system, with the plants and microbes that inhabit the plant roots taking nutrients from the stormwater.



GEOGRAPHICAL COORDINATES

Latitude: 36° 02' 93" N

Longitude: 78° 89' 94" W

BASIC INFORMATION

Construction year: 2010

Constructor: NCDENR – Division of Water Quality

Source of financing: partly NCDENR – 95 000\$, governmental funds- rest

Total cost: 182 355 \$

Facility operator: The North Carolina Department of Environmental Quality

Maintenance cost: 2 000 \$

Contact person: Ryan J. Winston
(winston.201@osu.edu)

LOCATION

Country: United States of America

City: Durham, NC

Type of climate: Cfa

Average temperature: 15.7°C

Sum of precipitation: 1136m



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆	☆☆	☆☆☆

UCC

1	2	3	4	5	6	7
+	+					

TECHNICAL DATA

Area of the facility: 370 m²(FWIs);
3 600 m²(FWIs+surface water)
Volume: 92 m³
Catchment area: 15 500 m²
Hydraulic load: 45 l/day
Operating experience: The museum pond with FWI has significantly reduced contrecation of all pollutants studied.
Dominant plant species: *Carex stricta*, *Juncus effusus*, *Spartina pectinata*

ECOLOGICAL POTENTIAL

The facility improves the above-water ecosystem, while the roots provided submerged habitat. Also the systems take up excess agricultural nutrients. Minimizing algal blooms and dead zones. Research suggests they can be used to reduce manmade contaminants that persist in the environment.

ADVANTAGES

1. No need for additional land to be used for treatment.
2. Do not detract from the required storage volume.

DISADVANTAGES

1. Prior water quality tests must be carried out.
2. The efficiency of the facility is based on appropriated plant choice.

Museum Pond



DOT Pond



Source: William F. Hunt et al. „Evaluation of Floating Wetland Islands (FWIs) as a Retrofit to Existing Stormwater Detention Basins”



Funded by the Horizon 2020 Framework
Programme of the European Union

This document was prepared as a part of
NICE Project by the technical team from
Gdansk University of Technology




FLOATING TREATMENT WETLAND

OBJECT INFORMATION

Name: FTW in Fairfax, Virginia
Type of facility: FTW
Treated medium: stormwater urban runoff
Description of the solution: This project adapted a standard water quality retrofit of a wet pond on Ashby Road in Fairfax, Virginia to incorporate evaluation of FTWs as a potential new treatment technology. FTWs improve water quality by removing nutrients through plant uptake, microbial uptake, and increased sedimentation. Four treatments with three replicates following a completely randomized block design were installed to evaluate effects of the floating mats and different plant species in the FTW mesocosm system. The four treatments included control, un-vegetated floating mat, pickerelweed, and softstem bulrush.

BASIC INFORMATION

Construction year: 2009-2013
Constructor: City of Fairfax Parks and Recreation
Source of financing: project – National Fish and Wildlife Foundation
Total cost: 330 000\$
Facility operator: City of Fairfax Parks and Recreation
Maintenance cost: 3 500-5 000\$ / year
Contact person: City of Fairfax Park and Recreation (fairfax.gov/government/park-recreation)




GEOGRAPHICAL COORDINATES

Latitude: 38° 50' 51" N
Longitude: 77° 17' 10" W

LOCATION

Country: United States of America
City: Fairfax, VA
Type of climate: Cfa
Average temperature: 13.6 °C
Sum of precipitation: 1075 mm



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆	☆☆	☆☆☆

UCC

1	2	3	4	5	6	7
+	+					

TECHNICAL DATA

Area of the facility: 8000 m²

Catchment: 566 560 m²

Dominant plant species: *Pontederia cordata* L., *Schoenoplectus tabernaemontani*

Efficiency and effectiveness: The values are less than the afforded credits for TP (50%) and TN (50%) currently assigned to wet ponds by the Virginia Stormwater BMP Clearinghouse (Virginia Department of Environmental Quality 2013).

ECOLOGICAL POTENTIAL


The floating treatment wetland allows for purification of water. Moreover, it is a great facility that increases the biodiversity of Fairfax city. It allows for ecotourism and recreation. Additionally, it is a great place for school excursions.

ADVANTAGES

1. Promising potential results – removal of 10 tons of sediment per year.

DISADVANTAGES

1. Low efficiency ratio leading to a disappointing performance of the facility.



Source: nfwf.org/sites/1884_Final_Report



Funded by the Horizon 2020 Framework Programme of the European Union

This document was prepared as a part of NICE Project by the technical team from Gdansk University of Technology

FLOATING TREATMENT WETLAND



OBJECT INFORMATION

Name: BioHaven floating island at Hyde Park, UK

Type of facility: FTW

Treated medium: surface water

Description of the solution: As part of a programme of wildlife habitat improvements in the Royal Parks, a large FTW has been built on the Serpentine Lake in London's Hyde Park. Ecologists and landscapers worked with Salix bio-engineers to install a 200 m² island in the southern lake to clean the lake's water naturally. The FTW on the Serpentine will help to improve the water quality in a chemical free way and provide habitat and food for a variety of wildlife including insects, waterfowl and amphibians.



GEOGRAPHICAL COORDINATES

Latitude: 51° 30' 19" N

Longitude: 0° 10' 05" W

BASIC INFORMATION

Construction year: 2013

Constructor: Salix river & Wetland Services Ltd.

Source of financing: government funds

Total cost: 800 000 €

Facility operator: The Royal Parks

Maintenance cost: 3 000-5 000 € / year

Contact person: Leela O'Dea

(leela@frogenvironmental.co.uk)

LOCATION

Country: England

City: London

Type of climate: Cfb

Average temperature: 10.8°

Sum of precipitation: 690mm



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆	☆☆	☆☆☆

UCC

1	2	3	4	5	6	7
+	+					

TECHNICAL DATA

Area of the facility: 200 m²

Volume: 160 m³

Operating experience: BioHaven FTW mimics the environmental benefits of wetlands in the natural world. At the bottom of the chain, microscopic organisms will build-up naturally, becoming a biofilm on the surface of the island, cleaning the water and providing food for the zooplankton, micro and macro invertebrates like dragonfly nymphs and snails, and further up the chain, food for the fish.

Dominant plants species: sedge, iris, rush, mint, purple loosestrife

ECOLOGICAL POTENTIAL

The facility rapidly improved the area of provided habitat, which in turn boosted the biodiversity. The root systems of the plants on the floating islands also process excess nutrients in polluted waters. This improves water quality and the wider aquatic habitat for insects and fish.

ADVANTAGES

1. The islands provide a beautiful and diverse habitat.
2. Recycling and reusing materials.

DISADVANTAGES

1. Prior water quality tests must be carried out.
2. Concern about water contamination with microplastics (referring to the latest research).



Source: salixrw.com/wetland-habitat-creation/royal-parks-serpentine-lake



Funded by the Horizon 2020 Framework
Programme of the European Union

This document was prepared as a part of
NICE Project by the technical team from
Gdansk University of Technology





IN-STREAM RESTORATION - BUFFER ZONES

OBJECT INFORMATION

Name: Meadow Creek Stream Restoration

Type of facility: Buffer zone

Treated medium: Surface water

Description of the solution: The project consisted of 2.75 linear kilometers of stream restoration and the conservation of 300 000 m² as easement land, of which 160 000 m² are new public parkland. The main goals of this project are to: decrease sedimentation, improve stability, improve habitat, enhance surrounding forest, protect infrastructure, and create educational and recreational opportunities. The restoration design followed the natural channel approach to establish a dynamically meandering pattern to reconnect the stream with its flood plain and reduce bank erosion and sedimentation.



CHARLOTTESVILLE, VA

GEOGRAPHICAL COORDINATES

Latitude: 38° 03' 45" N

Longitude: 78° 29' 01" W

LOCATION

Country: USA

City: Charlottesville, VA

Type of climate: Cfa

Average temperature: 13.8°C

Sum of precipitation: 1047m

BASIC INFORMATION

Construction year: 2013

Constructor: Vanasse Hangen Brustlin, Inc. ,
Coastal Design and Construction, Inc.

Source of financing: Foundation- VIRGINIA
The Nature Conservancy

Total cost: 4 000 000\$

Facility operator: The City of Charlottesville

Maintenance cost: 18 000-35 000\$ / year

Contact person: Dana Kasler

(kaslera@charlottesville.gov)



Source: landscapeperformance.org/case-study-briefs/meadow-creek-stream-restoration

Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆☆	☆☆☆☆	☆☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+			+		

TECHNICAL DATA

Area of the facility: 300 000 m² as easement land; 2.75 linear kilometers of stream restoration

Catchment area: around 25 km²

Efficiency and effectiveness : Bank Erosion Hazard Index(BEHI: method for assessing stream bank erosion potential)- sediment loading was reduced by 1 790 tons per year.

ECOLOGICAL POTENTIAL

The natural resources contained in the facility are the source of ornaments and decorations. The vegetation planted during the works purifies the air and increases the biodiversity of the area attracts bees that pollinate plants, the flora becomes a shelter for many animals.

ADVANTAGES

1. This project is improving the creek and forest health with better water quality.

DISADVANTAGES

1. No disadvantages have been noted during the operation of the plant.



Source: : landscapeperformance.org/case-study-briefs/meadow-creek-stream-restoration



Funded by the Horizon 2020 Framework Programme of the European Union

This document was prepared as a part of NICE Project by the technical team from Gdansk University of Technology





IN-STREAM RESTORATION - BUFFER ZONES

OBJECT INFORMATION

Name: Tassajara Creek Restoration
Type of facility: Buffer zones
Treated medium: Surface water
Description of the solution: The project sought to stop chronic incision caused by years of grazing along a one-mile stretch of the creek in an area where significant development was anticipated. In 1998, after much consultation with the state-owned entities and geomorphologists, the Authority began construction of a compound channel with two reaches of low-flow channels and flood terraces planted with native vegetation for higher flows. The restored creek conveys 100-year flood waters, supports the local ecosystem, and serves as an amenity for the surrounding housing developments, sporting a mile-long trail that connects to local parks and the East Bay Regional Trail network.



GEOGRAPHICAL COORDINATES

Latitude: 37° 42' 31" N
Longitude: 121° 52' 46" W

LOCATION

Country: United States of America
City: Dublin, CA
Type of climate: Csc
Average temperature: 13.5° C
Sum of precipitation: 581mm

BASIC INFORMATION

Construction year: 1999
Constructor: RGW Construction
Source of financing: project funds – Smith Group
Total cost: 5 000 000\$
Facility operator: Alameda County surplus Property
Maintenance cost: 18 000 – 35 000\$ / year
Contact person: Miw Lehrer
(info@studio-mla.com)



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆	☆☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+			+		

TECHNICAL DATA

Area of the facility: 14 000 m²

Catchment area: 60 km²

Primary design factor: Downstream reach: the entire channel was reconstructed with a low-flow channel designed to convey the 2-year flow (14-18 m³/s) before overtopping onto the floodplain terrace designed to convey the 100-year flow.

Efficiency and effectiveness: The facility has been operating flawlessly since 1999. The assumptions made at the beginning of the project were 100% implemented.

ECOLOGICAL POTENTIAL

The purpose of the TW is to purify surface water from the urbanized and agricultural wasted district, which reduces the risk of bloom in the river. Moreover, it is a meeting place for natives, where they can rest and relax.

ADVANTAGES

1. Prevented 159 m³ of concrete from entering a landfill by repurposing material from a former military bridge and a drop structure as buried riprap along the channel.

DISADVANTAGES

1. Miscommunication between project planners and those tasked with maintaining the site after project completion initially led to excessive trimming of riparian vegetation along the channel.



BEFORE



AFTER

Source: landscapeperformance.org/case-study-briefstassajacreek-restoration



Funded by the Horizon 2020 Framework Programme of the European Union

This document was prepared as a part of NICE Project by the technical team from Gdansk University of Technology





RESTORATION OF NATURAL WETLAND

OBJECT INFORMATION

Name: Aarslev Restored Wetland

Type of facility: Restoration of Natural Wetland

Treated medium: Surface Water

Description of the solution: The Aarslev wetland area has been cultivated and drained for agricultural purposes for over a century. Over time, cultivation of the fields became increasingly challenging due to soil flooding, making it politically and operationally acceptable to construct a natural wetland on the area. The purpose of reconstructing the wetland was to decrease the amount of nitrate reaching Aarhus Bay where oxygen depletion has caused several events of fish death. By stopping the agricultural activities and drainage, the meadows of the area were wetted and flooded and the site is now classified as a Nature 2000 and EU habitat area. The flooded meadows provide several ecosystem services by reducing the nutrient content of the water before reaching the bay, support of wildlife and function as recreational area outside the city. Birdwatching towers, paths for hiking and bikes, information boards and rest places have been installed along the banks to allow leisure activities.

BASIC INFORMATION

Construction year: 2003

Constructor: Aarhus County, Municipality of Aarhus

Source of financing: Water plan II, Municipality of Aarhus

Total cost: 2,455,079.40 €

Contact person: Carlos A. Arias
(carlos.arias@bio.au.dk)

Source: Carlos A. Arias

AARHUS



GEOGRAPHICAL COORDINATES

Latitude: 56°08'29.9"N

Longitude: 10°04'08.6"E

LOCATION

Country: Denmark

City: Aarhus

Type of climate: Cfb /Dfb

Average temperature: 8.4 °C

Sum of precipitation: 897 mm



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆	☆☆☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+			+		

TECHNICAL DATA

Area of the facility: 117 ha wetland + 98 ha wet meadow, wetland to catchment ratio 0.8

Catchment area: 267.5 km²

Volume: 584,290 m³

Hydraulic data: Monthly loading: 102,446 10⁻³ m³, Annual retention time: 2.1 days

Efficiency and effectiveness of facility:

Parameter	Inlet	Outlet	Retention	
	Kg yr ⁻¹	Kg yr ⁻¹	kg ha ⁻¹ yr ⁻¹	%
NO ₃ ⁻ - N	307,7	243,4	299	21
TN	365,8	309,7	261	15
PO ₄ ³⁻ - P	6,115	3,267	13.2	47
TP	12,38	10,17	10.3	18

ECOLOGICAL POTENTIAL

1. Biodiversity, nesting of native bird species and resting spot for migrating birds.
2. Ecosystem services by treating stream water before discharging to downstream ecosystems.



ADVANTAGES

1. Decreasing the nutrient content of the catchment water before entering Lake Brabrand and preventing nutrients to reach and discharge in Aarhus Fjord.
2. Supporting wildlife, native species, and resting migrating birds.
3. Minimizing and mitigating Flood Risk
4. Recreation facilities

DISADVANTAGES

1. Flooding of the surrounding meadows has resulted in periodically negative effect on the fauna.
2. High predation and low survival rates of the trout stock in the narrow passage between Aarslev Restored Wetland and Lake Brabrand.
3. Frequent algae blooms in the wetland due to the high nutrient concentrations. However, this was expected given the motivation of the project.
4. High area demand

Source : Carlos A. Arias



Funded by the Horizon 2020 Framework Programme of the European Union

This document was prepared as a part of NICE Project by the technical team from Gdansk University of Technology





RESTORATION OF NATURAL WETLAND

OBJECT INFORMATION

Name: Egaa Restored Wetland

Type of facility: Restoration of Natural Wetland

Treated medium: Surface Water and Rainwater

Description of the solution: : Egå Engsø was restored by re-flooding meadows on land previously drained in the 1950s for agricultural use. By the 1990s the water quality and natural ecosystem in and around the Egaa river, into which the site drained had declined in quality due to the effect of nitrate fertilizer and phosphorus through intensive farming in the area. In 2006 Aarhus Municipality, Aarhus County and the Danish Forest and Nature Agency decided to reestablished and construct a wetland and a lake as part of Action Plan for the Aquatic Environment II from 1998 to reduce this effect through biological denitrification. Another major reason for establishing the wetland and go ahead with the project, was the need for a strengthened defense and mitigate against the potential increasing rainfalls due to climate change.

BASIC INFORMATION

Construction year: 2006

Constructor: Aarhus County, Municipality of Aarhus

Source of financing: Municipality of Aarhus

Total cost: 418,575.95 €

Contact person: Carlos A. Arias
(carlos.arias@bio.au.dk)

AARHUS



GEOGRAPHICAL COORDINATES

Latitude: 56°13'17"N

Longitude: 10°13'54"E

LOCATION


Country: Denmark

City: Aarhus

Type of climate: Cfb /Dfb

Average temperature: 8.43°C

Sum of precipitation: 703mm



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆	☆☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+			+		

TECHNICAL DATA

Area of facility: 115 ha + 100 ha reed beds and meadows, mean depth of 1.00 m

Catchment area: 47 km², 46% agriculture

Volume: 894,630 m³

Hydraulic data: monthly loading depending on the precipitation in the catchment

Annual retention time: 160 days

Efficiency and effectiveness of facility: It is anticipated that the lake will contribute to a reduction in nitrogen emissions by approximately 33 t of N and 0.6 t of P annually. This reduction is estimated to represent 36% of the nitrogen discharge from Egå and nearly 6% of the TN discharge from Aarhus Municipality to the bay in 2006, which amounted to 556 t. However, a comprehensive assessment of the actual nitrogen retention within the wetland has not been conducted.

Operating experience: Bird management has been implemented to avoid invasive species nesting in the area.

ECOLOGICAL POTENTIAL

1. The wetland already holds several rare species, and some are even on the Danish Red List (IUCN Red List). The meadows surrounding Egå Wetland are grazed by cattle during the summer months, creating ideal conditions for the emerging flora and fauna associated with wet meadows. This trend is expected to continue as the wetland ages.
2. Ecosystem services by treating stream water before discharging to downstream ecosystems.



ADVANTAGES

1. Using existing ecotypes for treatment purposes.
2. Low maintenance cost.
3. Decreasing the nutrient content from the catchment water and discharge to the bay.
4. Supporting wildlife, native species, and resting birds. Bird species are returning to the area (e.g. sea eagles)
5. Minimizing flood risk.
6. Recreation facilities.

DISADVANTAGES

1. Flooding of properties located near the wetland has been observed at several heavy rain events. The restoration of an additional wetland, downstream of the current wetland, will enhance the storage effect and reduce the risks of flooding. The proposed infrastructure is being "considered to decrease flood risk during heavy rain events and climate adaptation.
2. The decline in the number of trout smolts within the streams of the area. The trout is dependent on the streams for reproduction and with the establishment of the wetland, this ecotype was fragmented leading to a decrease in the abundance by 83%.
3. High area demand.

Source: : Carlos A. Arias



Funded by the Horizon 2020 Framework Programme of the European Union

This document was prepared as a part of NICE Project by the technical team from Gdansk University of Technology



SEWAGE SLUDGE TREATMENT REED BED

OBJECT INFORMATION

Name: Sludge treatment reed bed in Gniewino
Type of facility: STRB
Treated medium: sewage sludge
Description of the solution: Total area of the STRB is 2400 m² and it consists of six beds planted with reed. The time required to feed sludge to one bed is about 1 day. The facility treated surplus sewage sludge from biological part of WWTP for 15000PE. About 35% of wastewater supplied to the WWTP comes from the dairy and food industry and 17% of wastewater is delivered from septic tanks.



GEOGRAPHICAL COORDINATES

Latitude: 54° 42' 17" N
Longitude: 17° 59' 7.8" W

LOCATION

Country: Poland
City: Gniewino
Type of climate: Cfb
Average temperature: 9 °C
Sum of precipitation: 500mm

BASIC INFORMATION

Construction year: 2011
Modernization: 2018
Constructor: WWTP in Gniewino Municipality
Source of financing: own funds with support of Provincial fund for environmental protection
Facility operator: WWTP in Gniewino
Total cost: approx. 140 000 €
Maintenance cost: 1 000-2 000 €
Contact person: Katarzyna Kołeczka (katkolec@pg.edu.pl) or Dariusz Rohde (dariusz.rohde@gpk-kostkowo.pl)



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆	☆☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
	+	+	+	+		

TECHNICAL DATA

Area of the facility: 6 reed beds about 2400m² in total

Hydraulic load: 70 kg of dry matter per 1m² of beds

Operating experience: Due to errors in the design, construction and initial operation stages, operational problems appeared. For this reason, the facility has been modernized. Currently it works properly.

ECOLOGICAL POTENTIAL


The STRBs treat sewage sludge using natural processes. They do not require additional chemicals and reduce energy consumption. This facility provides habitat for plants, insects and amphibians. The STRBs close the cycle of nutrients in the environment by converting waste into a product i.e. fertilizer, structure-forming materia.

ADVANTAGES

1. The method is predicted for long-term management of sludge.
2. This is a low-energy method.
3. Simple construction and operation process.
4. Final product for reuse as a compost or soil amendment.

DISADVANTAGES

1. Even minor errors during construction and initial operation can cause serious operational problems.
2. The STRBs require a much smaller load in the start up period than in the regular operation one.



Source: K.Kołecka



Funded by the Horizon 2020 Framework Programme of the European Union

This document was prepared as a part of NICE Project by the technical team from Gdansk University of Technology



SEWAGE SLUDGE TREATMENT REED BED

OBJECT INFORMATION

Name: Waagner Biro Gulf
Type of facility: STRB
Treated medium: sewage sludge
Description of the solution: An aim of the NBS is to convert of conventional septic tank with soak away at Dubai Municipality (60 staff members). Use of septic tank as pretreatment conversion of soak away to a pump station and pumping of outflow to a 170 m² vertical flow sand filter reed bed for biological and tertiary treatment of pre-treated wastewater. Analyses proved sufficient quality for drip irrigation. Facility is treated by optional additional UV treatment of stored effluent with UV lamp in stainless steel pipe.



GEOGRAPHICAL COORDINATES

Latitude: 25° 08' 00" N
Longitude: 55° 14' 30" E

BASIC INFORMATION

Construction year: 2005/2006
Constructor: Waagner Biro Gulf
Source of financing: local funding
Facility operator: Respective owner in cooperation with Waagner Biro Gulf
Total cost: 40 500€
Maintenance cost: 450 €
Contact person: Jana Schlick
(jana.schlick@planco.org)

LOCATION

Country: United Arab Emirates
City: Al Awir
Type of climate: BWh
Average temperature: 28.2°C
Sum of precipitation: 68mm



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆	☆☆☆	☆☆☆☆☆☆

UCC

1	2	3	4	5	6	7
	+	+	+	+		

TECHNICAL DATA

Area of the facility: 170 m²

Hydraulic load: 170 m³

Operating experience:

Daily tasks: Visual check of the system

Weekly tasks: Change of the distribution from one bed to another (opening and closing a valve); remove reed shoots from the service ways around the beds; visual check of the pump station.

Every three months: Discharge sludge from the pretreatment; flush distribution and drainage system, clean pump stations.

ECOLOGICAL POTENTIAL


Storage of sewage sludge in an elevated tank and a pond for reuse for concrete mixing, soil watering, car washing and a fish ponds. Moreover, it enables sub-surface irrigation of different plants including tomatoes, melons, cucumbers, date palms, flowers, bushes and grass areas. Analyses of the plants have complied with WHO standards.

ADVANTAGES

1. Simple to operate without chemical additives or complex electronic controls.
2. Effects could be seen within one year by saving fresh water and tanker disposal cost.

DISADVANTAGES

1. An importance of proper sizing and dimensioning for sludge material, i.e., mixture of water with solids, to prevent clogging.



Source: entsorgungsverband.de/uploads/media/Vortrag-bleif.pdf



Funded by the Horizon 2020 Framework Programme of the European Union

This document was prepared as a part of NICE Project by the technical team from Gdansk University of Technology



SLUDGE TREATMENT REED BED

OBJECT INFORMATION

Name: Sludge treatment reed bed in Helsingør

Type of facility: STRB

Treated medium: sewage sludge

Description of the solution: The surplus sludge from the activated sludge treatment systems to the left is pumped to fourteen reed beds in sequence. The water draining from the reed beds (reject water) is returned to the activated sludge tanks. When the beds are filled up with sludge after 8 to 12 years, the dewatered and partly mineralized sludge are used as a fertilizer in agriculture. The Helsingør system was established in 1996 with ten beds. The system was expanded with four extra beds in 2013.



GEOGRAPHICAL COORDINATES

Latitude: 54° 42' 17" N

Longitude: 17° 59' 7.8" W

LOCATION

Country: Denmark

City: Helsingør

Type of climate: Cfb

Average temperature: 9.1 °C

Sum of precipitation: 792 mm

BASIC INFORMATION

Construction year: 1996

Constructor: Orbicon company

Source of financing: local funds

Facility operator: Helsingør WWTP

Maintenance cost: about 10% of traditional methods of sludge treatment, cost of energy for pumps and control

Contact person: Katarzyna Kołeczka
(katkolec@pg.edu.pl)



Source: H. Brix "Sludge Dewatering and Mineralization in Sludge Treatment Reed Beds"

Source: globalwetttech.com/references/sludgedewatering/item/87-helsingor-sludge-treatment-reed-bed-system

Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆	☆☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
	+	+	+	+		

TECHNICAL DATA

Area of the facility: 10 reed beds about 10 500m²

Sludge volume: 7630 ton of dry matter per year

Efficiency and effectiveness: dewatering from 99% to about 25% dry matter content

Operating experience: Object has been working for a long time and serious problems with maintenance have not occurred.

ECOLOGICAL POTENTIAL


The STRBs treat sewage sludge using natural processes. They do not require additional chemicals and reduce energy consumption. This facility provides habitat for plants, insects and amphibians. The STRBs close the cycle of nutrients in the environment by converting waste into a product i.e. fertilizer, structure-forming materia.

ADVANTAGES

1. The method is predicted for long-term management of sludge.
2. This is a low-energy method.
3. Simple construction and operation process.

DISADVANTAGES

1. Even minor errors during construction and initial operation can cause serious operational problems.
2. Facilities require relatively large area.



Source: www.limnos.si



Funded by the Horizon 2020 Framework Programme of the European Union

This document was prepared as a part of NICE Project by the technical team from Gdansk University of Technology

SLUDGE TREATMENT REED BEDS & FRENCH TREATMENT WETLAND



OBJECT INFORMATION

Name: Nègrepelisse

Type of facility: STRB for septage treatment, French TW for leachate treatment and short rotation coppice for effluent reuse

Treated medium: Septage

Description of the solution: This treatment system was designed to (1) treat septage (131 tons of TSS/year - 11 000 m³/year) with sludge treatment beds, (2) treat leachates from sludge treatment beds with French VFTW and (3) reuse effluent by application on short rotation coppice in summer or (4) direct treated percolates to ponds in



GEOGRAPHICAL COORDINATES

Latitude: 44°04'22.1"N

Longitude: 1°29'34.6"E

BASIC INFORMATION

Construction year: 2012

Constructor: SAVEA

Designer: EcoBIRD

Source of financing: local funds

Total costs: 1 382 104 € / 2 371 719 € (incl. VAT)

Facility operator: local municipality

Maintenance cost: 27 816 € per year (incl. VAT)

Contact person: Stéphane Troesch (s.troesch@ecobird.fr)

LOCATION

Country: France

City: Nègrepelisse (district Occitanie)

Type of climate: Cfb

Average temperature: 13,4°C

Sum of precipitation: 644 mm



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆	☆☆☆	☆☆☆☆☆

TECHNICAL DATA

Area of facility: 2 700 m² in total

STRB: 2 600 m²; VFCW: 100 m²

Volume: 1 360 m³

SDRB: 1 300 m³; VFCW: 60 m³

TSS flux: 50 kg TSS/m²/y

Efficiency and effectiveness of facility:

guaranteed discharge levels: COD = 1000 mg/L

TSS = 1000 mg/L

Operating experience: simple maintenance and operation



UCC

1	2	3	4	5	6	7
	+	+	+	+		

ECOLOGICAL POTENTIAL

The treatment system provides ecosystem services such as waste decomposition and detoxification as well as supporting services as nutrient cycling, primary production habitat for insects and aesthetic value by being consistent with the surrounding landscape.



ADVANTAGES

1. Low cost and efficient dewatering process.
2. High load variation acceptance
3. Sludge highly stabilized for agricultural land spreading.
4. Treated effluent is reused for the irrigation of wood (short rotation coppice) that is used as fuel for the municipal social housing heating system.

DISADVANTAGES

1. Need for a substantial land area.
2. Operation and maintenance requirement (half full time job).

Source: S. Troesch



Funded by the Horizon 2020 Framework Programme of the European Union

This document was prepared as a part of NICE Project by the technical team from Gdansk University of Technology

FRENCH TREATMENT WETLAND & SLUDGE TREATMENT REED BEDS



OBJECT INFORMATION

Name: Paslières WWTP

Type of facility: French TW for domestic wastewater treatment and STRB for septage treatment

Treated medium: sewage (combined sewer) and septage

Description of the solution: This treatment system was designed to treat (1) the wastewater from 900 p.e. with French VFTW as well as (2) the septage from 900 septic tanks with sludge treatment beds. The leachate from STRB is treated on the TW.



BASIC INFORMATION

Construction year: 2016

Contstructor: SAVEA

Designer: EcoBIRD

Source of financing: local funds (Water agencies and Municipality)

Total cost: 790 334 € (incl. VAT)

Facility operator: Syndicat intercommunal Eau et Assainissement Rive Droite de la Dore
Maintenance cost: 6 840 € per year (incl. VAT)

Contact person: Stéphane Troesch
(s.troesch@ecobird.fr)

GEOGRAPHICAL COORDINATES

Latitude: 45°56'10.0"N

Longitude: 3°29'05.4"E

LOCATION

Country: France

City: Paslières
(district: Auvergne-Rhône-Alpes)

Type of climate: Cfb

Average temperature: 11,5°C

Sum of precipitation: 644 mm



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆	☆☆☆	☆☆☆☆☆

TECHNICAL DATA

Area of facility: 2 255 m² in total
VFCW (first stage): 1 085 m²; VFCW (second stage): 720 m²; STRB: 450 m²

Catchment area: 6 750 m²

Volume of filtration: 1 556 m³ in total
VFCW (first stage): 705 m³; VFCW (second stage): 648 m³; STRB: 203 m³

Water flow : Dry weather: 146 m³/d; Wet weather: 246 m³/d

Septage flow: 800 m³/year

Efficiency and effectiveness of facility:
guaranteed discharge levels and removal rates: BOD₅ = 20 mg/L – 85 %; COD = 90 mg/L – 75 %; TSS = 20 mg/L – 85 %; TKN = 15 mg/L – 70 %

Operating experience: simple maintenance and operation

UCC

1	2	3	4	5	6	7
	+	+	+	+		

ECOLOGICAL POTENTIAL

Facility provides water purification, nutrient cycling, habitat for insects and aesthetic value by being consistent with the surrounding landscape.



ADVANTAGES

1. This type of treatment system allows the application of raw wastewater directly without pretreatment.
2. Simple and highly efficient dewatering of sludge with SDRB.
3. Simple to operate.
4. No odour nuisance.

DISADVANTAGES

1. Availability of land area.

Source: S. Troesch



Funded by the Horizon 2020 Framework Programme of the European Union

This document was prepared as a part of NICE Project by the technical team from Gdansk University of Technology



LANDFILL LEACHATE TREATMENT WETLAND SYSTEM

OBJECT INFORMATION

Name: Burnie landfill leachate treatment wetland system
Type of facility: TW
Treated medium: landfill leachate
Description of the solution: Constructed on top of a recultivated landfill cell. The treatment process removes low level contaminants via a treatment train comprising a precipitation pond to remove metals, aerobic and anaerobic ponds for biological removal of ammonium nitrogen and nitrate by endemic plants, a polishing pond and final discharge to Cooee Creek via infiltration within a constructed wet eucalypt forest.



GEOGRAPHICAL COORDINATES

Latitude: 41° 6' 3" S
Longitude: 145° 51' 45" E

BASIC INFORMATION

Construction year: 2017
Constructor: SYRINX company
Source of financing: The Burnie Waste Management Centre (BWMC)
Total cost: 10 000 000 €
Maintenance cost: 10 000-20 000 € / year
Facility operator: SYRINX
Contact person: www.syrinx.net.au/contact

LOCATION

Country: Australia
City: Burnie
Type of climate: Cfb
Average temperature: 12.3 °C
Sum of precipitation: 910mm



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆	☆☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+	+	+		+	

TECHNICAL DATA

Area of the facility: 258 000 m²

Operating experience: The wetland system treats an average of 490 000 litres of landfill leachate per day. Flows have been successfully disconnected from the sewer network, reinstating environmental flows, freeing up TasWater network capacity and reducing ratepayer costs.

ECOLOGICAL POTENTIAL


The facility effectively cleans precipitation in the form of surface runoff. In addition, it accumulates heavy metal compounds and biogenic compounds that are harmful to soils and inland waters. The surroundings around the facility allows to spend quality free time and relax. In addition, it can be a learning experience on many plants that grow in Tasmania.

ADVANTAGES

1. Use of TW technology for treatment of leachate provided an effective and relatively low-cost solution that goes beyond simply addressing an issue.

DISADVANTAGES

1. Very stringent discharge standards set to protect the sensitive receiving creek system.



Source: synix.net.au/portfolio/burnie



Funded by the Horizon 2020 Framework Programme of the European Union

This document was prepared as a part of NICE Project by the technical team from Gdansk University of Technology



LANDFILL LEACHATE TREATMENT WETLAND SYSTEM

OBJECT INFORMATION

Name: TW pilot trial for copping landfill
Type of facility: TW
Treated medium: landfill leachate
Description of the solution: The Copping Pilot Trial Wetland is a TW and biofilter system designed to treat leachate from the Category B-Cells within the Copping Regional Landfill Facility. This system treats the leachate to a standard that enables sustainable, beneficial reuse for TW irrigation, using a modular, novel series of phytoremediation / adsorption biofilters and wetlands. The combined technologies use the processes of oxidation, precipitation, aeration, adsorption, biotransformation and phytoremediation to remediate the leachate.



COPPING

GEOGRAPHICAL COORDINATES

Latitude: 31° 56' 29" S
Longitude: 115° 57' 02" E

BASIC INFORMATION

Construction year: 2015-2020
Constructor: SYRINX company
Source of financing: project funding
Total cost: 12 000 000\$
Facility operator: Southern Waste Solutions, a joint authority made up of Clarence City, Sorell and Tasman Councils
Maintenance cost: 35 000 – 60 000 \$ /year
Contact person: Syrinx – Dr Kathy Meney (kmeney@syrix.net.au)

LOCATION

Country: Australia
City: Copping
Type of climate: Csa
Average temperature: 18.6 °C
Sum of precipitation: 766mm



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆	☆☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+	+	+		+	

TECHNICAL DATA

Area of the facility: 30 000 m²

Capacity: 4 000 m³ per year

(evaporation is the reason of describing capacity by perspective of time)

Dominant plant species: *Lemna spp*, *Duckweed*, *Schoenoplectus pungens*, *Eleocharis spp*, *Suaeda australis*, *Atriplex spp*, *Phragmites australis*.

Others important: Flows have been successfully disconnected from the sewer network, reinstating environmental flows, freeing up TasWater network capacity and reducing ratepayer costs.

ECOLOGICAL POTENTIAL

The facility performs many regulating services: it purifies wastewater, reduces the salinity of wastewater from the landfill, protects against flooding.


In addition, it is a place to relax. It is a symbol of a given region in the country and scientific research is carried out here.

ADVANTAGES

1. The system is closed with no discharge to the environment.
2. Low levels of odour from leachate, low levels of volatile compounds.

DISADVANTAGES

1. The facility generates noise due to the excavation proces and ongoing operation of pumps.
2. Sludge in the header tank and settlement tank to be disposed of in the landfill cells



Source: SYRINX



Funded by the Horizon 2020 Framework Programme of the European Union

This document was prepared as a part of NICE Project by the technical team from Gdansk University of Technology



LANDFILL LEACHATE TREATMENT WETLAND SYSTEM



OBJECT INFORMATION

Name: Tianjin Qiaoyuan Park: The Adaptation Palettes
Type of facility: TW
Treated medium: reject water from garbage dump and shooting range
Description of the solution: The site had previously been a military shooting range and then a garbage dump, surrounded by slums and highways. Polluted urban stormwater runoff drained to and ponded on the site, with drainage further complicated by several connections between surface and groundwater. The soil was heavily contaminated and quite saline and alkaline, making it a challenging environment for plants. The facility manages urban stormwater from offsite and reject water from garbage dump, improve the saline-alkali soil through natural processes, and allow rich patches of native vegetation to establish seasonally creating a unique, “messy” aesthetic experience.

LOCATION

Country: China
City: Tianjin
Type of climate: DWa
Average temperature: 13.3 °C
Sum of precipitation: 605mm



GEOGRAPHICAL COORDINATES

Latitude: 39° 07' 26" N
Longitude: 117° 15' 24" E

BASIC INFORMATION

Construction year: 2008
Constructor: Tianjin TEDA Eco-Landscape Development Co, Ltd
Source of financing: governmental
Total cost: 14 100 000\$
Facility operator: Environment Construction and Investment Co, Ltd ; Tianjin city
Maintenance cost: 50 000 – 70 000\$
Contact person: Kongjian Yu, (phone: +86-10-62745788)



BEFORE



AFTER

Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆	☆☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+	+	+		+	

TECHNICAL DATA

Area of the facility: 220 000 m²

Volume: around 6000 m³

Efficiency and effectiveness: Soil pH dropped from 7.7 and now fluctuates around 7.2, and water pH levels dropped from 7.4. to 7 or less.

Operating experience: When compared to the typical cost of weeding, pruning, irrigating, and fertilizing a traditional park, the low-maintenance “bubbles” (wet and dry ponds) save nearly 19,000\$ in maintenance costs each year.

ECOLOGICAL POTENTIAL

The natural resources contained in the facility are the source of ornaments and decorations. TW cleans the surface runoff water from the city, and the vegetation planted during the works purifies the air and increases the biodiversity of the area. It serves as a recreation destination for inhabitants.

ADVANTAGES

1. Sequesters an estimated 539 tons of carbon in the trees and plants on the site, a service valued at approximately 7200\$.

DISADVANTAGES

1. Deep basins, some of them even up to 5 m deep, pose a risk of drowning for children.



Source:
landscapeperformance.org/case-study-briefs/tianjin-qiaoyuan-park-the-adaptation-palettes



Funded by the Horizon 2020 Framework Programme of the European Union

This document was prepared as a part of NICE Project by the technical team from Gdansk University of Technology





POST-INDUSTRIAL LEACHATE TREATMENT WETLAND SYSTEM

OBJECT INFORMATION

Name: Sydney Olympic Millennium Parklands
Type of facility: TW
Treated medium: post-industrial leachate
Description of the solution: The facility covers an area slightly larger than 4km² that was once home to various industrial uses and was contaminated with commercial and industrial waste. The site has set world standards for the innovative techniques devised to deal with massive quantities of both contaminated material and clean fill on site, integrate highly technical water recycling systems, and create an environment in which native plants can thrive. The resulting parklands, which were designed to be self-sustaining, reconnect residents of Sydney's western suburbs to its major waterway and provide recreational and educational opportunities for 2.5 million visitors annually.



GEOGRAPHICAL COORDINATES

Latitude: 33° 50' 22" S
Longitude: 151° 03' 57" E

BASIC INFORMATION

Construction year: 2000
Constructor: OCA Olympic Coordination Authority
Source of financing: governmental funding
Total cost: 50 000 000 €
Maintenance cost: 75 000-100 000 €
Facility operator: OCA
Contact person: GIPA
(ethics@dpie.nsw.gov.au)

LOCATION

Country: Australia
City: Sydney
Type of climate: Cfa
Average temperature: 18.0 °C
Sum of precipitation: 912mm

BEFORE



AFTER



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆	☆☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+	+	+		+	

TECHNICAL DATA

Area of the facility: 4 km²

Efficiency and effectiveness: Treats contaminated soils. Roughly 35 000m³ of leachate have been collected and transferred to a waste treatment facility. Groundwater contaminated with 750 kg of hydrocarbons, including 430 kg of benzene, has been successfully degraded .

Recycled over 4 600m³ of water over 7 years, for irrigation. Of total water consumption during this period, only 2% was sourced from Sydney's water supply despite one of the worst droughts in Australia's history.

ECOLOGICAL POTENTIAL

The site allows for the capture and treatment of surface runoff water that comes from the city, as well as the purification and use of surface water for plants irrigation in the park.

The park is home to many native species of animals and birds, whose numbers are constantly monitored. In addition, this facility is a meeting place for residents and a destination for tourists.

ADVANTAGES

1. Effective solution to the problem of the globe and groundwater containing hydrocarbons.

DISADVANTAGES

1. The constant need to monitor the hydrological situation, including the occurrence of flooding, as well as chemical and biological monitoring.



Source: landscapeperformance.org/case-study-briefs/sydney-olympic-millennium-parklands



Funded by the Horizon 2020 Framework Programme of the European Union

This document was prepared as a part of NICE Project by the technical team from Gdansk University of Technology





POST-INDUSTRIAL LEACHATE TREATMENT WETLAND SYSTEM

OBJECT INFORMATION

Name: Tangshan Nanhu Eco-city Central Park
Type of facility: TW
Treated medium: post-industrial lechate
Description of the solution: The facility is a mine reclamation project, the former 6.3km² post-industrial area is now a dynamic public space, featuring recreational facilities, conservation areas. The former coal mining site was heavily polluted and damaged after a massive 1976 earthquake. The site became a safety hazard and was used largely as a city landfill and a sewage lagoon. In 2008, the reclamation project began. Using sustainable practices such as material reuse, stormwater management, and wildlife habitat restoration, the project has fundamentally improved the environmental quality of Tangshan City and created a major new public recreational space, accessible to more than 10,000 residents within a 15 minute walk.



GEOGRAPHICAL COORDINATES

Latitude: 39° 35' 04" N
Longitude: 118° 07' 54" E

BASIC INFORMATION

Construction year: 2009
Constructor: Tangshan Nanhu Eco-city Management Committee
Source of financing: governmental
Total cost: 68 000 000\$
Facility operator: Tangshan Urban and Rural Planning Bureau
Annual maintenance: 15 000 - 20 000\$
Contact person: Ming-Han Li
(minghan@msu.edu)

LOCATION

Country: China
City: Lunan Tangshan
Type of climate: DWa
Average temperature: 12.7 °C
Sum of precipitation: 566mm



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
☆	☆☆☆☆	☆☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+	+	+		+	

TECHNICAL DATA

Area of the facility: 6,3 km²

Catchment: 30 km³

Efficiency and effectiveness:

Sequesters an estimated 2 828 tons of CO₂ annually in the trees of the park. Reduces potable water consumption by 29 200 000 m³ annually by importing reclaimed water from a nearby sewage treatment plant. The reclaimed water is further treated in a series of CWs and used for water body recharge and irrigation in the park, saving about \$15.4 million per year.

ECOLOGICAL POTENTIAL

The area where the NBS is located, is home to many animal species. Nearby wetlands treat post-mining leachate, which after treatment is used to irrigate the entire park. Altitude, wetlands and trees capture a huge amount of CO₂. It is a popular place for residents who spend their free time and relax.

ADVANTAGES

1. Saved \$47.2 million in material costs by reusing 6 000 000 m³ of coal ash to produce foundations and bricks used in park construction.

DISADVANTAGES

1. The facility does not have biochemical monitoring. No analysis of the properties of the physicochemical medium. Danger to visitors.



Source: landscapeperformance.org/case-study-briefs/tangshan-nanhu-eco-city-central-park



Funded by the Horizon 2020 Framework Programme of the European Union

This document was prepared as a part of NICE Project by the technical team from Gdansk University of Technology



FRENCH VERTICAL-FLOW TREATMENT WETLANDS FOR COMBINED SEWER OVERFLOW



OBJECT INFORMATION

Name: French vertical-flow treatment wetland in France

Type of facility: SSVFTW

Treated medium: surface runoff and WW in CSO

Description of the solution: The Challex WWTP, which is situated in the Rhône Alpes region of France, alongside the Rhône river, was commissioned in April 2010. The WWTP is composed of two VFTW. The first stage is composed of three parallel cells (861m² each) and receives raw wastewater (sludge and wastewater treatment) while the second stage is composed of two parallel cells (712.5m² each). All filters are 0.8 m deep.



GEOGRAPHICAL COORDINATES

Latitude: 46° 10' 31" N

Longitude: 5° 59' 02" E

BASIC INFORMATION

Construction year: 2010

Constructor: SCRIBE

Source of financing: no data available

Total cost: 1 847 000 €

Facility operator: no data available

Maintenance cost: 12 000 € / year

Contact person: Pascal Molle
(pascal.molle@inrae.fr)

LOCATION

Country: France

City: Challex

Type of climate: Cfb

Average temperature: 9.7°C

Sum of precipitation: 1584mm



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
-	☆☆☆☆	☆☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+		+			

TECHNICAL DATA

Area of the facility: 4000m²

1st stage - 2580m² 2nd stage - 1420m²

Volume: 3 200 m³

Primary design factors: 2000 PE

Catchment: 60 hectare

Efficiency and effectiveness: maximal 24h mean concentration for dry weather period: BOD₅= 25 mg/L; COD=90 mg/L; SS=35 mg/L; TKN=20 mg/L.

Operating experience: Batches are delivered at a flow rate of about 0.38 m³/h and 0.29 m³/h per m² to the first and second stage, respectively. Flow rate and batch volume are lower than the French guidelines (Molle et al. 2005a) which do not ensure good water distribution onto the filter surface (the system requires 20 to 50 mm of water at a minimal flow rate of 0.5 m³/h per m²).

ECOLOGICAL POTENTIAL


The content of water and plants has a positive effect impact on the microclimate. The CW system is also visually appealing. The plant also became part of the walkway of Challex residents.

ADVANTAGES

1. The facility is designed to avoid untreated overflow during rain events.

DISADVANTAGES

1. Requires regular maintenance such as plant harvest.



Source: J. Bertrand-Krajewski et al. "Vertical-flow constructed wetlands for the treatment of wastewater and stormwater from combined sewer systems"



Funded by the Horizon 2020 Framework Programme of the European Union

This document was prepared as a part of NICE Project by the technical team from Gdansk University of Technology



MULTISTAGE TREATMENT FOR COMBINED SEWER OVERFLOW

OBJECT INFORMATION

Name: CSO-TWs in Gorla Maggiore
Type of facility: constructed wetland
Treated medium: surface runoff and WW in CSO
Description of the solution: The treatment system consists of a subsurface VFTW followed by a FWS TW for polishing. Additionally, the use of green infrastructure allowed the abandoned poplar site to be converted into a park near the Olona River. Finally, the FWS-TW was designed also to work as a detention basin for flood mitigation and to increase biodiversity in the area.

BASIC INFORMATION

Construction year: 2014
Constructor: IRIDRA company
Source of financing: local funds- Lombardy Region
Total cost: 820 510 €
Facility operator: Gorla Maggiore Municipality
Maintenance cost: 3500 € / year
Contact person: Anacleto Rizzo (rizzo@iridra.com)



GORLA MAGGIORE

GEOGRAPHICAL COORDINATES

Latitude: 45° 39' 53.9" N
Longitude: 8° 53' 09.7" E

LOCATION

Country: Italy
City: Gorla Maggiore, Lombardy
Type of climate: Cfa
Average temperature: 12.5 °C
Sum of precipitation: 1467 mm



Source: A. Rizzo „ Treatment wetland combined sewer overflow at Gorla Maggiore water park, Italy”

Ecosystem services

Provisioning	Regulating	Cultural	Supporting
-	☆☆☆☆	☆☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+		+			

TECHNICAL DATA

Area of the facility:

First stage VF - 3840m²

Second stage FWS - up to 7200m²

Total - around 11 000m²

Volume: 7 700m³

Efficiency and effectiveness: Showed overall measured mean removal efficiencies of 87% and 93% for COD and NH₄⁺, respectively.

ECOLOGICAL POTENTIAL


The FWS-TW stage was designed to support biodiversity. The presence of a surface water body resulted in a clear advantage in terms of biodiversity for the NBS, which received a score for support of wildlife of approximately 85%. It is a place of recreation for nearby citizens.

ADVANTAGES

- 1.NBSs allow the on-site treatment of CSO since traditional solutions are not suitable for this aim.
- 2.Approval of the people in the community, who use the new Water Park without any complaints.

DISADVANTAGES

- 1.FWS-TW only fed by CSO can face prolonged dry periods due to stochastic rainfall patterns. Therefore mosquito and odour issues may arise in the summer months.



Source: A. Rizzo „ Treatment wetland combined sewer overflow at Gorla Maggiore water park, Italy”



Funded by the Horizon 2020 Framework
Programme of the European Union

This document was prepared as a part of
NICE Project by the technical team from
Gdansk University of Technology

MULTISTAGE TREATMENT FOR COMBINED SEWER OVERFLOW



OBJECT INFORMATION

Name: CW system of Carimate WWTP in Italy

Type of facility: constructed wetlands

Treated medium: surface runoff and WW in CSO

Description of the solution: The centralised WWTP of Carimate treats the wastewater from the CSO serving 11 towns in Como province (70,040 inhabitants). The CSO-CW is a 2 stage system.

- The 1st stage comprises two VF CW beds, each one further divided into 2 separated hydraulic sectors for a total area of 8500m².
- The 2nd stage is a free water surface (FWS) CW of 4500 m². The system is fed by a pumping system and automatically regulated by a PLC to properly treat the first more polluted fraction of the CSO events.

LOCATION

Country: Italy

City: Carimate

Type of climate: Cfa

Average temperature: 12.7°C

Sum of precipitation: 1467mm



GEOGRAPHICAL COORDINATES

Latitude: 45° 41' 27.51" N

Longitude: 9° 7' 10.2" E

BASIC INFORMATION

Construction year: 2018

Constructor: Sud Seveso Servizi spa

Source of financing: no data available

Total cost: 1 300 000 €

Facility operator: Sud Seveso Servizi spa

Maintenance cost: waste disposal for VF 8500m² = 500 € / year

Contact person: Anacleto Rizzo
(rizzo@iridra.com)



Ecosystem services

Provisioning	Regulating	Cultural	Supporting
-	☆☆☆☆	☆☆☆	☆☆☆☆☆

UCC

1	2	3	4	5	6	7
+	+		+			

TECHNICAL DATA

Area of the facility:

VF – 8500m²

FWS - 4500m²

Volume:

VF – 7650m³

FWS - variable water depth around 3500m³

Hydraulic and hydrological data:

Hydraulic load 1300 m³/h. Load of pollutants- 700 m³/h (104tCOD/year; contained in about 890.000m³/year)

ECOLOGICAL POTENTIAL

The maximum exploitation of CW ecosystem services is planned thanks to the FWS stage, which also aims to increase biodiversity and to recreate an area suitable for environmental educational activities. The riparian area along the left side of the Seveso river is planned to be involved in river restoration activities, with plantation of vegetation more suitable for riparian environments.


ADVANTAGES

1. In situ treatment of CSO, intercepting high pollutant loads.
2. The facility reduces diluted wastewater conveyed to centralized WWTPs.

DISADVANTAGES

1. The design of CW for CSO upstream WWTP requires profound care.

Design: CW configuration



Source: F. Massi et al. „Treatment of combined sewer overflow upstream centralized treatment plants with nature-based solutions: the constructed wetland system of Carimate WWTP”



Funded by the Horizon 2020 Framework Programme of the European Union

This document was prepared as a part of NICE Project by the technical team from Gdansk University of Technology

TREATMENT WETLAND FOR COMBINED SEWER OVERFLOW



OBJECT INFORMATION

Name: Retentionsbodenfilter Kenten CSO

Treatment Wetland in Germany

Type of facility: TW

Treated medium: surface runoff and WW in CSO

Description of the solution: The TW is situated after two retention tanks and is only charged when the overflow from the sewer network exceeds their capacity. The filter has a surface of 2,200 m² and is designed to treat up to 4,200 m³ with a filtration velocity of 0.025 L/s/m². The minimum interval between two events is 36 hours. Located on the suburbs of the city, the facility treats the volume of water runoff from the fields of the Erft river basin. The presented wetland is one of the 36 objects that purify the surface runoff entering the Erft watercourse and is an important part of the hydrotechnical infrastructure in the area.

LOCATION

Country: Germany

City: Bergheim

Type of climate: Cfb

Average temperature: 10.7 °C

Sum of precipitation: 989 mm

BERGHEIM



GEOGRAPHICAL COORDINATES

Latitude: 50° 51' 37" N

Longitude: 6° 44' 11" E

BASIC INFORMATION

Construction year: 2006

Constructor: Erft Verband

Source of financing: governmental

Total cost: 820 510 €

Facility operator: IMT Atlantique

Maintenance cost: 8 000-10 000 €/year

Contact person: Katharina Tondera

(info@katharina-tondera.de)



Source: Pinnekamp, J. „Betriebsoptimierung von Retentionsbodenfiltern im Mischsystem.“



Source: A.I. „The role of constructed wetlands as green infrastructure for sustainable urban water management“

Ecosystem services

Provisioning	Regulating	Cultural	Supporting
-	☆☆☆☆	☆☆☆	☆☆☆☆☆

TECHNICAL DATA

Area of the facility: 2200 m²

Volume: 4200 m³

Dominant plant species: *Phragmites Australis*

Primary design factor:

- approximately inflow 1000 m³/hour of CSO;
- minimum interval between two events is 36 hours
- filtration velocity of 0.027 L/s/m²

UCC

1	2	3	4	5	6	7
+	+		+			

ECOLOGICAL POTENTIAL

Wastes from the facility are used to grow plants. Moreover, the planted species of reeds develop the biodiversity. The facility improves the microclimate of the environment and captures biogenic and carbon compounds.

ADVANTAGES

1. This technology is currently the only one available to provide biological, biochemical and mechanical treatment of combined sewer overflows.
2. Retention of TSS (90%), COD (60–85%), nitrification of ammonium (60%) and indicator bacteria (1–3 log₁₀) have been very well documented.

DISADVANTAGES

1. Risk of clogging in the hydraulic system of the running pump.
2. Difficulties to measure the physicochemical properties of the water infiltrate in the surface of the object due to the effect of the periodic drought.



Source: Pinnekamp, J.
„Betriebsoptimierung von
Retentionbodenfiltern im Mischsystem.



Funded by the Horizon 2020 Framework
Programme of the European Union

This document was prepared as a part of
NICE Project by the technical team from
Gdansk University of Technology

Contact:



MAGDALENA GAJEWSKA

TEAM LEADER

mgaj@pg.edu.pl



KATARZYNA KOŁECKA

TEAM MEMBER

katkolec@pg.edu.pl



KAROLINA FITOBÓR

TEAM MEMBER

karfitob@pg.edu.pl



MAGDA KASPRZYK

TEAM MEMBER

magkaspr@pg.edu.pl



ALICJA KUPCZYK

TEAM MEMBER

alikuspcz@pg.edu.pl